A Database Publication

ATARI USER

Vol. 4 No. 1 May 1988 £1 25

WIN the sensational ATARI GAMES SYSTEM + lots of other prizes in our BIRTHDAY CONTEST

How to find your way around The Eidolon

REVIEWS: Thundercats, Zynaps, Olympiad '88, Super Soccer

LISTING: Explore the unknown in Mine Runner

LISTING: Clever classic cavity toolbox

FREE
when you subscribe
to Atari User

Starquake



In this delightful game you control BLOB, the Biologically-Operated Being, navigating him through 500 action packed screens to rebuild the unstable planet's core

Bubble Bus Starquake is one of the biggest-selling games for home micros, due to its incredibly addictive gameplay and cleverly-animated graphics It has received such accolades as Game of the Month in *Computer and Video Games*, and was awarded a *Crash Smash*.

● *What reviewer Bob Chappell said about the Atari version*

'Starquake is top-notch fare quality dripping from every byte'

Don't miss out on this tremendous offer – fill in the coupon on Page 61 without delay

Suitable for	Product	Format	RRP	Special reader offer	YOU SAVE	Offer including subscription
Atari 8 bit (48k minimum)	Starquake	Tape	£9.95	£4.95	£4	FREE
		Disc	£12.95	£6.95	£6	FREE

N.B. Current subscribers can re-subscribe early to take advantage of this very special opportunity

Contents



Vol 4 No 1 May 1988

MANAGING EDITOR
Derek Meakin

GROUP EDITOR
Alan McLachlan

FEATURES EDITOR
Ken Hughes

PRODUCTION EDITOR
Peter Glover

EDITORIAL ASSISTANT
Neil Fawcett

NEWS EDITOR
Mike Cowley

REVIEWS COORDINATOR
Pam Turnbull

TECHNICAL EDITOR
Andre Willey

ADVERTISEMENT MANAGER
John Snowdon

ADVERTISING SALES
Nora Lawton

Tel 0625 878888 (All depts)
0625 879940 (Subscriptions)

Telex 26571 MONREF G
Quoting Ref 72 MAG001

Telecom Gold 72 MAG001

Prestel Mailbox 614568383

Fax 0625 879966

Published by
Database Publications Ltd
Europa House Adlington Park
Adlington Macclesfield SK10 4NP

ABC 33 573 January-June 1987

Subscription rates for
12 issues post free

£15 – UK
£18 – Europe (Incl Eire)
£33 Overseas (Airmail)

ISSN 0269 845X

Atari User welcomes program listings and articles for publication. Material should be typed or computer printed and preferably double spaced. Program listings should be accompanied by cassette tape or disc. Please enclose stamped self addressed envelope otherwise the return of material cannot be guaranteed. Contributions accepted for publication by Database Publications Ltd will be on all rights basis.

© 1988 Database Publications Ltd. No material may be reproduced in whole or in part without written permission. While every care is taken, the publishers cannot be held legally responsible for any errors in articles, listings or advertisements.

Atari User is an independent publication and Atari Corp (UK) Ltd are not responsible for any of the articles they contain or for any of the opinions expressed.

News trade distribution: European Sales and Distribution Limited, Unit 1, Burgess Road, Ivyhouse Lane, Hastings, East Sussex TN35 4NR. Tel: 0424 430422

News **5**
All the latest from the ever changing world of the 8 bit Atari

Basic Revealed **9**
View a program's token tables with our easy-to-use program

MicroLink News **13**
More information on Britain's online database for micros

Biorhythm **15**
At a low ebb? Check your ups and downs with this super routine

Jigsaw **19**
Pick up the pieces with this colourful and entertaining routine

Programmer's Challenge **21**
We give you the program to solve the problem we set you

Cassette Verify **22**
Having tape saving problems? Here's a utility to solve them

Reviews **25**
We look at Zybex, Thunderfox, Winter Olympiad and more

Map **32**
Plan your route through the subterranean caverns of The Eidolon

Hints and Tips **34**
Help for gamesters continues with The Eidolon and Spy Hunter

Rouloc **35**
Our resident adventurer has some hints for The Dungeon

Birthday Bonanza **37**
Atari XE Games system and £500 worth of software to be won

Mine Runner **39**
It's a dodgy business with our tricky golden game of the month

Software Solutions **45**
Your programming problems solved by our technical wizard

Five Liners **48**
Another set of prize-winning mini programs from our readers

Easy Programming **50**
We look further into simple animation techniques using Atari Basic

Mailbag **55**
Your chance to get your news, views, moans and name in print

Winter Olympiad **59**
We look at the company behind this super sports simulation



All major listings in this issue are accompanied by checksums to help overcome typing mistakes. For full details of how they work, see the article on page 23 of the November 1987 issue of *Atari User*

Link your Atari to the outside world with...

MicroLink

Electronic mail – The cheapest and fastest form of communication possible. It costs the same to send a message to one mailbox as to 500!

Telex – Link up with 36 000 telex subscribers in the UK and 1.5 million worldwide. You can even send and receive telexes after office hours or while travelling.

Telemessages – Type in your message before 8pm and delivery is guaranteed by first post the next day (except Sunday) anywhere in the UK and USA.

Tele booking – Reserve train and theatre tickets, check flight details worldwide or order from a vast range of products – from flowers to floppy discs.

Telesoftware – Download directly into your Atari any program from the ever growing library now available on MicroLink – both games and utilities.

Company searches – Obtain facts about any British limited company in seconds, and fully analysed financial information on over 100,000 major companies.

Translation – Access the biggest and most up to-date multi lingual dictionary in the world, with over 380,000 words.

News – Use the powerful search commands to pinpoint vital business information from the world's leading news services, newspapers and periodicals.

Radiopaging – If you also have a pocket radiopager you'll be alerted each time an urgent message arrives in your mailbox. So you're always in touch.

Gateways – Get through to New York in just five seconds – or key into the EEC computer in Luxembourg, which links you to 600 databases throughout Europe.

When you join MicroLink you've got the world of communications at your fingertips – 24 hours a day. You'll have immediate access to ALL the facilities offered by Telecom Gold ... and a great deal more besides.



Two recommended packages

If you have an 850 interface
Pace Nightingale manual modem + cable (£116.15) PLUS Mini Office II (£19.95)
Total price £136.10

If you don't have an interface
Miracle WS2000 V21 V23 modem + Datatari interface + cable + Datatari software
Total price £148.95

With either combination you can also log on to other databases and bulletin boards all round the world.

All you need – apart from your Atari – is a modem, which plugs into your telephone wall socket, plus suitable communications software.

We have provided two possible options on the left.

Whichever equipment you use, you will be able to call MicroLink, open your mailbox, save to disc any messages waiting for you, and disconnect in as little as two minutes.



More than 90 per cent of subscribers can connect to the MicroLink computer at local call rates

TO FIND OUT MORE
Fill in the coupon and send it to the address below. You will receive full details of services and costs, together with an application form. Complete this and within days you and your Atari will be able to use all the services of MicroLink and Telecom Gold.

Please send me full details about MicroLink and information sheets about the following hardware and software options (please tick)
☐ Pace package ☐ Miracle package

Name_____

Address_____

_____

Postcode_____

Send to MicroLink, Europa House, Adlington Park, Adlington, Macclesfield SK10 4NP

ATUS

Cashing in on price rises

THE Atari 8 bit could be heading for a boom – courtesy of price increases which have hit the ST range

While Atari has consistently cut production costs and pared its own margins it has now announced that it can no longer absorb the financial difficulties caused by the world shortage of memory chips

The shortage stems from Japanese restrictions on chip production – prompted by trade disputes with the States.

And particularly affected are dynamic random access memories (drams) which are at the core of more powerful computers – and for users this translates as the higher the power, the higher the price

In turn, this means that the 520 and 1040 STs have been hiked by a hefty £100 each Trade sources are positive this will boost 8 bit sales

'We expect the recent price increase on the ST to make the Atari games machines a more attractive proposition", one leading dealer told *Atari User*

'After all, you can now buy a complete Atari games system for little more than the amount of the price increase"

Atari has been trying for some months to buy out a chip manufacturing company 'so that we are not subject to the whims of third party suppliers" according to one company spokesman

And should the venture prove successful, prices could again fall

But in the interim, the 8 bit market seems set for a resurgence

Gadgets Goulding 'joins up'

REGULAR contributor Len Golding has landed a plum job – thanks to his articles in *Atari User*

Len, who has been writing for the magazine since its early days is perhaps best known for his gadgets series

And it was this that caught the eye of Earl Morse, who is the science coordinator for American forces in Germany and provides materials for USAF schools throughout Europe

The 147 schools with thousands of pupils of all ages, all have computers installed – 2,000 of them

Earl was so impressed by Len's articles that he's signed him up for a contract to assist school teachers with science related projects in the classroom

Regular readers need not worry however Len will still be contributing to *Atari User* and has a host of gadgets in the pipeline



Joystick is going a bomb...

WHEN is a joystick not a joy stick? When it's a hand grenade of course And that's the problem with Robtek's latest offering for the Atari 8 bit market

The unusual design of its Terminator joystick has already caused security officers at Heathrow airport to refuse to let the device on board an aircraft

"The trouble is that the Terminator is too realistic", said a spokesman for Robtek (01-947 4457)

"Airport authorities at Heathrow called us and asked if we would warn our customers not to try and take the grenade-shaped device on board planes as hand luggage

'Rightly they are concerned about the possibilities of someone removing the cables from the joystick and threatening the flight crew with what looks for all the world like a real hand grenade'

Robtek is now enclosing a leaflet with all new deliveries of the Terminator joystick warning customers not to try to take it on board as hand luggage

Price £19 95

Silica backing for 8 bit Ataris

A MASSIVE commitment to the 8 bit games market has been made by Silica Shop with the purchase of 50,000 roms

"Our reputation was built on the Atari 8 bit and we have no plans of dropping it in favour of the ST" said John Hambly, Silica's buying controller

"We have a warehouse full of software for the machine with a tremendous selection of both old and new titles", he said

The announcement from Silica comes as Atari is trying to set up a dealer network of 20 shops to promote greater support for the 8 bit market

Plans to introduce new software display shelving in selected dealers stores are at an early stage but some retailers are treating the new initiative with a little scepticism

Harry Nadler of Red Rat Software said "It is a great idea If it works Had this happened about two years ago then the Atari 8 bit computer may have had a higher profile In the market place than it has today"

Conversion

AFTER a successful debut on the Commodore 64 and Spectrum, Nebulus – from Hewson (0235 832939) – is being converted for the Atari 8 bit

'Originality pays handsome dividends", said managing director Andrew Hewson "We've had a number of approaches for the various conversion rights"

X marks comms blackspot

COMMUNICATIONS problems caused by British Telecom's new System X appear to be on the increase.

Difficulties arise when the new digital system is connected to the older analogue exchanges. To make the two compatible BT has had to attenuate the signal.

One outcome of the drop in level is that modems have difficulty in maintaining the line once logged on.

Rob Flemming of Pace Micro Technology said: "We have had a number of complaints from Atari users who are using our Nightingale modem. After a good deal of research, as well as a large number of expensive phone calls, BT admitted to causing the fault."

According to Flemming, communication difficulties appear to get worse when dialling from one System X exchange to another.

"Not only are outgoing lines attenuated but incoming lines as well. Between two new exchanges the loss in signal level is dramatic", he said.

A spokesman for British Telecom told *Atari User*: "We are aware of the difficulties being caused by our modernisation programme. Once System X is in use nationwide it will actually improve data transmission and reception.

To overcome the immediate problems, Atari users in a System X exchange can request British Telecom to unattenuate the line."

Loading chart leader

THE latest budget title from Atlantis – League Challenge – roared straight to the top of the Gallup Chart. However, as several readers have pointed out, the loading instructions on the inlay card are incorrect – instead of holding down the Start and Option keys, it's only necessary to hold down the Start key.

Drive delay rapped

ATARI UK is letting the side down, according to Karen Sutherland, manageress of computer dealer Atari World in Manchester.

The attack comes after repeated enquiries to Atari about the availability of disc drives for its 8 bit games machines.

For despite Atari's announcement of its XF551 drive last summer, supplies still haven't reached the shops.

"I am furious about the situation", said Karen. "If a disc drive was readily available I could sell at least 30 to 40 a week. Every time I contact the people at Atari to find out when supplies will be available they just say they are waiting for a boat load to arrive from Singapore. It must be a very slow boat."

One outcome of the shortage is that the older 1050 drive is maintaining a high second-hand value with prices in the region of £95.

An Atari spokesman said: "We are still waiting for the disc operating system to be finished which it should be in the next couple of weeks."

THE GALLUP CHART TOP 20 ATARI SOFTWARE

THIS MONTH	LAST MONTH	TITLE (Software House)	PRICE
1	1	SPEED ACE *Zeppelin*	2.99
2	•	ROCKFORD *Mastertronic*	2.99
3	•	STEVE DAVIS SNOOKER *Blue Ribbon*	1.99
4	1	SPACE SHUTTLE *Firebird*	1.99
5	1	POLE POSITION *Atari*	12.99
6	16	MILK RACE *Mastertronic*	2.99
7	•	FOOTBALL MANAGER *Addictive*	2.99
8	•	SPOOKY CASTLE *Atlantis*	1.99
9	10	PLATFORM PERFECTION *US Gold*	9.95
10	•	NINJA MASTER *Firebird*	1.99
11	1	LEAGUE CHALLENGE *Atlantis*	1.99
12	•	GAUNTLET *US Gold*	9.95
13	1	PANTHER *Mastertronic*	1.99
14	1	FEUD *Mastertronic*	1.99
15	1	HENRY'S HOUSE *Mastertronic*	1.99
16	1	GHOSTBUSTERS *Mastertronic*	1.99
17	•	WINTER OLYMPIAD *Tynesoft*	9.95
18	•	FREEWAY *Activision*	9.95
19	•	ACE OF ACES *US Gold*	9.99
20	1	180 *Mastertronic*	2.99


Compiled by Gallup/Microscope

There are nine new entries this month, including a few old games making their appearance in the chart. The first game from Zeppelin goes to number one, followed by the entry of two old favourites in second and third positions.

NEW LOW PRICE ST!

ST PRICE INCREASE

Due to a worldwide shortage of memory chips prices of many computers have gone up. From April 1988 the Atari ST range is also likely to be affected. For details of any price increase please return the coupon below for our latest literature.



ONLY FROM SILICA

Firstly there's a personal computer the size and price you'd expect to pay for computers. But it's not the one you can buy from other computers have chosen. After carefully considering the options, Silica Shop are pleased to announce the ST as part of personal purchasing service from Atari. The ST was designed using the revolutionary 68000 microprocessor technology and is already firmly established as the choice of many leading British users in various business, educational and scientific applications. With a unique specification including 512K RAM memory, high resolution graphics, built-in MIDI interface and GEM operating system, the ST is firmly established as one of the most powerful personal computers currently available. And now you can buy the Atari ST direct from Silica Shop and benefit from the unique combination of after sales service, expertise and competitive prices that have made Silica Shop the UK's No.1 Atari specialist. With a proven track record in professional computer sales, Silica Shop are dedicated to providing you with the complete support service that you will need, now and in the future. Call us today and see why over 15,000 customers have relied on us for their Atari requirements.

FREE STARTER KIT *Only From Silica*

When you purchase any Atari ST computer you will not only receive the most suitable computer at the cheapest price, but you will also receive the following from Atari Corporation as part of the package.

1st Word™ Word Processor ST Basic Language Disk ST Tutorial Manual ST Owners Manual Plus Much More!

If you buy your ST from Silica Shop you will also receive:

Multi-tasking Software Business Software 1st Word™ Word Processor

In addition, we will provide what we consider to be a flying start with your new computer as we have also supported a special ST STARTER KIT worth over £100 which we are giving away FREE OF CHARGE with every ST computer purchased at our Sidcup retail branch. This kit is available ONLY FROM SILICA and is aimed at providing users with a thorough introduction to the world of computing. We are continually researching the ST scene, with exclusive public domain and other material becoming available and to include a magazine pack recommended or endorsed by ST computing. Return the coupon below for full details.

DEDICATED SERVICING *Only From Silica*

At Silica Shop, we have a dedicated service department of highly skilled technicians with many years experience in the industry. Due to the complexity of the ST range, our technicians undergo additional training on the new machines to ensure that they are fully conversant with the latest developments. Our workshop is geared to handle all Atari computer products. They are equipped with the latest diagnostic equipment and have direct access to spare parts from Atari. So if your machine ever needs attention, you can be confident that it will be serviced by the experts. Unlike dealers who may only employ part time staff, you can be sure that our technicians are always available to help you. Call us today and see why over 15,000 customers have relied on us for their Atari requirements.

1MB RAM UPGRADE *Only From Silica*

Silica can upgrade the 1040ST-F or 520ST-FM keyboard to a 1MB specification. The upgrade increases the memory from 512K to a massive 1MB. The upgrade is fully compatible with all existing hardware and software and includes a 3 month warranty. Fitting is quick and simple and is carried out by our team of dedicated technicians. Prices are: 1040ST-F or 520ST-FM keyboard upgraded to 1MB - £129.95 + VAT (£149.45). 520ST-FM keyboard upgraded to 1MB with internal disk drive - £179.95 + VAT (£206.95). Please call us for more information.

TV MODULATOR UPGRADE

Silica can upgrade the 1040ST-F to include a TV modulator so that you can use your computer with your TV set. This is an internal upgrade and does not require any soldering. A cable to connect your ST to any European TV is supplied in the price of the upgrade which is only £49.95 (inc VAT). The upgrade is also necessary for early 520ST computers if the new style price drop is to be enjoyed.

THE FULL STOCK RANGE *Only From Silica*

We aim to keep stocks of all Atari leisure products and our warehouse contains a stock of over £1m. We can supply most items direct from the USA and you will find that we have new releases as soon as many of our competitors. Unlike dealers who only carry a selection of titles, we have the full range in stock as we carry a comprehensive stock of titles. We also have many additional items available from us, including books, magazines and accessories. As soon as we receive any new releases we will add them to our mailing list at no charge. If you have not already received a recent copy of our catalogue, then please write to us requesting a copy.

AFTER SALES SUPPORT *Only From Silica*

Read about us and see what we have to offer. Our mailing lists are updated regularly and we will inform you of any new releases and developments. We will also keep you informed of any changes to our specialist Atari service and support. Our technical support team is available to help you with any problems you may have with your Atari ST. We are always at the end of the phone when you need us. We also provide a free printed newsletter service which is sent to you on a regular basis. The newsletter is crammed with information, including details of new releases, technical hints and tips, special offers and much more. If you have not received a recent copy of our newsletter then please write to us requesting a copy. We want you to be fully satisfied with your purchase from Silica Shop and hope that you will take advantage of our after sales service. Why not call us today and see why over 15,000 customers have relied on us for their Atari requirements.

FREE CATALOGUES *Only From Silica*

At Silica Shop, we recognise that Atari users require in depth information before making a purchase. We have therefore produced a range of catalogues which are free of charge to our customers. These are up to 64 pages long and are updated regularly. Our catalogues include details of the entire Atari ST range, including many third party products. We also stock a wide range of books and magazines for the Atari ST and would be pleased to add your name to our mailing list, please complete the coupon below or write to us. The latest catalogues are available FREE OF CHARGE to customers across the UK. They are published throughout the year and we will be pleased to send you the latest copy as soon as it is released. Please write to us requesting a copy.


FREE OVERNIGHT DELIVERY *From Silica*

Most stocks are processed through our computer within 24 hours of receiving order. Most hardware peripherals are sent by next overnight SPECIAL 1 securities service FREE OF CHARGE to customers across the UK. This method helps to ensure a speedy and reliable delivery to your doorstep.

PRICE MATCH *Only From Silica*

We hope that we can match competitors on like for like delivery service. FREE across the UK and FREE overnight delivery on most items. We will

Mini Office II



6 powerful home and business programs in just ONE package – at a price that simply can't be matched!

Voted Business Program of the Year – 1985 AND 1986

"This package is incredible value"

WORD PROCESSOR
Compose a letter, set the print-out options using embedded commands or menus, use the mail merge facility to produce personalised circulars – and more!

SPREADSHEET
Prepare budgets or tables, total columns or rows with ease, copy formulae absolutely or relatively, use a wide selection of mathematical and scientific functions, recalculate automatically – and more!

GRAPHICS
Enter data directly or load data from the spreadsheet, produce pie charts, display bar charts side by side or stacked, overlay line graphs – and more!

DATABASE
Build up a versatile card index, use the flexible print-out routine, do powerful multi-field sorting, perform all arithmetic functions, link with the word processor – and more!

COMMS MODULE
Using a modem you can access services such as MicroLink and order a wide range of goods from flowers to software, send electronic mail, telex and tele-messages in a flash – and more!

LABEL PRINTER
Design the layout of a label with the easy-to-use editor, select label size and sheet format, read in database files, print out in any quantity – and more!

DATABASE SOFTWARE Europa House, Adlington Park, Adlington, Macclesfield SK10 4NP

ORDER FORM

Please send me Mini Office II for the Atari 400/800/XL/XE (48k required) on 5¼ disc for £19.95

I enclose cheque made payable to Database Software or debit my Access/Visa card

☐☐☐☐ ☐☐☐☐ ☐☐☐☐ ☐☐☐☐

Exp date ☐☐☐☐

Signed

Name

Address

ORDER HOTLINE: TEL: 0625 879920

SEND TO Database Software, Europa House, Adlington Park, Adlington, Macclesfield SK10 4NP

ATS

Learn your token tables

ANDRÉ WILLEY ends his look at Atari Basic by giving you a program to investigate listings

I START this month's final look into the inner workings of Atari Basic with a small apology if you read my Checksum Buster article in the April issue, as a good many of you did judging by the mail we have received, you might have been a little upset to find the message APRIL FOOL splashed all over your screen

Sadly, re assembling a line of text from a three digit checksum is impossible – there are many different permutations which can generate the same value Apart from being a lesson in never trusting anyone – not even me – it does teach us quite a few useful things about how Basic works

When you used the program, typing LIST just caused a page of jovial text with no line numbers or command words to be output So how can a program exist in a tokenised – or SAVE format – file if it contains nothing that could have been correctly tokenised in the first place?

The answer is that Basic only checks for the validity of a program line when you type it in or use ENTER It therefore assumes that any SAVEd tokenised file must have been error checked at the original time of entry and is now syntactically correct

What Checksum Buster does is create a file which is correct in terms of the individual tokens and pointers, but makes no sense as a logical program

To understand it further, let's take a look at the file format used by Basic when you type SAVE or CSAVE

The bulk of it consists of the tokenised program lines themselves in the format that we have been looking at so far The variable name table must also be saved because the tokenised version of a program holds only the variable reference numbers and is meaningless without the corresponding names

For some reason a SAVEd file also contains the complete variable value table I really don't see why it couldn't have been re-generated at LOAD time, saving a couple of hundred bytes on even the shortest of files But if you know, why not drop us a line?

The only other information required by Basic is the contents of the zero page ram pointer table which is saved at the start of the file – see Figure I

One problem with saving this address pointer table is that it is only applicable to the current system set up If for example, you decide to move from a cassette system to a disc one, the value of LOMEM will be much higher due to the presence of Dos.

Since the first entry in the zero page table is LOMEM itself the first two bytes in a SAVE format file will always be zero – calculated from LOMEM minus LOMEM Similarly, the second two bytes – which represent the address of the variable name table – will always be 256 because this table is 256 bytes from LOMEM

These seven offset values take up the first 14 bytes of the file and are followed by the variable name, value and statement tables containing all the actual program lines

The final element of the file is the current statement line – numbered 32766 – which contains whatever command Basic was currently processing

Normally the last thing being worked on before a file is written is the SAVE command itself, and this is what you would usually expect to be found here.

This file format is shown in Figure II, but you might like to see it in action for yourself by typing in the listing As written it will only work on disc files because there is no facility for random access within a tape file However, cassette users might like to try modifying it to read a complete file into memory and examine it from there

Type it in and check it with Get It Right! before running it Be especially careful with lines 6400 to 6520 which contain a machine code routine

After you type RUN the program will check which version of Basic you are using and read the various rom based text tables into the pseudo string arrays *CMD$* and *OP$* These will later be used to display the correct text for each available token

Once this is complete you will be asked to enter a filename Use the full name – such as D2 FILE BAS – of the Basic SAVEd file you want to view The first 14 bytes will then be read in and the rest of the file scanned to obtain the correct NOTE and POINT

Turn to Page 10 ▶

Address	Name	Function
128/129	LOMEM	Lowest memory address accessible after Dos
130/131	VNTP	Variable name table pointer (start address of VNT)
132/133	VNTD	Variable name table dummy (end address of VNT)
134/135	VVTP	Variable value table pointer (contents of variables)
136/137	STMTAB	Statement table (start address of tokenised program)
138/139	STMCUR	Current statement (address of final tokenised command line)
140/141	STARP	String/array pointer (address of string/array contents)
142/143	RUNSTK	Runtime stack (internal GOSUB/FOR NEXT addresses)
144/145	MEMTOP	End of current Basic program space

(All addresses stored as two bytes in standard 6502 low-high format)

Figure I Basic's zero page pointer table

◀ *From Page 9*

values for each of the file segments we are interested in – the variable name, value and statement tables.

You will then be shown the information obtained from the first 14 bytes and be asked if you wish to view the variable name table or a program line. At this point you may also toggle between printer output and screen display by pressing the spacebar, or press the Escape key to select a new filename.

The variable listing will show the full name and reference number for each variable in the table, including those which may no longer be in use in the main body of the program. You will also see what type it is and the data stored in the variable value table.

Numbers are shown in an expanded BCD layout, although you could change lines 1180 to 1270 to print them in normal numeric form if you wish.

The program listing will look very different to the form you are used to seeing from the LIST command. Individual statements on a single program line are shown separately with an overall header for each and with each statement being numbered.

I've also omitted much of the normal expansion of string and numeric constants – so all numbers will be shown as *nnn* and all strings will be shown as *$$$*.

Equally, lines containing standard Ascii text – such as REM and DATA – will be shown as *$$$+EOL* in place of the text itself. Variables will be displayed as *Var0*, *Var1*, *Var2* and so on. Implied commands will be shown inside square brackets – such as the implied LET on a line like

```
100 NUMBER=100
```

which would be shown as

```
[LET] Var0=nnn
```

These changes have been made to help you see the structure of the program without being distracted by the finer details. After all, if you'd wanted to see a normal listing all you needed to do was type LIST.

If you try out this program on the Basic file created by last month's Checksum Buster you'll start to see how the seemingly impossible was created. All the lines of text were stored in the variable name table with the final character of each in inverse video to fool Basic into thinking they are just long variable names.

So you've discovered that a complete program can't be made from its checksums, but you might have learnt more about the way that Basic functions and also that the tokenising system is not quite as rigid as it first looked.

There is a well known saying which applies very well to computers and especially to Basic. It's impossible to make anything completely foolproof because fools are so ingenious.

PROGRAM BREAKDOWN

10-70	Initialise dimensions, strings, and so on
80-90	Print the title message
100-250	Get filename, open file, scan and store NOTE values
260-350	Print file's header information
360-510	Menu choice and printer/screen select function
Printing out variable name table information	
1000-1120	Get variable name and value data and print the name
1130-1180	Check for which type of variable
1190-1260	Print numeric variable information
1290-1350	Print numeric array information
1360-1410	Print string variable information
Printing out program listing from statement table	
2000-2080	Get line number and print length details
2090-2100	Print segment number and length
2110-2130	Get command token and print expanded version from *CMD$*
2140-2290	Get each operator token byte in turn, print expanded version from *OP$* and check for special cases such as 22 – EOL – and 20 – end of statement
5000-5040	Subroutine to call Get bytes routine from *BGET$*
Initialising strings	
6000-6040	Test for Revision A, B or C and gives a Basic error if none of these
6100-6170	Create *CMD$* from command token table in Basic rom
6200-6270	Create *OP$* from operator token table in Basic rom
6300-6380	Add special cases such as implied LET and so on
6400-6430	Read *BGET$* data for binary Get byte routine
6500-6520	Data for machine code binary Get routine
10000-10010	File format error handler

Part I: These values will be added to LOMEM to form the zero page ram table

Bytes	Contents	Function
0/1	0	File format flag (zero)
2/3	256	Displacement of the variable name table from the beginning of part two, plus 256
4/5	DVNTE	Displacement to the end of the variable name table from the beginning of part two, plus 256
6/7	DVVT	Displacement of the variable value table from the beginning of part two, plus 256
8/9	DST	Displacement of the statement table from the beginning of part two, plus 256
10/11	DSTC	Displacement of the current statement line from the beginning of part two, plus 256
12/13	DEND	Displacement to the end of the file from the beginning of part two, plus 256

Part II: Starts at byte 14 of the file

0	VNT	Variable name table
DVVT – 256	VVT	Variable value table
DST – 256	ST	Statement table
DEND – 256		End of file

Figure II: SAVE and CSAVE file format

```
10 REM TOKENISER BASIC PROGRAM VIEWER
20 REM BY ANDRE WILLEY
30 REM (c)ATARI USER
40 REM
50 OPN FILES(3#),INPS(500),BUFFERS(250
0),SPACES(80),CHRS(1000),OPS(1000),MGET
K(40)
60 BUFFERS(1)=  BUFFERS(2500)=  GU
FFERS(2)=BUFFERS SPACES=BUFFERS CHRS=B
UFFERS OPS=BUFFERS OPEN #3,4,8,K
70 GRAPHICS 0 POKE 82,0 POKE 752,1 ?
?  PLEASE WAIT 20 SECS -- CREATING TA
BLES ?  GOSUB 4000 GOTO 100
80 POKE #2,0 GRAPHICS 0 SETCOLOR 4,9,4
:?        TOKENISED BASIC PROGRAM VIEWE
R"
90 ? "     Copyright (C) Atari User,
May 1988 ?  RETURN
100 REM ** INPUT NEW FILE **
110 GOSUB 80
120 TRAP 100 ? " ? " ?     Enter new
FileSpec  , INPUT #16,FILES POKE 752,
1 ?
130 CLOSE #1 OPEN #1,4,0,FILES
140 ? "   PLEASE WAIT  Scanning file n
ow"
150 GET #1,A GET #1,B NEWLO=A+B*256 IF
 NEWLO<>0 THEN 100
160 GET #1,A GET #1,B VNTP=A+B*256-256
 IF NEWLO<>VNT THEN 10000
170 GET #1,A GET #1,B VNTD=A+B*256-256
180 GET #1,A GET #1,B VVTP A+B*256-256
190 GET #1,A GET #1,B STMTAD=A+B*256-2
56
200 GET #1,A GET #1,B STMCUR A+B*256-2
56
210 GET #1,A GET #1,B STARP=A+B*256-25
6
220 NOTE #1,VNTSECT,VNTBYTE NN=VVTP GO
SUB 5000
230 NOTE #1,VVTSECT,VVTBYTE NN=STMTAD-
VVTP GOSUB 5000
240 NOTE #1,STMSECT,STMBYTE NN=STMCUR-
STMTAD GOSUB 5000
250 NOTE #1,CURSECT,CURBYTE NN=STARP-S
TMCUR GOSUB 5000
260 REM ** PRINT INFO TABLE **
270 GOSUB 80 POKE 752,1
280 POKE 82,2 ? "    HEADER TABLE OF
FSETS FROM LOMEM ";  , FOR I=1 TO 5
? " CHRS(15), NEXT I
290 ? " ? Current file  ,CHRS(34),FIL
E$,CHR$(34)
300 ? " ? Start of VARIABLE NAME TABLE
  ,  ,VNTP+256
310 ? "  End of VARIABLE NAME TABLE
  ,VNTD+256
320 ? "Start of VARIABLE VALUE TABLE
  ,VVTP+256
330 ? "  Start of STATEMENT TABLE
  ,STMTAD+256
340 ? "CURRENT STATEMENT Pointer
  ,STMCUR+256
350 ? "  Last byte of program area
  ,STARP+256 ?
360 REM ** MENU CHOICE ROUTINE **
370 POSITION 2,18 IF MODE=0 THEN " Ke
y (1) to show Variable Name Table,
380 IF MODE=1 THEN " Key (1) to print
 Variable Name Table,
390 ?  (2) for program Line Listin
g, ?  or ESC to select a new T Lespe
c
400 POSITION 1,22 ? (Press the Space
 Bar to toggle output " between the S
CREEN and the PRINTER),
410 GET #5,OPT
420 IF OPT=32 THEN MODE=ABS(MODE-1):GO
TO 360
430 IF OPT=27 THEN 100
440 IF OPT<49 AND OPT<>38 THEN ? CHR$
(253), GOTO 410
450 POKE 82,0
460 IF MODE=0 THEN CLOSE #2 OPEN #2,8,
0,E  POKE 752,1
470 IF MODE=1 THEN CLOSE #2 OPEN #2,8,
0,P  ? #2 GRAPHICS 0 POKE 752,1 ?  ?
          PRINTING - PLEASE WAIT
480 IF OPT=49 THEN GOSUB 1000 REM FOR
VARIABLES
490 IF OPT=50 THEN GOSUB 2000 REM FOR
PROGRAM LINES
500 IF MODE=0 THEN ? "  ?  "                <<<Pr
ess any key for menu>>>", GET #3,OPT
510 GOTO 260
1000 REM ** SHOW VARIABLE DETAILS **
1010 ? #2,  Variable Name Table of ,
FILE$
1020 SECT1=VNTSECT BYTE1=VNTBYTE SECT2
=VVTSECT BYTE2 VVTBYTE VARNO=0
1030 CH=0 POINT #1,SECT1,BYTE1 IF SECT
1=VVTSECT AND BYTE1=VVTBYTE THEN RETUR
N
1040 ? #2 ? #2,VARNO,  , IF VARNO<10
THEN ? #2,  ,
1050 IF VARNO<100 THEN ? #2,  ,
1060 GET #1,A IF A=0 THEN ? #2,0
     END OF VARIABLE TABLE  RETURN
1070 IF A<128 THEN ? #2,CHR$(A), CH=CH
+1 GOTO 1060
1080 A=A-128 NOTE #1,SECT1,BYTE1
1090 POINT #1,SECT2,BYTE2
1100 NN=0 GOSUB 5000
1110 NOTE #1,SECT2,BYTE2
1120 ? #2,CHR$(A), CH=CH+1 GOSUB 1130
VARNO VARNO+1 GOTO 1030
1130 REM ** SHOW VARIABLE CONTENTS **
1140 IF CH<11 THEN ? #2,SPACE$(1,11-CH
),
1150 TYPE=ASC(BUFFER$)
1160 IF TYPE=64 THEN ? #2,  UN-DIMMED
ARRAY RETURN
1170 IF TYPE=128 THEN ? #2,  UN-DIMMED
 STRING RETURN
1180 IF TYPE>0 THEN 1200
1190 REM ** NUMERIC (#CB) VARIABLE **
1200 ? #2, BCD NUMBER ,WANT=PEEK(BU
F+2) IF WANT=0 THEN ? #2, Zero RETUR
N
1210 ? #2 ? #2,SPACE$(1,17), IF WANT>1
27 THEN WANT=WANT-128 ? #2, ",
1220 WANT=WANT+64 FOR I=BUF+3 TO BUF+7
1230 NN=PEEK(I):NN$=INT(NN/16)+0 1) LO=I
NT(NN-(N$*16)+0 1)
1240 ? #2,NN;LO, IF I=BUF+3 THEN ? #2,
 ,
1250 NEXT I
1260 IF WANT<>0 THEN ? #2, x 100  WA
NT RETURN
1270 ? #2 RETURN
1280 IF TYPE<>65 THEN 1350
1290 REM ** PRINT ARRAY INFO **
1300 ? #2,  ARRAY
1310 ? #2,SPACE$(1,17),Offset Address
 -  ,PEEK(BUF+2)+PEEK(BUF+3)*256
1320 ? #2,SPACE$(1,17), Dimension One
 =  ,PEEK(BUF+4)+PEEK(BUF+5)*256-1
1330 NN=PEEK(BUF+8)+PEEK(BUF+7)*256-1
IF NN>0 THEN ? #2,SPACE$(1,17), Dimens
ion Two  =  ,NN
1340 RETURN
1350 IF TYPE<>128 THEN RETURN
1360 REM ** PRINT STRING INFO **
1370 ? #2,  STRING
1380 ? #2,SPACE$(1,17),"Offset Address
 = ",PEEK(BUF+2)+PEEK(BUF+3)*256
1390 ? #2,SPACE$(1,17)  Current Length
    PEEK(BUF+4)+PEEK(BUF+5)*256
1400 ? #2 SPACE$(1,17), Max num Le gth
 = ,PEEK(BUF+6)+PEEK(BUF+7)*256
1410 RETURN
2000 REM ** SHOW PROGRAM STATEMENTS **
2010 ? #2,   PROGRAM STRUCTURE OF ,F
ILE$
2020 POINT #1,STMSECT,STMBYTE
2030 REM ** GET LINE NUMBER & SIZE **
2040 FINAL=0 GET #1,A GET #1,B LINE=A+
B*256
2050 GET #1,SIZE NN=SIZE-5 GOSUB 5000
2060 ? #2 IF LINE=32768 THEN ? #2, Las
t Immediate command, FINAL=1 GOTO 208
0
2070 ? #2, Line ,LINE
2080 ? #2, (,SIZE, bytes long) SEG
=0 CURR=0
2090 REM ** PRINT SEGMENT DETAILS **
2100 SEG=SEG+1 ? #2,  ~ SEG, , Offse
t=,PEEK(ADR(BUFFER$)+CURR),  ,
2110 REM ** GET & PRINT COMMAND **
2120 CURR=CURR+1 BYTE=PEEK(ADR(BUFFER$
)+CURR) CH=BYTE+10+1
2130 IF CMD$(CH,CH)<>CHR$(255) THEN ?
#2 CMD$(CH,CH), CH=CH+1 GOTO 2130
2140 REM ** GET & PRINT EACH OP BYTE *
*
2150 ? #2,  , IF BYTE=0 OR BYTE-1 OR
BYTE=55 THEN ? #2, $$$=EOL GOTO 2030
2160 CURR=CURR+1 BYTE=PEEK(ADR(BUFFER$
)+CURR)
2170 IF BYTE=14 THEN ? #2, nnn , CURR
CURR+2 GOTO 2160
2180 IF BYTE 15 THEN ? #2, $$$ , CURR-
CURR+PEEK(BUF+CURR+1)+1 GOTO 2160
2190 IF BYTE=22 THEN ? #2 IF FINAL=0 T
HEN GOTO 2050
2200 IF BYTE 22 THEN RETURN
2210 IF BYTE=20 THEN CURR=CURR+1 ? #2
GOTO 2090
2220 IF BYTE>127 THEN ? #2, Var ,BYTE-
128, GOTO 2160
2230 CH=BYTE+10+1 OK=1 IF (BYTE<22 AND
 BYTE<28) OR (BYTE>=0 AND BYTE<43) THE
N OK=0 ? #2,  ,
2240 IF OP$(CH,CH)<>CHR$(255) THEN ? #
2,OP$(CH,CH), CH=CH+1 GOTO 2240
2250 IF OK=0 THEN ? #2  ,
2260 IF BYTE >27 THEN 2160
2270 BYTE=PEEK(ADR(BUFFER$)+CURR+1)+IF
 BYTE<>14 THEN ? #2 CURR=CURR+1 GOTO 2
090
2280 ? #2, [GOTO] nnn GOTO 2030
2290 GOTO 2160
5000 REM ** GET NN BYTES ROUTINE **
5010 BUF=ADR(BUFFER$)
5020 IF NN>2500 THEN CIO=USR(ADR(GET$
),1,BUF,2500,7) NN=NN-2500 GOTO 5020
5030 IF NN>0 THEN CIO=USR(ADR(GET$),1
,BUF,NN,7)
5040 RETURN
6000 REM ** SETUP TOKEN STRINGS **
6010 VER=PEEK(43234)
6020 IF VER=192 THEN STATTAB 42159 OPT
AB=42979 REM REV A BASIC
6030 IF VER=234 OR VER=96 THEN STATTAB
=42143 OPTAB=42874 REM REV B/C BASIC
6040 IF OPTAB=0 THEN ? "    ERROR N
OT REV A, B OR C BASIC END
6100 REM ** SET UP COMMANDS STRING **
6110 NUM=0 ADDR=STATTAB ? " COMMANDS
 "
6120 ADDR=ADDR+2
6130 ? #, IF PEEK(ADDR)=0 THEN 6200
```


Turn to Page 12 ▶

◀ From Page 11

```
6140 CURB=WUN*10+1 WUN=WUN+1
6150 IF PEEK(ADDR)>127 THEN 6170
6160 CMD$(CURR,CURB)=CHR$(PEEK(ADDR))
CURR=CURR+1 ADDR=ADDR+1 GOTO 6150
6170 CMD$(CURR,CURB)=CHR$(PEEK(ADDR)-1
28) CMD$(CURR+1,CURR+12)=CMD$(255) ADDR
=ADDR+1 GOTO 6120
6200 REM ** SETUP OPERATORS STRING **
6210 WUN=16 ? ? ? FUNCTIONS, ETC

6220 ADDR=OPTAB
6230 ? "," IF PEEK(ADDR)=0 THEN 6300
6240 CURR=WUN*10+1 WUN=WUN+1
6250 IF PEEK(ADDR)>127 THEN 6270
6260 OP$(CURR,CURB)=CHR$(PEEK(ADDR)) C
URR=CURR+1 ADDR=ADDR+1 GOTO 6250
6270 OP$(CURR,CURR)=CHR$(PEEK(ADDR)-12
8) OP$(CURR+1,CURR+1)=CHR$(255) ADDR=A
DDR+1 GOTO 6230
6300 REM ** ADD NON-PRINTING CODES **
6310 CMD$(54,54)=CLE$: CMD$(546,54
6) CHR$(255)
6320 CMD$(551,557)=ERROR- CMD$(558,
558)=CHR$(255)
6330 OP$(161,161)=CHR$(34)
6340 OP$(171,171)=CHR$(255)
6350 OP$(561,561)=(
6360 OP$(571,571)=(
6400 REM ** SETUP M/CODE ROUTINE **
6410 I=1 ? ? ? M/CODE
6420 ? ; READ A IF A<>-1 THEN DOETS
(I,1)=CHR$(A):I=I+1:GOTO 6420
6430 RETURN
```

```
6500 REM ** M/CODE DATA **
6510 DATA 104,104,104,10,10,10,10,37,
104,157,89,3,104,157,88,3,104,157,75,2
6520 DATA 104,157,72,3,104,104,157,64,
3,32,86,228,132,212,169,0,133,213,96,-
1
10000 REM ** FILE ERROR **
10010 ? ?  FILE FORMAT ERROR END
```



10 CP1 (Y1)	22D SWK (P)	43D DDG (L2)	
2D CP2 (X)	23D ELA (X)	44D VYS (S2)	
3D CP3 (X1)	24D G3A (H)	45D S02 (E2)	
4D CP4 (4)	25D CNY (U1)	46D W1S (A2)	
5D BUS (K)	26D RLT (N1)	47D AA6 (C2)	
6D 3W1 (U)	27D ZWE (N1)	48D UA8 (E)	
7D AJE (E3)	28D 1C3 (J1)	49D UGV (T)	
8D SVW (D)	29D T40 (J1)	50D S2E (R)	
9D JLU (U3)	30D BPJ (Z)	51D BJC (B)	
10D CUS (N)	31D 1XO (W)	52D CKN (F)	
11D WFJ (7)	32D FWS (P)	53D 021 (V2)	
12D OEX (4)	33D CR3 (N1)	54D Y5K (Z)	
13D HJ4 (Z)	34D GBJ (F)	55D 3RX (S)	
14D YEF (0)	35D VM6 (T)	56D 3SV (F)	
15D EUV (4)	36D DLU (N1)	57D W7 (4)	
16D ER5 (X)	37D UF4 (2)	58D KXB (B1)	
17D QW9 (U)	38D WLJ (P)	59D 2SF (G)	
18D ZJS (3)	39D ALB (Z)	60D AE1 (W1)	
19D 40L (H)	40D KP4 (N)	61D E7A (1)	
20D 2HM (B)	41D SUY (R)	62D 78D (W2)	
21D 3N0 (B)	42D 04C (O)	63D 1HR (B)	

11 2D HPB (4)	284D DX0 (B)	405D RTF (L)	
11 3D DBN (2)	285D 501 (2)	406D 155 (O)	
11 4D 0BT (5)	286D UN5 (A)	407D D2T (S)	
11 5D ECA (H)	287D CGD (G)	408D JYK (O)	
11 6D JWS (L)	288D 1S0 (T)	409D V2B (Y)	
11 7D SBE (4)	289D DHP (W)	410D ZNY (1)	
11 8D WLA (5)	290D RUV (N)	411D 5Y4 (S)	
11 9D DNN (1)	291D 0AP (J)	412D SMG (V)	
12 0D 13V (P)	292D VW1 (M)	413D ERF (G)	
12 1D 3W5 (V)	293D 702 (A)	414D JU2 (V)	
12 2D H17 (V)	294D DAP (F)	415D D6T (V)	
12 3D 010 (T)	295D 60A (2)	416D DFL (S)	
12 4D 9WU (B)	296D 3D6 (N)	417D WJR (X)	
12 5D W95 (B)	297D FN5 (E)	418D ZPY (1)	
12 6D 1FH (1)	298D FRY (S)	419D 134 (4)	
12 7D WGE (P)	299D DBN (7)	420D SMD (4)	
12 8D 55P (S)	300D 20J (O)	421D PEU (E)	
12 9D DRN (V)	301D X48 (D)	422D N3R (E)	
13 0D 27K (1)	302D EYP (7)	423D 0AI (E)	
13 1D PON (C)	303D KK6 (N)	424D L0U (T)	
13 2D CYU (J)	304D RS7 (S)	425D KNU (7)	
13 3D 0DN (C)	305D 62V (1)	426D FS5 (N)	
13 4D VXK (F)	306D SVT (E)	427D KC6 (S)	
13 5D 24Y (B)	307D U2K (A)	428D 59V (O)	
13 6D BPN (F)	308D WSP (G)	429D SEE (1)	
13 7D 7A5 (R)	309D P1W (P)	430D DFT (2)	
13 8D PFN (A)	310D CX5 (N)	431D FNO (S)	
13 9D S6S (T)	311D D6F (L)	432D VRV (C)	
14 0D PJN (A)	312D PTT (N)	433D WOW (C)	
14 1D VVK (E)	313D P5G (X)	434D DKT (B)	
28 0D CXP (B)	314D VKP (X)	435D NN1 (P)	
28 1D GSG (C)	315D CXT (Y)	436D QPF (C)	
28 2D 03H (S)	316D 9GL (P)	437D 003 (9)	
28 3D 04P (B)	317D WU3 (4)	438D 4W5 (E)	

MILES BETTER SOFTWARE

221 Cannock Road, Chadsmoor, Cannock,
Staffs WS11 2DD Tel (0543) 466577/8

LIB GOLD	Cass.	Disc
Eternal Dagger	18.95	
Age of Aces	8.95	18.95
Fernn Charge	22.95	
Battle Cruiser	22.95	
221B Baker Street	11.95	
Breakdown	22.95	
U.S.A.A.F.	24.95	
Computer Ambush	24.95	
Warship	24.95	
Carrier Force	24.95	
Colonial Conquest	22.95	
Wizards Crown	18.95	
Gunslinger	12.95	
Sons of Ambition	24.95	
Kamikazegruppe	24.95	
Panzerlegs	24.95	
Dropzone Disc I	17.95	
Dropzone Disc II	17.00	
Rasputin + Dropzone + Caverns	8.95	
Mastiner Games	19.95	
Real Deal Massive	7.95	11.95
Beach Head II	11.95	
Leaderboard	7.95	11.95
Eagle Nest	9.95	11.95
Rise of Fire	11.95	
Vietnam	11.95	
Gauntlet	8.95	11.95
Attempt Reality II	10.95	
Phantasie	19.95	
Gettysburg	25.95	
Panzer Grenadier	22.95	
War Game Construction Set	19.95	
Mean Brigade	24.95	
Leaderboard Tournament	4.95	8.95
Gauntlet Deeper Dungeons	4.95	8.95
War in Russia	29.95	
ENGLISH SOFTWARE	Cass.	Disc
Smash Hits Vol 5	8.95	12.95
Smash Hits Vol 6	8.95	12.95
Smash Hits Vol 7	8.95	12.95
ACTIVISION	Cass	Disc
Ghostbusters	8.95	
CODE MASTERS	Cass	
Grand Prix Simulator	1.99	
Phone for availability		

Piste Simulation	1.99
Feet Mac	1.99
Transmission	1.99
SONARK	Cass	Disc
Living Daylights	8.95	12.95
Tiffast Pursuit	10.95	15.95
ELECTRIC DREAMS	Cass.	Disc
Spindizzy	8.95	12.95
CRITAL INTEGRATION	Cass.	Disc
Fighter Pilot	8.95	10.95
Tomahawk	8.95	12.95
NOVAGEN	Cass.	Disc
Mercenary	7.95	10.95
Second City	5.95	8.95
Mercenary Comp. Pack	12.95	14.95
DATABYTE	Cass.	Disc
Spy V Spy II	7.95	12.95
Aztec	7.95	12.95
Spy V Spy III	9.95	12.95
Spy V Spy I	9.95	12.95
Soorted Dash Construction Kit	8.95	12.95
MARINE/OCEAN	Cass.	Disc
Arkanoid	7.95	11.95
Green Beret	7.95	
INFOCOM	Cass	Disc
Station Fall		22.95
Hitchhikers Guide to the Galaxy		22.95
MASTERTRONIC	Cass.	Disc
On Cue	2.99	
Storm	1.99	
180	2.99	
Amaurote	2.99	
Universal Hero	1.99	
Kick Start	1.99	
Last V8	2.99	
Ninja	2.99	
3 W A T	1.99	
Molecule Man	1.99	
Crystal Raaaze	1.99	
Sun Last	1.99	
Mutant Camels	1.99	
Fronts	1.99	
Horror Soccer	1.99	
RAINBIRD/FIREBIRD	Cass	Disc
Knight Orc	8.95	12.95
Druid	8.95	12.95

Jewels of Darkness	10.95	12.95
Guild of Thieves		16.95
Silicon Dreams	12.95	12.95
The Pawn		16.95
GREMLIN GRAPHICS	Cass	Disc
Basil the Mouse Detective	8.95	12.95
Trail Blazer	7.95	11.95
Footballer of the Year	6.95	12.95
SYSTEM 3	Cass	Disc
International Karate	6.90	10.95
ARIOLA	Cass	Disc
Zaxxon + Pooyan	9.95	9.95
TYNESOFT	Cass	Disc
Who Dares Wins II	8.95	8.95
Kelly Speedway Mcnl only		8.95
Mirax Force	8.95	8.95
DATABASE	Cass.	Disc
Mini Office II		19.95
MICROPROSE	Cass.	Disc
Silent Service	8.95	19.95
F-15 Strike Eagle	8.95	19.95
Gunship	8.95	19.95
Conflict in Vietnam	12.95	19.95
CLUB SOFTWARE	Cass.	Disc
Brian Cloughs Football	12.95	16.95
Cellulus Chess IV	8.95	12.95
ORIGIN	Cass	Disc
Autoduel		17.95
Ogre		16.95
Ultima III		16.95
Ultima IV		19.95

ATARI SOFTWARE	Cass	Disc
Star Raiders II		12.95
RED RAT SOFTWARE	Cass	Disc
Little Devil	8.95	8.95
Night Mares	6.95	8.95
Compilation 1	8.95	8.95
Compilation 2	8.95	8.95
Astro Droid	8.95	8.95
Space Lobster	6.95	8.95
Synergy	8.95	8.95
Crumbles Crisis	6.95	8.95
Bootstomping Wings	6.95	8.95
BUBLONIC		Disc
Flight Simulator II		30.95
San Francisco		21.95
Japan		21.95

BUDGET TITLES

	Cass.	Disc
Scooter	1.99	
Colony	1.95	
War Hawk	1.99	
Football Manager	2.95	
Master Chess	1.99	
Micro Rhythm	1.99	
Rockford	2.95	
Speed Ace	2.99	

HARDWARE
Sega System including free Outrun £87.95
Nintendo System £95.00
Ferguson CM80E Monitor/TV £209.00
XC12 cassette unit £34.95

PHONE FOR LATEST ST PRICES

For full list of ST Software see our advert in the Atari ST User

SPECIAL OFFERS

	Cass.	Disc
Strip Poker	–	6.95
Cat 'n Faste	–	14.95
Quest Paste	–	8.95
Pinball Construction Set	–	7.95
Philosophers Stone		5.95
Alien Aces	6.95	–
Pattern Perfection	6.95	–
Shoot 'em Up	6.95	–

All prices are correct at time of going to press. Postal or Visa orders welcome.
Please add £1 per item for overseas orders
Please send Cheques or Postal Orders payable to
MILES BETTER SOFTWARE
Please or write for comprehensive Atari list for Atari and ST software + Hardware

WHILE STOCKS LAST

MUG

THE INDEPENDENT MicroLink User Group NEWSLETTER

Bulletin Board update

The MicroLink Bulletin Board has just had a spring clean, and a backlog of 9,000 old messages removed. But at the rate at which it's being used it won't take more than a couple of months to replace them.

The Bulletin Board is an area where anyone can leave a public message, start or join in a discussion on any topic or just ask for help.

The range of subjects covered is huge and always changing, cars are bought and sold, philosophy, pop music and poaching argued about and the reasons why somebody's software doesn't seem to work are revealed.

There are even the occasional trivia quizzes (well, do YOU know how many electric tramways are still running in the UK?).

There's nothing quite like it outside the world of computers, but be warned: it can be very addictive.

Prepariog for Prime time

EVERYONE upgrades their hardware occasionally, and MicroLink is no exception. But it's not an Amstrad PC1640 they're getting.

For some time now, the rate at which people are joining has put a bit of a strain on the old Prime 850 computer, and many users would agree that sluggish is perhaps a mild way to describe MicroLink at peak times.

Now work is underway to install a Prime 9955 – not only has it got a longer name but it's faster and better able to cope with the increased demand.

There's a lot of things to be done before the switchover can happen, software has to be changed and the digital detritus collected on the old computer in its years of dealing with us humans has to be cleared up.

Exactly how much better the new service will be isn't clear, although technical people tend to use words like "massively" and get quite excited.

We're all eager to find out.

The MicroLink User's Manual

ONE of the projects that MUG is coordinating is the production of the MicroLink User's Manual. Designed to complement the information given to every MicroLink subscriber on old fashioned paper, the manual sets out to be an online way of describing the many facilities available on MicroLink from the point of view of the people who use them.

At first MicroLink can appear to offer a bewildering selection of things to try, and even for experienced users the different options can be confusing. And there's always a way to do things faster, or at less cost.

Of course, the information to help people do this has always existed. But it's been hard to find, and until now there hasn't really been any way for users to share their discoveries in such a way that others will be able to make use of them. The MicroLink User's Manual sets out to remedy this problem.

At the moment MUG is collating the information. Sometimes the amount of data collected by users can be staggering – one subscriber mailed in over 200k of hints and tips saved up over years. Of course, we're just as happy to hear from anyone with one good idea.

All the data will be indexed and made available, the exact design is still being discussed, but like anything else MUG does, it will be free to use.

User groups are good news

THE MicroLink Users' Group came about as a result of various subscribers asking whether there was any organisation run to help users.

User groups in any area are usually good news, they form a focus for ideas, opinion and self-help and give the users a collective voice.

The flexibility provided by MicroLink and Telecom Gold make MUG particularly useful. There are no printing costs for newsletters and there's almost an instant access to everyone in the group through the mail system.

MUGs been going for about a month now, and we've already formed a team of people who have volunteered to answer queries and help anyone with MicroLink-related problems.

It's a small world . . .

. . . but full of Telecom Gold computers, it seems. The UK Telecom Gold system of which MicroLink is the most active part, is just one sector of a global network called Dialcom.

While MicroLink is System 72 and other UK computers are in the range 70 to 90, there are Dialcom computers almost everywhere. And like international telephone exchanges they've all got their own numbers.

MUGger Adrian Mars is trying to find out just which computers are where. This might seem an eccentric if harmless, hobby, but such information as is available on MicroLink is difficult to find and (apparently) out of date.

And it could be the first step to organising an international group of Dialcom users, which really would be a first and another step towards the electronic community of tomorrow.

If you know anything about the Dialcom network numbering scheme then Adrian (MARS ADRIAN on the mail system) and MUG would be glad to hear from you.

Odd offers

THE prize for the most unusual use of MicroLink goes to . . . well, nobody knows. But the last month has seen some odd goings-on.

There have been people advertising for goose shooting, others looking for burned out buildings and the usual range of online florist orderings to persuade mothers and lovers that computers aren't so bad after all.


But you have to take your hat off if nothing else, to Keith Channing. He helps run COKAL, Clothes Optional Recreation and Leisure, a naturist organisation dedicated to promoting the various activities enjoyed by those who feel happier without their clothes on. And with a bit of advertising on the Bulletin Board and a touch of help from MicroLink themselves he's gathering together all those on the system who are similarly inclined.

Now that has to be the most original use for MicroLink.

Unless (of course) you know better.

Suggestions of material for inclusion in the MUG Newsletter should be sent to Rupert Goodwins on MAG95816

MUCH MORE THAN A MAGAZINE



PAGE 6 bas been supporting Atari computers for 5 years – coverage now includrs both 8-bit and ST. Get the latest copy from your local newsagent or by subscribing.

We also support our readers in many other ways.

* **All 8-bit magazine programs on disk with bonus programs included**
* **Books for beginners to experts**
* **Dust covers for all Atari equipment**
* **The widest range of Atari public domain software avaiiable anywhere**

Phone us on 0785 57005 for further details or visit your local newsagent today

All disks are sent by First Class post or courier service at no extra cost

TOP QUALITY DISKS AT ROCK BOTTOM PRICES

3.5" BULK PACKED–Top QUALITY	10	25	50	100	150	200
Single Sided 48T P I	£5.49	£10.50	£19.50	£37.50	£51.50	£69.95
Single Sided 96T P I	£5.95	£10.75	£19.95	£38.50	£53.00	£69.00
Double Sided 48T P I	£5.95	£11.00	£19.50	£36.50	£49.00	£65.00
Double Sided 96T P I	£6.95	£11.50	£20.50	£39.00	£56.00	£69.50
Double Sided Coloured 96T P I	£7.95	£13.75	£26.75	£48.95	£67.50	£89.75
Bulkrite Sides Reversible 96T P I	£7.95	£15.00	£28.50	£53.50	£65.00	£100.50
Coloured & Reversible 48T P I	£8.95	£17.25	£32.75	£60.25	£82.95	£109.75
Coloured & Reversible 96T P I	£9.95	£18.75	£36.50	£65.50	£90.75	£143.75

Packs of 10 5.25" Disks come with Free Plastic Library Case (worth £1.49!)
Coloured Disks come in five colours (Red, Blue, White, Yellow, Green)
Reversible disks have two holes holes and two notches!
Coloured and reversible holes come in five colours and have two holes and notches
All Double disks are packed with a protective jacket (envelope) and come with a full user set, including a disk and a write protect tab. The disks are manufactured to top international standards and have a hub ring for added protection. All disks carry our no quibble replacement guarantee and are certified 100% error free



Storage Boxes

3.00" Lockable – Holds 25	£7.49
3.50" Lockable – Holds 40	£7.49
3.00" Lockable – Holds 60	£8.49
3.50" Lockable – Holds 80	£8.49
3.50" Lockable – Holds 120	£10.95
5.25" Lockable – Holds 50	£7.49
5.25" Lockable – Holds 100	£8.49
5.25" Lockable – Holds 140	£10.95

3.5" Cleaning Disc	£4.99
5.25" Cleaning Disc ..	£3.99
Disk Notcher	£3.49
ST Printer Cable ..	£8.49



PROFESSIONAL PRINTER STAND

This new printer stand is very space efficient as it takes roughly any same room then your printer Due to the unique positioning of the paper guide mechanism and rehold compartmenge that is one solves the other the desk space is effectively halved The space saving design allows easy access to the paper from both sides the special dial controlled paper feed system with adjustable deflector plates ensures smooth paper flow and automatic refolding

80 Col	£29.95
132 Col	£34.95

COPY HOLDERS



YU-H32 Copy Holder with Adjustable Arm
Size 9.5" x 11.5" with smooth slide line guide – £19.95
YU-H34 Copy Holder with Adjustable Arm
Size 15" x 12" (A3) – £29.95

SPECIAL OFFERS
3.5" DISCS + LOCKABLE BOXES



20 x 3.5 DS-DD DISKS PLUS 40 CAPACITY LOCKABLE BOX FOR
ONLY £24.95

OR

40 x 3.5" DS-DD DISKS PLUS 40 CAPACITY LOCKABLE BOX FOR
ONLY £44.95

50 x 3.5" DS-DD DISKS PLUS 80 CAPACITY LOCKABLE BOX FOR
ONLY £54.95

OR

80 x 3.5" DS-DD DISKS PLUS 80 CAPACITY LOCKABLE BOX FOR
ONLY £79.95

3.5" TOP QUALITY BULK PACKED DISKS

	10	25	50	100	150	200
Single Sided 135T P I	£12.45	£23.95	£46.95	£91.95	£129.95	£169.95
Double Sided 135T P I	£14.49	£26.95	£52.95	£99.95	£145.95	£189.95

Rainbow Pack of five colours – New product!

Single Sided 135T P I	£17.95	£39.95	£82.95	£159.95	£219.95
Double Sided 135T P I	£19.95	£39.95	£79.95	£154.95	£214.95	£279.95

Packs of 10 5.5" Disks come with Free Plastic Library Case (worth £1.49!)
All discs are supplied with labels and are certified 100% error free

CENTEC DISK SUPPLIES


UNIT 3, THE METRO CENTRE, BRIDGE ROAD, ORPINGTON, KENT BR5 2BE
TEL. (0689) 35353 (6 Lines) (24 Hours) Fax 0689 77737

Please note we operate a call sucking system Outside office hours a telephone answering machine will take your order
Remember – all prices include VAT and delivery! There are no hidden extras so yay! Personal callers welcome Monday-Friday 9.30am-4.30pm

VISA

HAVE A Nice DAY

GREGORY BENHAM provides a routine to plot the ups and downs of your life



THIS easy-to use program is based on a simple theory put forward by research scientists that the physical, mental and emotional states of the human body are constantly undergoing three fluctuating cycles

These are very similar to each other but differ in their frequency. Physical emotional and mental states have 23 28 and 33 day periods respectively so they are not usually in phase with each other.

They are said to be activated on the day we are born and controlled by a kind of built-in biological clock. The listing here represents these changing moods by sketching standard sinusoidal waves in graphical form for any month since a person's birth date.

The critical periods for us are at the highest and lowest peaks on the curves, when our moods will be correspondingly strong and weak. When all three peaks coincide we are therefore to be regarded as on the ball and buzzing or, in the second case better off staying in bed all day.

Since these cycles apply to everyone it therefore means that the three biocycles are running parallel, but individually with those of other people with the same constant phase lag depending on the difference between their birth dates.

Biorhythm calculates this difference for each of the three categories and computes the combined average to give a figure as a percentage for how any two people's overall mood status compares and hence determines their compatibility.

The three main screen displays are all different display lists stored in page 6 of memory enhanced by a customised character set used throughout. If you study lines 3000 to 3360 you will see a number of techniques used to make keyboard input easy yet idiot-proof.

When entering dates you must use the format DD/MM/YYYY. For example 01/05/1988 or 1/5/1988 – the slash sign must separate the numbers. If you make a mistake the computer will either prompt you to re-enter the date or refuse to accept the input. You can erase any entry using the Delete key.

The program contains many useful routines which add to the overall presentation. A flashing cursor, a totally re-defined character set and display lists have been used wherever possible to enhance the graphic screens.

N B. I cannot be held responsible if you run the program and find out that you are not compatible with your wife

```
10 REM **********************
20 REM *    BIORHYTHMS      *
30 REM *  BY GREG BENHAM    *
40 REM *   (C)1988 USER     *
50 REM **********************
100 DIM CS$(1024),GO$(8),B(3),A$(37),N(3),
,N2$(12),BM(12),BY(12)
120 A$=" "+A$(1,36):M$=A$(1,36):RESTORE
 160
130 FOR I=1 TO 12:READ B:BM(I)=B:NEXT
I
140 FOR I=1 TO 12:READ B:BY(I)=B:NEXT
I
150 FOR I=0 TO 11:READ N$:M$(I*3+1)=
N$:M$(I*3)=" "
160 DATA 31,28,31,30,31,30,31,31,30,31
,30,31,1,32,60,91,121,152,182,213,244,
274,305,335
170 DATA JANUARY,FEBRUARY,MARCH,APRIL
,MAY,JUNE,JULY,AUGUST,SEPTEMBER,OCTOBER
,NOVEMBER,DECEMBER
180 FOR I=1536 TO 1663:READ B:POKE I,B
:NEXT I
190 FOR I=1664 TO 1791:POKE I,15:NEXT
I
200 FOR I=1792 TO 1799:READ B:POKE I,B
:NEXT I:X=USR(1536)
210 DATA 100,165,9,41,1,240,14,189,12,
141,43,6,165,13,141,44,6,169,1,133,9,1
69,39,133,12,169,6
220 DATA 133,13,162,5,168,45,169,7,32
,92,220,96,32,79,6,76,77,188,188,87,200
,76,206,70,6,200
230 DATA 21,160,0,166,93,81,94,41,127
,205,6,177,94,73,128,145,94,169,32,141
,78,6,76,98,228,32
240 DATA 112,112,112,73,0,140,9,9,9,9
,9,9,7,7,7,8,8,8,8,8,8,2,2,2,2,2,1,1,
2,65,79,6
250 DATA 112,112,112,70,0,128,2,6,6,8
,6,2,65,112,6
260 DATA 112,112,112,71,0,146,7,7,7,7
,7,2,2,2,2,2,2,2,2,2,65,195,6
270 GRAPHICS 0:? CHR$(125):CLOSE #1:PO
KE 708,206:POKE 709,6:POKE 710,14:POKE
 711,42:POKE 712,134
280 POKE 704,255:POKE 756,PEEK(106)-4:
POKE 559,34:POKE 54279,PEEK(106)-4:POK
E 53277,3
290 POKE 559,46:POKE 54286,192:POKE 53
248,PEEK(106)-4:POKE 53249,PEEK(106)-3
300 CHBAS=PEEK(756)*256:TOPSCR=PEEK(CHB
AS+1)*256+PEEK(CHBAS)-1
310 RESTORE 340:FOR COL=0 TO 9:READ DS
ET:FOR I=0 TO 7
320 POKE TOPSCR+(INT(I/2)+1)*40+COL,PEE
K(CHBAS+I+(DSET*8))
330 NEXT I:NEXT COL
340 DATA 34,41,47,50,48,57,52,40,45,51
350 POKE A,2:POKE 88,119:PRINT#6;"
? MM  Main Menu
360 POKE A,1:POKE 88,180:POSITION 2,8
:? #6;"DO YOU WANT TO "
370 POKE 87,0:POKE 82,2:? #6;"   [1]
 Calculate a new curve"?"    [2] Calc
ulate Compatability
380 ? #6;"   [3] Exit from program":?:?
"Please press required number key"
390 OPEN #1,4,0,"K"
400 GET #1,K:K=K-48:IF K<1 OR K>3 THEN
 400
```

Turn to Page 15 ▶

◀ From Page 15

```
410 OR R GOTO 1000,2000,450
420 GOTO 270
450 CLOSE #1 ? CHR$(125) POKE 87,2 POK
E 88,160 POKE 755,0 POKE 710,130
460 POSITION 0,0 ? #6;'by" POSITION 4
1;? #6;"[FREE SCREEN]
470 POKE 87 1 POKE 88,160 POSITION 2 8
 ? #6; for '0160I USE0''
480 LIN=480 FOR SEL=1 TO 78 NEXT SEL G
OTO 6000
```

```
1150 POKE 88,20 POKE 89,136:COLOR 2 FO
R L=4 TO 156 STEP 5 PLOT 3,0 DRAWTO L,
4 PLOT L+1,0 DRAWTO L+1,4 NEXT L
1160 POKE 87,0 POKE 88,160 POKE 752,1
POSITION 0,0:? "[BLACK BACKGROUND]
[REVERSE]
1170 POKE 87,1 POKE 88,230 POSITION 0
,1 ? #6;" POSICAL ewatrana1 [RED
WAN]"
1180 POKE 87,7 POKE 88,20 POKE 89,120:
COLOR 1 POKE 708,136:POKE 709,204:POKE
 710,54 POKE 712,170
1190 PLOT 0,0 DRAWTO 0,61 DRAWTO 159,6
```

```
1850 POKE 88,20 POKE 89,136:COLOR 2 FO
R L=4 TO 156 STEP 5 PLOT 3,0 DRAWTO L,
4 PLOT L+1,0 DRAWTO L+1,4 NEXT L
1860 POKE 87,0 POKE 88,160 POKE 752,1
POSITION 0,0:? "[BLACK BACKGROUND]
[REVERSE]
1870 POKE 87,1 POKE 88,230 POSITION 0
,1 ? #6;" POSICAL ewatrana1 [RED
WAN]"
1880 POKE 87,7 POKE 88,20 POKE 89,120:
COLOR 1 POKE 708,136:POKE 709,204:POKE
 710,54 POKE 712,170
1890 PLOT 0,0 DRAWTO 0,61 DRAWTO 159,6
```

```
MTOP:GOSUB 3000
2010 A1$="                    ":? #6;"Enter 1st person's nam
e" GOSUB 3100 A1$ A$="":"
2020 ? #6;"Enter Birth-date" GOSUB 3200
 D1=D M1=M Y1=Y
2030 IF ERR THEN GOSUB 3500 ERR=0:GOTO
 2020
2040 GOSUB 3600 IF ERR THEN ERR=0 GOTO
 2000
2050 ? CHR$(125) A2$="                    ":? #6;"Enter 2nd
 person's name" GOSUB 3100 A2$ A$ A$="                    "
2060 ? #6;"Enter Birth date" GOSUB 3200
:D2=D:M2=M:Y2=Y
2070 IF ERR THEN GOSUB 3500 ERR=0 GOTO
 2060
2080 GOSUB 3600 IF ERR THEN ERR=0:GOTO
 2000
2100 IF D1=D2 AND M1=M2 AND Y1=Y2 THEN
  ? :? #6;"SAME DATE"  FOR SEL=1 TO 200
NEXT SEL GOTO 2100
2110 IF Y1>Y2 THEN GOSUB 2170
2120 IF Y1<Y2 THEN 2180
2130 IF M1>M2 THEN GOSUB 2170
2140 IF M1<M2 THEN 2160
2150 IF D1>D2 THEN GOSUB 2170
2160 GOTO 2100
2170 D1=D1:D2=D2:M1=M1:M1=M2:M2=M1:Y1=
Y1:Y1=Y2:Y2=Y1:RETURN
2180 CLOSE #1 GOSUB 4000 GOSUB 4200
2200 POKE 560,195:POKE 561,6 POKE 755,
0
2210 POKE 709,42 POKE 709,110 POKE 710
,0 POKE 711,202 POKE 712,0 ? CHR$(125)
2220 POKE 87,2 POKE 88,1 POKE 89,148 P
OSITION 1,0 ? #6;"Compatibility Y"
2230 ? #6;" -  --  -- ---" ? #6
2240 ? #6;"[INVERSE]--- --',CINT(ABS(PP
)*10+0.5))/10
2250 ? #6;"[WHITE]      ',CINT(ABS(EP
)*10+0.5))/10
2260 ? #6;"[CHIP]      ",(CINT(ABS(MP
)*10+0.5))/10
2270 ? #6;"[WHITE]   -  " ;(CINT(ABS(DP
)*10+0.5))/10
2280 POKE 87,0 POKE 88,160,POSITION 2
1:? #15 ? #15
2310 POSITION 1,5 ? "Press  C  for mor
e compatabilities" ? "        M' to re
turn to menu' LIN=2120 GOTO 5000
2320 K=PEEK(764) IF K<>16 AND K<>32 TH
EN 2120
2330 POKE 764,255:POKE 87,2 POKE 88,0
2340 FOR I=3 TO 6:POSITION 15,I ? #6;"
     " NEXT I
2150 POKE 87,0 POKE 88,160 FOR I=0 TO
9 POSITION 0,I ?
                    :NEXT I
2360 GRAPHICS 0 IF X=17 THEN DF=0 GOTO
 270
2370 IF DF THEN PL=3:ML=M1:YL=Y1:DF=0
2380 POKE 755,2 POKE 709,12 POKE 710,1
12 POKE 712,112
2390 POKE 756,PEEK(106)-8 OPEN #1,4,0,"K
":GOTO 2050
2000 POKE 694,0:IF PEEK(16)<>127 THEN P
OKE 16,(PEEK(16)-128)
2010 RETURN
2020 POKE 85,PEEK(85)-1 ? " ",:POKE 85
,PEEK(85)-1
2030 IF I=0 THEN RETURN
```

```
1000 GRAPHICS 0 POKE 755,2 POKE 709,12
 POKE 710,112 POKE 711,112 POKE 756,88
MTOP:GOSUB 3000
1010 ? CHR$(125) ? "Enter Birth-date "
GOSUB 1200
1020 D1=D:M1=M Y1=Y IF ERR THEN GOSUB
1500 ERR=0 GOTO 1010
1030 POSITION 2,0 ? 'Enter today's dat
e" GOSUB 1200
1040 D2=D M2=M Y2=Y IF ERR THEN GOSUB
1500 ERR=0 GOTO 1030
1050 IF Y1>Y2 THEN 1080
1060 IF M1>M2 AND Y1=Y2 THEN 1090
1070 IF D1>=D2 AND M1=M2 AND Y1=Y2 THE
N 1090
1080 GOTO 1100
1090 GOSUB 3500 GOTO 1010
1100 GOSUB 3600 IF ERR THEN ERR=0 GOTO
 1010
1110 GOSUB 4000 DAYS=DAYS-D1 GOSUB 420
0 YR=Y2-Y1 NO=INT(DAYS/365) IF M1-Z AND LP3 THEN
 NO=NO-1
1120 LP=0 OPEN #2,4,0,"S:" GET #2,DEG:POKE
 756,RAMTOP
1130 POKE 560,112 POKE 561,0 POKE 87,1
 POKE 88,0 POKE 89,120
1140 POSITION 1,0 ? #6;"CALCULATING 3 MONTH
S YR POKE 87,7
```

```
3 PLOT 0,31 DRAWTO 159,31 COLOR 2 PLOT
 2,15 DRAWTO 4,15
1200 PLOT 3,14:DRAWTO 3,16 PLOT 2,47 D
RAWTO 4,47
1210 CL=23 PC=(160/CL)*PM G=1:GOSUB 13
00
1220 CL=20 PC=(300/CL)*EM G=2 GOSUB 13
00
1230 CL=13:PC=((60/CL)*MM G=3 GOSUB 13
00
1240 POKE 87,0 POKE 88,44,POKE 89,119
POSITION 4,0 ? 'Press any key to retur
n to menu" LIN=1250 GOTO 5000
1250 GET #1,K CLOSE #1
1260 POKE 87,1 POKE 88,0 POKE 89,128:P
OSITION 3,0 ? #6;'                '
1270 POKE 87,7 POKE 88,20 ? #6;CHR$(12
5) CLOSE #2 GOTO 270
1300 PC=INT(((PC*3.14159)/180)*COS(DEG
/CL
1310 COLOR G PLOT X-SIN(PC)*PC,Y+COS(PC
)*PC
1320 FOR I=0 TO 16 STEP 2
1330 X=INT((CL*SIN(DEG))+2.5):Y=INT((C
L*COS(DEG))+2.5):SOUND 0,Y,12,4
1340 DRAWTO X,Y NEXT I SOUND 0,0,0,0 R
ETURN
2000 GRAPHICS 0 POKE 709,12 POKE 710,1
12 POKE 712,112 POKE 755,2:POKE 708,84
```

PRDGRAM BREAKDOWN

100 – 260	Read the data into variables and the Display List data into page 6
270 – 420	Display the menu screen
450 – 480	Find the end of the program display
1000 – 1110	Enter information to be used in calculating the bio-curve
1120 – 1340	Display bio graph screen and draw the curves
2000 – 2160	Enter information for calculating bio-compatibility
2200 – 2310	Display bio compatibilities screen
3000 – 3070	Control keyboard entries
3100 – 3160	Accept name input
3200 – 3380	Accept date input
6000 – 4100	Calculate the difference between the two dates
4200 – 4290	Calculate cycle phases in terms of days and avoid numeric overflow errors
4300 – 4330	Calculate bio-compatibility as per-centages
5000 – 6170	Play a tune
9000 – 9160	Set-up the new character set

```
3000 IF [illegible] N=3 I=I-1:N=0:C(I-2)
AND (H(10))-(I-2) AND (H(10))*IF I=0
THEN I=1 N=1 POKE 85,1
3020 IF I=1 AND A$ (INCH INS=5(05(0) IN
S(N)="    "
3030 IF I = 2 AND ME THEN INS STR$(MO IN
S(N)-"    "
3070 RETURN
3100 I=0:0=3 ?
3110 IF N(1 THEN N=1 POKE 85,1
3120 GOSUB 3000 GET #1 K IF K<>155 THEN
 ? RETURN
3130 IF N)17 THEN ?  ? "Name too lon
g please re enter' ?  GOTO 3100
3140 IF (K(65 OR K)122) AND K()32 AND
K()126 OR (K)90 AND K(97) THEN 3120
3150 IF K=155 THEN O=0 I GOSUB 3020 GO
TO 3110
3160 ? CHR$(K)  N$(N) CHR$(K) N=N+1 GO
TO 3120
3180 I=1 N=1 0<>0 ME=0 ? "Enter date
in the form DD/MM/YYYY' ?
3210 IN$ '0'
3220 IF I=1 000 0=5 THEN 3270
3230 TRAP 3260 POKE 702,60 GET #1,K
3240 IF K 126 THEN N N-1 GOSUB 3020 GO
TO 3220
3250 IF K(47 OR K)57 THEN 3220
3260 ? CHR$(K), IF K()47 THEN IN$(N,N)
 STR$(K) N=N+1 GOTO 3220
3270 ON I GOSUB 3300,3320,3340.IF ERR
THEN RETURN
3280 N 1 I=I+1.IF I)3 THEN RETURN
3290 GOTO 3210
3300 D=VAL(IN$) OR 0 IF D(1 OR D)31 TH
EN 3260
3310 RETURN
3320 M=VAL(IN$):ME 0 IF M(1 OR M)12 TH
EN 3260
3330 RETURN
3340 Y=VAL(IN$) IF LEN(IN$)()4 OR Y(17
72 THEN 3260
```

This is one of hundreds of programs now available FREE for downloading on MicroLink

```
3350 RETURN
3360 GOSUB 3600 TRAP 40000:RETURN
3600 ?  ? "Invalid Date!" EAR 1 RETU
RN
3500 ?  ? "Incorrect Entry!  FOR OEL
=1 TO 500 NEXT OEL ? CHR$(125) RETURN
3600 ?  ? "Is this correct (Y/N) ",
3610 GET #1 K IF K()78 AND K()89 THEN
3610
3620 IF K=78 THEN FOR I
3630 RETURN
4000 DAYS (Y2-Y1)*365
4010 FOR I Y1 TO Y2 LPI I=(INT(I/4)*4)
 LP2-I-(INT(I/100)*100)
4020 IF LP1=0 AND LP2()0 THEN DAYS=DAY
S+1 IF I Y2 THEN LP1=19
4030 NEXT I
4040 IF Y2 (INT(Y2/4)*4)=0 AND Y2=INT
(Y2/100)*100)()0 THEN 4070
4050 M1=BY(M1)+D1-1 M2 BY(M2)+D2-1
4060 DAYS DAYS-M1+M2 RETURN
4070 FOR I=1 TO 12:BY(I)=BY(I)+1 NEXT
 I
4080 M1 BY(M1)+D1-1 M2 BY(M2)+D2-1
4090 DAYS-DAYS-M1+M2
4100 FOR I=1 TO 12 BY(I) BY(I)-1 NEXT
 I RETURN
4200 DEYS DAYS
4210 IF DAYS)31993 THEN DEYS=DAYS:MO 2
1:GOSUB 4430
4220 PM=DAYS-INT(DAYS/231*23
4230 IF DEYS)31993 THEN I=DAYS:DAYS DE
YS DEYS-2
4240 IF DAYS)31976 THEN DEYS=DAYS MO=1
0 GOSUB 4400
4250 EM=DAYS-INT(DAYS/28)*28
4260 IF DEYS)31970 THEN I DAYS:DAYS-DE
YS DEYS-I
```


SUNARO

PO BOX 78 MACCLESFIELD CHESHIRE SK10 3PF
Telephone (0625) 25228

ATARI ROMS

Battle Zone	14 95
Donkey Kong Jnr	12 95
Final Legacy	12 95
Joust	12 95
Moon Patrol	12 95
Ms Pacman	12 95
Robotron	12 95
Tennis	8 95

ATARI BUDGET CASSETTES

180	2 95
BMX Simulator	1 95
Boulderdash	2 95
Boulderdash II	2.95
Decathlan	1 95
Dizzy Dice	1 95
Football Manager	2 95
Footballer of the Year	2 95
Four Great Games II	3 95
Four Great Games II (disc)	5 95
Grand Prix Simulator	1 95
Henry's House	1 95
League Challenge	1 95
On Cue	2.95
Panther	2 95
Rockford	2 95
Speed Ace	2 95
Spooky Castle	1.95
Steve Davis Snooker	1 95

ATARI CASSETTES

Ace of Aces	8 50
Arkanoid	7 95
Atari Aces	8 50
Four Star Games II	8 95
Basil Mouse Detective	8 50
Colossus Chess IV	8 50
Druid	8 50
Football Fortunes	12 75
Four Star Games I	8 95
Gauntlet (54K)	8 50
Deeper Dungeons	4 95
International Karate	5 95
Jewels of Darkness 64K	12 75
Kennedy Approach	8 50
Leaderboard	8 50
Leaderboard Tournament	4 95
Little Devils	8 95
Living Daylights	8 50
Mirax Force	8 95
Nightmare	8 95
Phantom	8 95
Platform Perf 64k	8 50
Shoot em Ups	8 50
Silent Service	8 50
Silicon Dreams 64k	12 75
Spy Vs Spy II	8 50
Spy Vs Spy III	8 50
Tomahawk 64k	8 50
Trivial Pursuit	12 75
Winter Olympiad 88	8 50

ATARI DISKS

Alternate Reality II	16 95
Autoduel	16 95
Basil Mouse Detective	12 75
Druid	12 75
F 15 Strike Eagle	12 75
Flight Simulator II	39 95
Football Fortunes	15 95
Four Star Games I	8 95
Four Star Games II	8 95
Gauntlet 64k	12 75
Deeper Dungeons	6 95
Guild Thieves 64k	16 95
Jewels Darkness 64k	12 75
Kennedy Approach	12 75
Knight Orc	12 75
Leaderboard	12 75
Leaderboard Tournament	8 95
Little Devil	8 95
Living Daylights	12 75
Mirax Force	8 95
Mini Office II	16 95
Nightmares	8 95
Pawn 64k	16 95
Pirate Barbary	8 95
Silent Service	12 75
Spy Vs Spy II	12 75
Spy Vs Spy III	12 75
Tomahawk 64k	12 75
Trivial Pursuit	16 95
Winter Olympiad 88	12 75

ORDER VIA MicroLink 72 MAG00222

Please add 50p handling to all orders under £5
Cheques/PO's payable to SUNARO SOFTWARE (AU)
Girobank Transcash to account 664 6838

ACCESS

SUNARO

◀ From Page 17

```
4220 IF 00Y5)11577 THEN 0EY5-00Y5 MD I
3.G0SUB 4400
4200 MM-00Y5-INT(00Y5/33)*33
4290 IF 0EY5)31577 THEN I=00Y5 00Y5 0E
Y5 0EY5 I
4100 PP=100-ABS((200/33)*MM)
4110 EP=100-ABS((200/33)*EM)
4120 MP 100-ABS((200/33)*MM)
4130 OP (00S(PP)+00S(EP)+00S(MP))1/1 0E
TURO
4400 00Y5=00Y5/MD-LOT(00Y5/MD1 00Y5 IO
T((00Y5*MD)+0 61 0ETURO
5000 POKE 764 255 GOTO 5050
5010 FOR M=1 TO T 0E00 V0 V1 V2 V3 50U
ND 0,V0,10 0 50U00 1,V1,10,0 50UND 2 U
2,10,0 50UND 3 V3 10 0
5020 FOR OEL L TO 5 IF PEEK(7647)>255
THEN POP GOTO 5100
5030 0EN1 0EL NEKT M 0ETURO
5040 RE5TORE 6000 T=0 G0SUB 5010
5050 RE5TORE 6010 T 5B:G0SUB 5010 VER5
=VER5+1 LF VER5 2 THEN 5080
5060 TF VER5 3 THEN VER5 0 GOTO 5090
5070 GOTO 5040
5080 T=72 GOSUB 5010 GOTO 5050
5090 RE5TORE 6170 T=5 G0SUB 6010
5100 FOR M=0 TO 1 50UND M,0-0,0 NEKT M
 GOTO 6IN
6000 0ATA 0,0,0 197 120,0 0 0,0,0 0 0
144 0 0 0 153,0 0,255,0 0 0 0,177 0 0
204 0 0 0 0
6010 0ATA 151 0 0 197 0 0 0 0 120 151
0,0 126 0 0 0 114 144 173 255 0 0 0,
0,0,0,0,96 0 0,0
6020 0ATA 96 114,151,177 0,0 0 0 0 05 0
0,0,0,0 0 0 0,102,0,128,0 0 0 0 0 0 0,
0,0 0 0,0
6030 0ATA 0,0,0,151,0 0,0,0,05,102,120
 0,05 102,120 0,0,0,0,153 96,0,0,0 0 1
14 126 162 0,0 0 0
6040 0ATA 114 0 0 171,114,0,0,0 0,144
0,0,120,0,0,0 0,0,0,255,0 0 0 0 0 144
173,0,0 144 173,0
6050 0ATA 0 0,0 153,0 0,0,0 0 120,0,0 0
120 0 0 0 114 0 0,162,0 0,0,0,0,116,0,
0,96 0 0,0
6060 0ATA 96 114,144 171,0 114,144 0,0
5,0 0 0 0 0-0 0 0,102,121 144 72 102 1
21,0 72,102 121,0 05 0 0 0
6070 0ATA 26,102,120 151,0 0,0,0 76 10
2,120 0 0,0 0 120 05 102,144,255,76,0,
0,0,05,0 0 255 96 120 161,0
6080 0ATA 0,0 0 0 191,64 0 0,0 57,0 0,0,
80,0,0,0 47 0 0 255 45 0 0 0 42 0 0 0,
40,0 0,0
6090 0ATA 17 42 50,241 0 0,0 0 0 0 0 0
,0,0,0,0,0 0 0,220,0 0 0,0,17 42,50,0,
0,0,0,0
6100 0ATA 17,42 0 115 17 42 0 0,0,0,0,
0,15,42,0,0,0 0 0 204 0 0 0 0,0 5,0,0,
0 0,0,0
6110 0ATA 0 0,0,102 28 0 0 0 28,0,0,0,
0 0 0 0 33 17 0 191,17 45 0,0,0,45 57,0,
0,50 64 0,0
6120 0ATA 57 0 0 204 64 76 0 0 76,91,0
,0,05 102-0,0 31 114 0,228 102 128,0,0
,188 140 0 0 114 153,0,0
6130 0ATA 0 0 0 126 05 96 114 0,0 0 0,
0 0 0 0 0 0,0 120,0,0,0 0 05 96,114
0 0 0 0 0
6140 0ATA 05 30 0 121 05 96 0 0,0 0,0
0 01 96 114 0 0 0,0 114 0 0 0 0 0,0,0
0 0 0 0 0
6150 0ATA 25 11 0 215 23 10,0 0-20,20
0,0 11,42 0,0 26 13 0 120 25 11 0 0 0 59
,47 0 0,33 45 0 0
6160 0ATA 11 42 0 241,47 57 0,0-45,52,
0 0 47,50 0 0 0 50 64 0,255,52 50,0 0,57
,72 0 0 0 50 76 0 0
6170 0ATA 191,0 0 0,60 0,0 0 64,0 0,0
47 0 0 0 0 0,0,0
5000 RAMTOP=PEEK(106) 0 POKE 106 RAMTO
P 4 VAOR PEEK(134)*PEEK(135)*256 5TA50
 PEEK(104)*PEEK(105)*256
5010 OFF5ET 00MTOP*256-5TA00 NI IUFIOF
F5ET/250) L0-OFF5ET NIX256 POKE V000+2
,L0 POKE U50*45,NI
5020 C5$(1),80)-"0000000000000000000000
0000(A@ 8@_ H I 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
0000 0000 0000 0000
5030 C5$(0) 1601= "
0000(0000000000000000(CCCCC0@@A
0000)0)0)0
```

PICTURE PUZZLE

ALAN BATES presents a highly entertaining routine for jigsaw fans

OVER the years many programs have been written that load 62 sector uncompressed picture files and then allow you to alter them. However, none of them has ever let you to simulate a jigsaw puzzle

Jigsaw is a program which does just that. When it is first run you are presented with the title page – shown in Figure 1 – that tells you how to alter the colours of the picture once it has been loaded.

Next you are prompted to place a disc containing AtariArtist picture files into a drive. Pressing any key will give you a directory of the disc – only files with the extension .JIG will be displayed.

You are prompted for the number of pieces – 8, 32 or 128 – you want the jigsaw to consist of and once the picture is loaded you press Return for the computer to juggle the pieces.

A square cursor appears on the screen above the top left hand pieces and it can be moved using a joystick plugged into port one.

Place the cursor over the initial piece to swap and press fire. Now move it to the place you wish to swap it with and press fire again. If you have moved to the correct place within the jigsaw you'll hear a beep.

When the whole puzzle has been completed correctly the computer displays a short message and then returns you to the disc directory section of the program.

That's all there is to it – so have fun making jigsaws with your favourite pictures.

Keys	Function
0-3	Select colour
C	Changes the selected colour
- =	Change a colour's luminance

Figure 1. Colour selection options

```
10 REM JIGSAW
20 REM BY A. BATES
30 REM (C)ATARI USER
40 ? CHR$(125):? "PLEASE WAIT"
50 GOSUB 770
60 GOSUB 660
70 GRAPHICS 8:POKE 82,1
80 POSITION 17,1 ? "JIGSAW POSITION 9
,2 ? "Uses Atariartist files ? "Inser
t picture disk then press any key
90 POKE 764,255
100 ? "GET #2,A OPEN #1,8,0,"D1:*.JIG
110 TRAP 120:INPUT #1,FILES ?      ,F
ILES(13,18) GOTO 110
120 POKE 84,PEEK(106)-1 ?

150 CLOSE #1 ? ? ? "Enter Atariartis
t filename, FILES="D1: "INPUT AS FILE
$(4) "AS FILES(LEN(AS)+4)-".JIG
155 ? CHR$(125) SETCOLOR 2,0,0
140 ? "Jigsaw sizes available" ? ?
11 8 pieces " 23 32 pieces " 5) 12
8 pieces
145 ? ? "ENTER YOUR CHOICE 1,2 OR 5
150 INPUT N N=INT(N) IF N<1 OR N>3 THE
N 150
160 TRAP 150
170 OPEN #1,4,0,"I:GRAPHICS 24 POKE
 559,0 A=USR(ADR(LE$)) CLOSE #1 IF X>=
128 THEN ? "Error ";X " on disk GOTO
110
180 YC=12 XC=16 YB=12 XB=52 IF N 1 THE
N YC=68 XC=40 YB=55 XB=64
190 IF N=2 THEN YC=24 XC=28 YB=24 XB=5
4
200 POKE 205,BB/(B+N) POKE 204,96/N IF
 N=3 THEN POKE 205,4:POKE 204,24
210 POKE 703,4
220 BP=PEEK(88)+256*PEEK(89)-1 HE=PEEK
(204) WI=PEEK(205) N=0
230 FOR Y=1 TO HB PS(1,Y)=" " NEXT Y
240 FOR Y=0 TO 192-HE STEP HE
250 FOR X=0 TO 40-WI STEP WI
260 PS(((Y/HE)+10)+X/WI+1)=CHR$(N) N=N
+1
270 NEXT X NEXT Y POKE 559,42:POKE 764
,255 OS PS
280 POKE RR,C+L P=PEEK(766) L=L+((P=14
)+2)-((P=15)+2) IF L=-2 THEN L=14
290 IF L=16 THEN L=0
300 IF P=51 THEN RR=708 GOSUB 650
310 IF P=30 THEN RR=709 GOSUB 650
320 IF P=26 THEN RR=710 GOSUB 650
330 IF P=50 THEN RR=712 GOSUB 650
340 IF P=255 THEN 280
350 SOUND 0,10,10,1 IF PEEK(53775)=24
1 THEN 550
360 IF P=10 THEN C=C+16 IF C=256 THEN
C=0
370 POKE 764,255 SOUND 0,0,0,0 IF P<>1
2 THEN 280
380 POKE 559,0
390 FOR Y=0 TO 192-HE STEP HE
400 FOR X=0 TO 40-WI STEP WI
410 T1=INT(RND(0)*(192/HE))*HE X1=INT(
RND(0)*(40/WI))*WI T=BP+X1+T1*40 F=BP+
X+Y*40 N USR(ADR(SWS),F,T)
420 U=(((Y/HE)+10)+X/WI+1) V=(((Y1/HE)
+10)+X1/WI+1) N=ASC(PS(U,U)):P$(U,U)=P
$(V,V) PS(V,V)=CHR$(N)
430 NEXT X NEXT Y
440 POKE 559,42
450 X=XB Y=YB N=1
460 POKE 53248,X V=USR(ADR(MS),R+T2,R+
T)
470 S=PEEK(652) X=X+((S=7)-(S=11))*XC
N=N+(S=7)-(S-11)
480 Y2=Y Y=Y+((S=15)-(S=14))*YC N=N+((
S=15) (S=14))*10
490 IF X<50 THEN X=X+XC N=N+1
500 IF X>196 THEN X=X-XC N=N-1
510 IF Y<15 THEN Y=YC N=N+10
520 IF Y>101 THEN Y=Y-YC N=N-10
530 SOUND 0,0,0,0 POKE 77,0
540 IF PEEK(6442)=1 THEN 460
550 IF PEEK(6443)=0 THEN 550
560 IF J=0 THEN J=1 POKE 53249,V V=USR
(ADR(MS),R+128+YT,R+128+Y) XX=X YY=Y N
1=N GOTO 460
570 TF=INT((N-1)/10)*40+ME+BP XF=((((N-
1)/10-INT((N-1)/10))*10)+WI
580 YF=INT((N1-1)/10)*40+ME+BP XT=((((N
1-1)/10 INT((N1 1)/10))*10)+W1
590 V=USR(ADR(SWS),YF+XF,YT+XT) POKE 5
32,9,0 J=0 B=ASC(PS(N1,N1)) PS(N1,N1)=
PS(N,N) PS(N,N)=CHR$(B)
600 IF PS(N1,W1)=PS(N1,N11 OR PS(N,N)
PS(N,N) THEN SOUND 0,96,10,14
610 IF PS<>PS THEN 460
620 FOR V=255 TO 0 STEP -1 SOUND 0,V,1
0,14 NEXT V SOUND 0,0,0,0 POKE 53249,0
630 FOR V=1 TO 500 NEXT V GRAPHICS 0 ?
 ? " CONGRATULATIONS ! " ? "You have
completed this JIGSAW
640 ? "PRESS ANY KEY TO CONTINUE" P
OKE 764,255 GET #2,V GOTO 70
```

Turn to Page 20 ▶

◄ From Page 19

```
650 C=INT(PEEK(RR)/16)*10 L=PEEK(RR)-C
RETURN
660 GRAPHICS 17
670 ? #6;"                    " ? #6
680 ? #6;"FOLLOW THE BUILT INTHSTRUCT
IONS TO LOADA PICTURE     #6
690 ? #6;"  ONCE THE PICTURE   HAS LOAD
ED USE THE  FOLLOWING KEYS TO  CHANGE
 THE COLOURS     #6
700 ? #6;"  SELECT COLOUR
710 ? #6;"  CHANGE COLOUR
720 ? #6;"  CHANGE LUMINANCE ? #6 ?
 #6
730 ? #6;" return TO CONTINUE"
740 GET #2,A
750 RETURN
760 GOTO 760
770 DIM LB$(177),SW$(61),FILE$(17),A$(
81),PS(80),QS(80),RS(32) POKE 106,PEEK(
106)-16 B=PEEK(106)*256+512
780 POKE 53277,2 POKE 559,62 POKE 5427
9,PEEK(106)
790 FOR I=B TO 256 POKE I+R,0 NEXT I
800 POKE 704,200 POKE 705,52 POKE 625,
0
810 FOR X=1 TO 117,READ N:LB$(X)=CHR$(
N) NEXT X
820 FOR X=1 TO 61 READ N SW$(X)=CHR$(N
)-NEXT X
830 FOR X=1 TO 32 READ N MS(X)=CHR$(N)
 NEXT X
840 OPEN #2,4,0,"K:" RETURN
850 DATA 216,104,173,68,2,24,105,3,133
,203,173,69,2,105,0,133,204,160,0,177,
203,201,79,208,21
860 DATA 169,78,145,205,165,203,24,105
,2,133,203,165,204,105,0,133,204,169,0
,240,14,201,15,208,6
870 DATA 169,14,145,205,24,,4,201,45,2
40,17,165,203,24,105,1,133,205,165,204
,105,0,133,206,169,0
880 DATA 240,194,162,16,169,2,157,66,3
,169,0,157,73,5,165,88
890 DATA 89,157,69,3,32,86,228,189,67,
5,133,212,169,0,133,213,96
900 DATA 216,104,104,133,206,104,133,2
05,104,133,208,104,133,207,166,206,164
,205,177,207,72,177,207,145,205,104
910 DATA 145,207,136,208,243,165,207,2
4,105,40,133,207,165,208,105,0,133,208
,165,205,24,105,40,133,205,165,206
920 DATA 105,0,133,206,104,133,205,1
04,133,208,104,133,207,169,0,168,0,145
,205,136,208,251
930 DATA 104,104,133,206,104,133,205,1
04,133,208,104,133,207,169,0,168,0,145
,205,136,208,251
940 DATA 169,255,160,0,145,207,136,208
,251,96
```



10 CP1 (Y)	150 CE4 (H)	310 Y61 (H)	470 QXN (6)	630 F4Y (Y)	790 BND (B)
20 CP2 (S)	160 ROS (K)	320 YJS (T)	480 X1E (B)	640 2HT (J)	800 2XR (N)
30 CP3 (X)	170 HZ4 (6)	330 YNE (T)	490 VWK (I)	650 VAU (X)	810 VDG (E)
40 05M (S)	180 RMG (N)	340 32M (E)	500 HUU (B)	660 X16 (S)	820 052 (D)
50 RFM (7)	190 6PT (6)	350 J9P (3)	510 UH9 (7)	670 T5C (S)	830 VJI (U)
60 KRP (6)	200 VAQ (J)	360 E3S (B)	520 BNJ (O)	680 46F (1)	840 UFL (4)
70 AKW (2)	210 S2Q (S)	370 8T9 (2)	530 GVP (B)	690 RY1 (Y)	850 JVK (E)
80 RPP (M)	220 MNC (1)	380 T51 (F)	540 LAE (A)	700 WRY (2)	860 P3F (S)
90 SJ8 (P)	230 S60 (8)	390 QPR (6)	550 L6F (8)	710 UYK (-)	870 N69 (A)
100 116 (J)	240 62R (7)	400 M8X (9)	560 DF1 (F)	720 7RW (U)	880 AWW (P)
110 UXL (J)	250 NEV (D)	410 22J (K)	570 AGV (W)	730 HAN (H)	890 669 (V)
120 UMU (S)	260 53U (H)	420 210 (1)	580 PSC (S)	740 6N2 (S)	900 EAC (S)
130 XNH (R)	270 174 (4)	430 ODW (E)	590 YUP (O)	750 R1C (G)	910 BAS (A)
135 N9K (M)	280 DW9 (1)	440 SVA (R)	600 SJ7 (B)	760 RSE (T)	920 V9J (J0)
140 K41 (9)	290 R1A (N)	450 OE9 (J)	610 9LY (W)	770 NU8 (K)	930 K37 (9)
145 AKP (C)	300 Y5W (P)	460 6Q8 (S)	620 C6F (C)	780 RUT (P)	940 ABS (J)

How to get your Atari to talk to a BBC Micro

(or a Spectrum or a Commodore or an Amstrad or an IBM ... or ANY other computer)

Language problems become a thing of the past when you join MicroLink. Now you can use your Atari (plus your telephone) to send messages to any other computer user, with no restriction on make of machine – or even on distance.

MicroLink *electronic mail and much, much more!*

P.O. BOX 94 HEREFORD HR4 9TU

SOFTSCAN

TRANSFER YOUR GAME TAPES TO DISK!! Both single and multi stage cassette games can be converted to disk using **THE ALCHEMIST** tape to disk transfer system. Even 'dodgey' cassette only 5804s! Why endure slow and error prone cassette loads? Send for a copy today!

THE ALCHEMIST (D) @ ONLY £10.95 Post Free

REMARK 5804S BACKUP? The **DISK TO-DISK PLUS** utility will copy many of those unprotected disks, including disks that use CRC-error BAD-SECTORS for protection! The utility also features a TAPE TO DISK TRANSFER utility, a DISK TO TAPE TRANSFER utility, and a TAPE TO TAPE COPIER, offering a comprehensive backup system at an affordable price!

DISK TO-DISK PLUS (D) @ ONLY £10.95 Post Free

REDUCE CASSETTE LOADING TIMES!!! In addition to automatic copying of cassette games **TURBOCHARGER XL/XE** also offers you **TURBOSAVE!** The utility re-saves game tapes to an ordinary blank cassette – and the duplicated game will LOAD FASTER THAN THE ORIGINAL!!! The original game tape is unaffected.

TURBOCHARGER XL/XE (C) @ ONLY £9.95 Post Free

SEARCH PROTECTED GAME TAPES with THE BINARY TAPE EDITOR! As well as copying cassette games, the BTE will enable you to actually LOOK at the programs and even alter them so you enjoy them. Saves the game to an ordinary blank cassette

BINARY TAPE EDITOR (C) @ ONLY £8.95 Post Free

SPECIAL OFFER – buy TURBOCHARGER and THE BINARY TAPE EDITOR together and we will throw in THE CASSETTE DUPLICATOR, a tape copier written in LIST'ed Basic

SEARCH PROTECTED GAME DISKS for hidden text etc **THE SECTOR INSPECTOR** is a disk investigation aid that enables you to LOOK at the actual disk program and edit the software if you wish

SECTOR INSPECTOR (D) @ ONLY £7.95 Post Free

TAPE-TO-DISK MENULOADER – a SPECIAL OFFER package of TWO useful utilities at a NEW LOW PRICE!!! The **TAPE TO-DISK** utility will transfer any single-stage machine-code game to disk. **MENULOADER** is a menu driver that will create TEN games onto ONE disk – the games are then selected from a menu screen

TAPE TO-DISK MENULOADER (D) @ ONLY £12.95 Post Free

BASIC AUTOLOADER will convert any Basic program on cassette into a boot-load version enabling you to load your own programs in the same manner as commercial games – just switch START and SWITCH-ON!! Give your programs a touch of class!

BASIC AUTOLOADER (C) @ ONLY £7.95 Post Free

THE PROGRAMMERS UTILITY PACK – is a suite of powerful utilities designed to assist in game design and creation. The Pack achieves everything you need to write games on the Atari XL/XE in machine-code or Basic. **LIMITED OFFER!** We are currently supplying a **FREE** copy of **THE SOUND FX DESIGNER** disk with each P.U.P. sold. Please request this limited offer! (The Sound FX Designer is also available separately @ £7.95 (D)).

PROGRAMMERS UTILITY PACK (D) @ ONLY £22.95 Post Free

DISCOUNT PRICES ON ATARI XL/XE GAMES – VCS 2600 CARTS ATARI ST SOFTWARE – WHY PAY MORE?! – PHONE OR S.A.E. FOR DETAILS

MINI OFFICE II £17.95/SILENT SERVICE (C) £9.95/ (D) £13.95/LEADERBOARD (C) £8.95/ (D) £13.95/TOMAHAWK (C) £8.95/ (D) £13.95/ATARI VIAL PURSUIT (C) £13.95/ (D) £17.95/ MINAJ FORCE (C) £7.95/ (D) £9.95/DRUID (C) £7.95/ (D) £9.95/PHANTOM (C) £7.95/ (D) £8.95/JEWELS OF DARKNESS (C&D) £13.95/F-15 STRIKE EAGLE (C) £8.95/ (D) £13.95/ COLOSSUS CHESS 4 (C) £8.95/ (D) £13.95/AGE OF ACES (C) £8.95/ (D) £13.95/

All prices include postage (UK) Overseas customers please add £2 to your total order. For further information just drop us a line enclosing a S.A.E. Cheques and P.O's should be made payable to SOFTSCAN

FREE with any order over £20 TEN GREAT GAMES on disk. This offer should be requested and is strictly limited offer



OVER the last couple of months we have been outlining a problem for you to solve – together with some hints on how to go about writing a program to give the required answer

I asked you to test out a roulette gambling strategy To bet on the red numbers and, if you lost, to keep doubling the bet until you won Many of you will have written your own routines to solve the puzzle, and mine is shown below It follows the method described last month, but is just one of the infinite ways that you may have approached it

If you've solved the problem in a completely different way we'd like to see it, so send it to

Mailbag, Atari User, Europa House Adlington Park, Adlington Macclesfield SK10 4NP

We'll give £10 for the best solution that matches exactly the problem as it was originally defined in the March issue of Atari User

I HAVE kept the program to solve the gambling problem simple When run, an evening at the roulette table just flies by Line 100 defines how much money you have in your pot, with line 110 setting the size of the initial bet If you like, you can put input statements in both those lines to vary the amounts when run We can keep track of the largest bet we have placed with the variable *LBET*

Next we read in all the red numbers from the DATA statements into the array *RED()* The casino might close before we are through so the total number of spins of the wheel possible is tracked in the variable *TSP* Similarly the number of spins actually used is recorded in *SPIN* A logic variable *BUST* indicates if we have enough money to cover our bet and line 210 sets up the victory pot – the amount we have when we decide to give up for the night

So now we enter the casino and

In the third part of this series Mike Cook presents his solution

start our first cycle of bets Line 330 generates the random number as a result of spinning the roulette wheel Lines 340 to 370 see if we have won and then we must take the appropriate action if we have won or lost If we have won we add our winnings to our pot and end the current cycle of bet doubling If we have lost we need to double our bet if we have enough money – if not we are bust

Then if the casino is still open we can place our bet again After a winning cycle of bets we decide whether to call it a night or carry on

So there you have it You can see whether you will win I made an adjustment to the program to run it continuously – keeping a count of how many nights I won and lost I kept a record of 1,000 spins of the wheel and won 531 times

However, before you rush off to win a fortune consider a few more points First of all most casinos have house rules which limit the maximum and minimum bets and some tables limit the number of times you can double your bet. In addition you will have to subtract your entrance fee and any drinks you buy from your winnings Some casinos might not get through as many as 200 spins a night, so you will have to change that


Finally, it is rather a slow and boring way to make money It's much better to hone your programming skill and make that pay

So are you ready for next month's Programmers' Challenge?

```
10 REM PROGRAMMER'S CHALLENGE
20 REM THE SOLUTION
30 REM TO THE PROBLEM
40 REM (c)ATARI USER
50 GRAPHICS 0 SETCOLOR 2,0,0
60 POSITION 2,2 ? "PROGRAMMER'S CHALLE
NGE " ?
70 POSITION 2,3 ? "
" ?
80 ? "THE ROULETTE WHEEL
90 ? "(c)ATARI USER
100 POT=100 TRUE= 1 FALSE=0
110 BET=1
120 LBET=0
130 REM NOW INITIALISE RED NUMBERS
140 DIM RED(18)
150 FOR A=1 TO 18 READ X
160 RED(A) X
170 NEXT A
180 DATA 15,4,2,17,6,13,11,8,10,24
190 DATA 33,20,31,22,29,28,35,26
200 VIP=POT*2
210 TSP=200
220 SPIN=0
230 BUST=FALSE
240 REM NOW ENTER THE CASINO
250 REM A NEW CYCLE OF BETS
260 BET=FBET
270 REM THE LOOP RETURNS HERE
280 SPIN=SPIN+1
290 POSITION 2,10 ? " SPIN NUMBER ",SPI
N "
300 ? "YOUR BET IS ",BET,
310 IF BET>LBET THEN LBET=BET
320 TSP=TSP-1
330 A=INT(RND(0)*37)
340 WIN=FALSE
350 FOR A=1 TO 18
360 IF S RED(A) THEN WIN=TRUE
370 NEXT A
380 IF WIN=TRUE THEN ? "YOU WIN
390 IF WIN<>TRUE THEN ? "YOU LOSE "
400 IF WIN=TRUE THEN POT=POT+(BET*2).5
GOTO 440
410 REM WE MUST HAVE LOST TO BE HERE
420 BET=BET*2 BUST=TRUE
430 IF POT>BET THEN POT=POT-BET BUST=F
ALSE
440 ? " YOU HAVE $ POT,
450 IF WIN=TRUE THEN 490
460 IF BUST=TRUE THEN 490
470 IF TSP=0 THEN 490
480 GOTO 270
490 REM DO WE EMBARK ON ANOTHER ROUND?
500 IF BUST=TRUE THEN 540
510 IF (POT>=VIP) THEN 540
520 IF (TSP=0) THEN 540
530 GOTO 240
540 ? "THE LARGEST BET PLACED WAS $",L
BET
550 END
```

Missing in Oxide

Load and save errors? LEN GOLDING gives answers to prayers with a verify utility



THE Atari cassette system is beautifully designed and always works perfectly every time. And if you believe that you'll believe anything.

How often have you typed in a long program and CSAVEd it only to find later that there's a fault on the tape? A cassette file can be tested in only one way – by trying to load it. But this destroys the original program in memory so if the file happens to be faulty you've lost all your hard work.

All kinds of things can go wrong. The connecting plug may have worked loose, especially since terminals are fitted to only five of the 13 pins. There may be dead spots on the tape – perhaps from too much re-recording – and some tapes designed to record music are inherently unreliable when used for computer data.

The cassette unit itself can develop hardware faults – keys get stuck, heads get dirty or drift out of alignment and drive capstans develop flat spots – especially if you leave the recorder for long periods with Play locked down.

On some older computers there's a bug in the operating system which interferes with the cassette handler routine – the usual fix for this is to do an LPRINT before saving anything to cassette and ignore the ERROR 138.

There's even the possibility of pilot error – you might have forgotten to plug the recorder in or, on 410 models, left the power supply disconnected, or neglected to press both Play and Record.

The cassette handler has no way of knowing what, if anything, is plugged into the serial port – you could attach an electric toothbrush, for all it cares.

Whatever the cause, the result is likely to be ERROR 143, described in the manuals as a Dataframe checksum error and in more colourful language by users who have to endure it.

This little autoboot program provides an answer. It simulates the CLOAD or LOAD "C:" or ENTER "C:" commands, without disturbing the contents of memory. You will hear the bleeps and whistles from the TV speaker just as though the file was loading as usual, and any problems are therefore easy to detect.

But if a fault occurs your original Basic program will still be there in memory, so you can keep on trying until you produce a perfect copy.

Making the autoboot cassette file is very easy – Program 1 does it all for you. Lines 20 to 140 are identical to

```
10 REM Program 1  Creates an Autoboot
cassette file containing the Verify ro
utine
20 BFR=(PEEK(106)-24)*256 REM reserve
a safe area at the top of RAM as a tem
porary buffer
30 FOR X=0 TO 46 READ D POKE 1536+X,D
NEXT X REM Load the new SAVE routine i
nto page 6
40 DATA 104,104,133,204,104,133,205,10
4,133,206,104,133,207,162,16,160,11,15
7,66,3
50 DATA 165,203,157,68,3,165,204,157,6
9,3,165,205,157,72,3,165,206,157,73,3
60 DATA 32,86,228,96,67,58,155
70 REM Load the program temporarily in
to the reserved buffer space
80 X=0 RESTORE 150
90 READ D IF D>-1 THEN 120
100 POKE BFR+X,D X=X+1 GOTO 90
110 REM Now read the data from the tem
porary buffer  nto an Autoboot cassett
e file
120 OPEN #1,8,128,C
130 X=USR(1536,BFR,PEEK(BFR+1)*128)
140 END
150 DATA 0,2,8,7,13,7,169,68,141,2,211
,24,96,169,134,141,231,2,169,7
160 DATA 141,232,2,169,148,141,208,2,9
6,104,208,8,104,104,168,128,48,2,169,0
170 DATA 162,112,157,75,3,169,3,157,66
,3,169,4,157,74,3,169,131,157,68,3
180 DATA 169,7,157,69,3,32,86,228,48,3
9,162,112,167,7,157,64,3,169,255,157
190 DATA 68,3,169,3,157,69,3,169,128,1
57,72,3,169,0,157,73,3,32,86,228
200 DATA 16,224,140,138,7,192,136,240,
5,169,158,141,252,2,162,112,169,12,157
,66
210 DATA 3,32,86,228,169,3,141,15,210,
96,0,67,58,155, 1
```

10 CR1 (Y)	80 ERR (W	150 DYH (S)
20 42U (9)	90 GFR (W)	160 RPS (R)
30 VMO (7)	100 21F (S	170 KKV (G)
40 8FW (3)	110 CYS (G)	180 R07 (4)
50 RFZ (1)	120 1V1 (F)	190 GY6 (X)
60 J7K (U)	130 3V9 (2)	200 138 (0)
70 CP7 (Z)	140 BK1 (P)	210 W3S (A)

Listing 1. Autoboot creator

those used in several previous cassette autoboot routines we explained in our articles in *Atari User*, so you may already have a file with them on. The DATA at lines 40 to 60 holds the autoboot creator code and lines 150 onwards contain the Verify routine itself.

Type in Program I and – with fingers crossed – CSAVE a copy. Insert a blank fully re-wound cassette and run the program. After a few seconds you will hear the familiar double beep. Now follow the usual CSAVE procedure and the machine code routine will be written to cassette in autoboot format. From now on you'll use this new tape, so Program I shouldn't be needed any more. But keep it in case you've made any typing errors and need to change it later.

Before you can use the Verify routine however it has to be loaded into memory. Re-wind the tape with the autoboot program on it, switch power off then switch on again while holding down the Start key. When the single beep sounds, proceed as for CLOAD and the autoboot program will install itself before Basic takes control, changing the screen border colour to prove it.

Incidentally, if you don't like the colour change, replace the 148 at line 180 with 0 and make a new autoboot tape. You can always double check that the routine is installed, by typing PRINT PEEK(1821) – the result should be 104.

You can now carry on programming just as though the new routine wasn't there. When you've finished use the usual CSAVE, SAVE"C:" or LIST"C:" commands, and your program will be saved to tape.

Now's the time to check that it's a good copy. If the file was made using CSAVE, then type X=USR(1821). This simulates CLOAD, with its short inter-record gaps. If you used SAVE"C:" or LIST"C:", then type X=USR(1821,1). This lets the routine work with long inter-record gaps, to simulate LOAD "C:" or ENTER"C:".

In all cases the file is loaded 128 bytes at a time into the cassette buffer. A top notch Verify routine would check each byte against the Basic program in memory. However, this would make the code much more complex, and greatly increase the autoboot loading time. Apart from which it's extremely rare for just one or two bytes to be corrupted – if the file will load at all, it's almost certain to be a good copy.

To keep things simple and minimise typing, we've taken the soft option – our routine simply reads the file and does nothing with it. During the reading process you will hear the usual sounds from your TV speaker, so any problems are easy to detect, and any fault will produce an extra loud beep. When the test is either successfully completed or aborted the cassette motor is switched off and control passes straight back to Basic which prints the usual READY message.

If you're desperate to discover what type of error occurred, you can find out by typing PEEK (1922). An error-free file will leave 136 here, but any fault will insert its own identity number – usually 143.

Once you have a cassette copy which tests out successfully you should be safe to try loading it back into your micro's memory using CLOAD, LOAD"C:" or ENTER"C:" as appropriate. The Verify routine does not need to be in memory for this operation, though it can be if you wish. And that's all there is to checking that you've made a good copy of your program on your tape.

HOW THE PROGRAM WORKS

If you're into machine code you might like to take a look at the source listing. If nothing else, it will remind you what a cassette autoboot file looks like. The header starts with 0, then contains the file length in 128-byte sectors, followed by the load address and initialisation address.

On power up, and before Basic takes control, the operating system does a JSR to the sixth byte after *LOADADR*. This puts it at *COLDST* where the cassette motor is turned off and the Carry flag cleared to indicate a successful boot.

The RTS at line 300 returns control to the operating system, which then does a JSR to the initialisation address. This resets *MEMLO* and changes the screen border colour to let you know that the routine is installed. Pressing Reset repeats the JSR to *INIT*, reinstating the new *MEMLO* and border colour values.

The RTS at line 380 hands control to Basic, leaving the rest of the machine code routine safely tucked away and ready for your USR command.

The USR routine itself starts at line 410 with a PLA to detect whether or not a parameter was inserted. If not, it assumes that the file to be checked uses short IRGs. If any parameter was passed then long IRGs are selected. The specified mode is programmed by storing either *$80* or *$0* into the second auxiliary byte of *IOCB #7*. We chose this IOCB since it's the one used by the operating system for most external I/O transactions.

Lines 630 to 750 load the file, 128 bytes at a time into the area reserved for cassette I/O – *CASBUF*. So long as no error occurs, the 6502 processor's Sign flag remains at zero until the end-of-file. Consequently line 750 will loop back for another chunk of data. When the reading process stops for any reason the Sign flag is set, so the routine drops through to *ENDTST* with the error number automatically stored in the 6502's Y register.

If it's error *$88* – end of file – everything is alright, so we exit via *CLOSEIT* without beeping the speaker. If the error number is anything other than *$88*, lines 810 and 820 simulate the pressing of Control+2 on the keyboard, and this produces a beep. The error number is copied into *ERRHOLD* at address $782 – decimal 1922 – in case you need to inspect it when Basic gets control again.

The last few instructions from 840 to 890 close *IOCB #7* and ensure that there will be no continued whistling from the speaker when cassette I/O is finished. Control is then handed back to Basic by the final RTS.

```
 0 CASBUF=$3FB
 2 CH=$2FC
 3 CIOV=$E456
 4 CLOSE=$0C
 5 COLOR4=$2C8
 6 EOL=$9B
 7 GETCHR=$07
 8 ICAX1=$34A
 9 ICAX2=$34B
10 ICDAL=$344
11 ICBLL=$348
12 ICCOM=$342
13 ICCE=$7B
14 COLDADR=$E477
15 MEMLO=$2E7
16 OPEN=$03
17 PACFL=$E3B2
18 SKCTL=$020F
19 **LOADADR
20 ,
21 HEADER
22   BYTE 0
23   BYTE FINISH-LOADADR+127/128
24   WORD LOADADR
```

Turn to Page 24 ▶

Listing I: Machine-code version of Program I

◄ From Page 23

```
0250   WORD INIT
0260 COLDST
0270   LDA #$3C          Turr cassette
ontor off
0280   STA PACTL
0290   CLC               Ind cage su ce
ssful boot
0300   RTS               End of 1st sta
ge boot
0310 INIT
0320   LDA #FINISH#255   Reser MEMLO ro
 protect
0330   STA MEMLO         the area of RA
M containing
0340   LDA #FINTSH/256   our machine co
de
0350   STA MEMLO+1
0360   LDA #$94          Change border
 colour, to
0370   STA COLOR4        show routine i
s installed
0380   RTS               Return to Basi
c
0390 ;
0400 VERCOBE
0410   PLA
0420   BNE L5TFORM       Branch if no p
arameter
0430   PLA
0440   PLA               Any parameter
nearns
```

```
0450   LDA #$00
0460   JNI OPENIT
0470 L5TFORM
0480   LDA #8            No parameter =
 Long IRG mode
0490 OPENIT
0500   LDX #IOCB         Open #7 to rea
d characters
0510   STA ICAX2,X       in appropriate
 IRG mode
0520   LDA #OPEN
0530   STA ICCOM,X
0540   LDA #$04
0550   STA ICAX1,X
0560   LDA #FILENMA255
0570   STA ICBAL,X
0580   LDA #FILENM/256
0590   STA ICBAL+1,X
0600   JSR CIOV
0610   BNI ERROR
0620 LOOP
0630   LDX #IOCB         Read file in 1
28-byte
0640   LDA #GETCHR       chunks into ca
ssette buffer
0650   STA ICCOM,X       but do nothing
 with
0660   LDA #CASBUFB255   the data
0670   STA ICBAL,X
0680   LDA #CASBUF/256
0690   STA ICBAL+1,X
0700   LDA #$80
0710   STA ICBLL,X
```

```
0720   LDA #0
0730   STA ICBLL+1,X
0740   JSR CIOV
0750   BPL LOOP          Branch if no e
rror
0760 ENDTST
0770   STY ERRHOLD       Store error nu
mber
0780   CPY #$88          $88 means end-
of-file
0790   BEQ CLOSEIT
0800 ERROR
0810   LDA #$9E          Any other erro
r number
0820   STA CH            beeps the spea
ker
0830 CLOSEIT
0840   LDX #IOCB         CLose #7
0850   LDA #CLOSE
0860   STA ICCOM,X
0870   JSR CIOV
0880   LDA #$03          Stop the whist
ling noise
0890   STA SKCTL         that sometimes
 occurs
0900   RTS               Return from US
R call
0910
0920 ERRHOLD
0930   BYTE 0
0940 FILENM
0950   BYTE C ,EOL
0960 FINISH-+
```


ATARI 8 BIT DISK PUBLIC DOMAIN SOFTWARE – ALL £2.50

TURBO BASIC (XE/XL only) delete lines saves delete then Auto Renum, Hidden Defining Inc. DOS operations delete from delete delete with a compiler that updates up Turbo delete by 3-5 times and Atari Basic by 10. 5 screen scrolled program Renumber you in autoboot handling programs, delete Defining, extra mouse jump handling commands inc., undo, paint, fill, wipe, replace, repeat and more, delete with an enhanced set of extra and text delete. FANTASTIC VALUE.

ADVENTURE COMPANION Only want what you want to solve by operations how insert in autoboot step by step autoboot in Dark Crystal, Curthness, Island Tears, ultrasonic Castle to the Galaxy delete, Island of the Sun, Mystery Fortresse, Defence Renown Pyramid in Egypt, Pirate Adventure, Extreme and Colorfast.

PIX IT – (Translator) An autoboot 1 autoboot for the 130XE/XE that loads in the original Datafile compound system replacing you to run the older incompatible new Defender. When used in autoboot mode that program gives you an extra 40 id user port by replacing high mem. to be lomem Extreme

XE COPIER AND ATARI FILE DEVELOPER the XE copier is a one pass single replace or two pass loaded version delete delete. The A / D means on any item with 128K or more. If Defender you in the habit file copying to you don't have to, compress a delete disk or copy disk one by one & you want more than one but not all the disk system Also loads the program you can format, look, unsave and delete files.

TEXTPRO 100% Defender code INCREMENTED SHEET that is jumps to more one loaded three pages of the lomem commands/ INFO. All the Defender you delete delete from a two jumping program including not auto delete loaded auto replace, auto saves and a full appended macro feature so that your program's loops with Defender commands. Colour compiler with 2 lomem2 not be delete/ out on the 8 bits.

QUEST FOR POWER A commercial database program now Defender the the Atari Defender. You Sample a Knight will in the form of Defender and Ring delete with defend a database that be in your way and challenges to overcome.

ALL 8 DISK Compatible with Sed and 3 but delete Trapdoor Between single and two loaded replace delete of file or better copying jumps disk duplicator.

TRIVIA QUIZ A 100% Defender Language trivia game. Delete on the delete and Defender a program for jumps your own questions.

GAMES Delete A / Ai Ma hung it a brilliant downhill jetting game for up to Sed replace. Two rapid and loaded autoboot and jumps jumps in the great archery game. Three Defender reverse Defender and an delete on that you can loaded also over from an duo-delete versus ROBBALINCATHERS 1 - autoboot on the then to loaded the most Defender of the Defender Dungeons. A Defender to add Defender delete to an enhanced Defender program with full Defender delete.

UTILITY Disk 2 Master Disk catalogue delete Defender loaded replacing and Base printing. Disk to Cassette replace for Atari Tapes PC to Atari from Tapes with more than memory loaded Disk TAUF is loaded in an loaded part of replace, jumps you loaded reboot, to Disk to files from Delete delete Defender. Delete any loaded one write & compress also Sed delete/ Writer delete/ Sed search but 3 bit put back

MANY OTHER PROGRAMS AVAILABLE

520 STFM £259.95

Inc. Mouse 5 P D Disks Basic Disk and Manuals

COMPUTER ACCESSORIES

5.25 Locking Disk Box Cap 50	£7.95
5.25" Locking D.B – Cap 100	£9.95
Special Offer – 2 5.25" 100 Cap LDBs only	£18.00
5.25" Disk Notcher	£3.50
5.25" Disk Cleaning Kit (Fluid)	£3.50
5.25" Disk Cleaning Kit (Dry)	£2.50
Copy Holder (Thing)	£4.95
Big x of 10 5.25" DS/DD 48 TPI Branded Precision Disks	£8.50
Tracker 10 SS/DD 48tpi Cased	£7.00
Tracker 10 DS/DD 48tpi Cased	£8.00

BOOKS

Atari 130XE Games Book	£3.95
Atari Graphics and Sound	£3.95
Atari Strategy and Tactics	£3.50
Get More from the Atari	£3.00
Making the Most of Your Atari	£3.95

Send full details of your Hardware and Software if you want a quote for a trade in against an ST.

DUSTCOVERS – PROTECT YOUR HARDWARE

Please specify model

1050 drive/1010/XC11/XC12 tape	£2.95
800XL/130XE	£3.95
1027/1029 printer	£4.50

520STM, SF314 1 MEG DRIVE

MOUSE BASIC DISK 5 PUBLIC DOMAIN DISKS 1ST WORD wordprocessor SPELL IT spelling checker and manuals

£329.95

5.25" Bulk Disks – Certified Error Free – No quibble replacement Lifetime Guarantee

	10 cased	25	50	100
SS/DD 48tpi	£5.50	£9.00	£17.00	£33.00
DS/DD 48tpi	£6.50	£11.00	£19.00	£36.00
DS/DD 96tpi	£7.50	£13.00	£21.00	£37.00

50 SS/DD 48tpi + 100 Cap LD box. . . £24.95

50 SS/DD 96tpi + 100 Cap LD box £25 50

75 DS/DD 48tpi + 100 Cap LD box. . . .£32 95

75 DS/DD 96tpi + 100 Cap LD box £33 95

Just write for more information. Cheques etc. payable to STORT SOFT (Internat. bankers add £5). Overseas orders welcome pounds Sterling by bank draft or International money order. Write for quote in your own currency.

STORT SOFT 0279 89500

ACCESS MASTERCARD/EUROCARD/VISA Accepted. CREDIT CARD ORDER LINE – 0279 89500 24 HOURS A DAY, 7 DAYS A WEEK – VAT & P.P. INC. NO HIDDEN EXTRAS – WHAT YOU SEE IS WHAT YOU PAY

STORT SOFT 0279 89500

"18 CROWN CLOSE, SHEERING, BISHOP'S STORTFORD, HERTS CM22 7NX

SoftwarE

Thunder from the heavens...

Product Thunderfox
Price £4.99 (cassette)
Supplier Atari Corp (UK)
Atari House, Railway
Terrace Slough Berkshire
SL2 5BZ
Tel 0753 33344

A HEAVILY armed enemy transporter ship is carrying Disilicate energy crystals for the approaching Phalon mothership

Once these have been installed in the deadly Phalon war machine they will turn it into the most powerful destructive force in the Universe Capable of destroying entire solar systems in minutes it must be stopped

You have been chosen to represent the Federation forces The new Thunderfox – an ultra sleek and incredibly manoeuvrable space fighter – has been given to you in a last ditch attempt to destroy this evil threat to mankind

All you have to do is locate the crystals and destroy them to stop the war machine from being finished They are situated inside the transporter and are guarded by the crystal guardian Obvious if you think about it

Your way into the transporter is restricted by two anti-gravity stabilisers located at the far right of the ship You must bomb each five times before it is destroyed – not an easy task even for an avid games player

It is very easy to run out of bombs while you're trying to knock out the stabilisers so an option to reload is built into the game

When you have used all your bombs fly to the far left hand of the transporter and land on your mothership where your supply will be refurbished

When you have destroyed both stabilisers fly to the left of the transporter and land on the pad You will then be transported to the bowels of the ship and enter the thermonuclear laser room

If you come into contact with any of the lasers or the walls you will be instantly disintegrated

Remember to watch the level indicator at the top of the screen The intense radiation generated by the lasers will destroy your Thunderfox if you take too long getting through

Once you manage to get past the lasers you enter the energy crystal room where the guardian is waiting for you

The Disilicate crystal is located in its head and you must shoot it 10 times to blow it up This is hindered by the mobile wall that moves up and down in front

The playfield uses a split screen and in the bottom quarter is the long range scanner – which indicates how close the Phalon war machine is to the transporter

This distance is constantly closing, so time is of the essence – don't mess around shooting enemy vessels that you can just ignore Also at the bottom of the screen is a status line showing your score lives remaining weapon in use and the current level


The main action takes place at the top of the screen

An extra ship is awarded for every 5 000 points scored and your total score is calculated depending on a number of factors such as destroying the guardian head and blowing up ground installations

The game is joystick controlled, allowing you four directions of movement – up down, left and right If you are travelling flat out when you push forward or backwards you will accelerate or decelerate relative to the movement

However when your craft is moving at its slowest speed, when you pull in the opposite direction it will flip over and reverse its travel

The fire button is used to activate the on board lasers



but it also switches from lasers and bombs when you hold it down and move in the opposite direction

The graphics are nice with locally scrolling The sound effects are well implemented and there is a catchy main tune

When your fighter launches from its hangar you get a superb side on view of it – an original feature Also when your craft is hit by enemy fire it doesn't explode straight away It plummets to the surface of the transporter – another nice idea

The game is quite difficult to get to grips with, but after the initial hiccups it got me hooked I would recommend Thunderfox to lovers of shoot 'em ups

Neil Fawcett

Sound	*7*
Graphics	*8*
Playability	*7*
Value for money	*6*
Overall	*7*

Winter frolics...

Program Winter Olympiad 88
Price £9.95 (cassette) £14.95 (disc)
Supplier Tynesoft Unit 3 Addison Industrial Estate Blaydon Tyne and Wear NE21 4DE
Tel 091-414 4611

COMING hot on the heels of the recent Winter Olympics is this new sports simulation from Tynesoft.

Although this style of game is now a little old hat and similar ones were on the scene at least 12 months ago – notably Winter Games by Epyx – this fresh product from Tynesoft has a lot going for it.

It kicks off with a lively rendition of the signature tune from the BBC Ski Sunday program then offers up to six players the chance to participate in any or all of five different events – the downhill race ski jump, biathlon slalom and bobsled.

Each player can represent any country from 12 given although this has little bearing on the game. The selection process is followed by a picture of the Olympic flame in full blaze and then it's on to the simulation itself.



The Downhill

All the events rely on judicious and timely joystick waggling to control the participant's movements and, sometimes speed.

In the downhill race you view your skier from behind as he prepares to hurl himself down the slope. The objective is to manoeuvre him in and out of trees and sundry obstacles and deposit him safely across the finish line.

It's not easy and, since you only get the one attempt mistakes such as creaming yourself on a sitka spruce are costly – not to mention probably fatal.

Next comes the ski jump. If you ever thought you could do better than Eddie the Eagle, now's your chance.

Your man shuffles out from a hut and positions himself at the top of the long and menacing ramp. Your view is from behind him. Then it's all systems go as he launches himself down the jump.

When he reaches take-off point the picture changes to give a side on view of the



The Skijump

competitor as he flies through the air.

Unless you manipulate your joystick correctly chances are the poor chap's legs and skis will go every which way and he'll make an ungainly landing usually face first.

Unlike Eddie the jumper doesn't get up and smile when he goes base over apex but instead beats the ground with his fists.

My skier must have had hands like raw beetroot by the time I'd finished because this is not one of the easier events to complete successfully, even though you do get three attempts at it.

The biathlon is somewhat boring and easy in comparison. It involves making two laps of a course on skis the course consisting of a couple of flat tracts – one past a lake complete



The Biathlon

with motorboat – a short uphill climb followed by a pretty bridge and then a short downhill run.

The view during this is from the side. However during each lap you have two opportunities to draw a bead with your rifle and hit five static targets – 20 targets and 20 bullets in all. Here the view is from behind the competitor.

The slalom is particularly difficult. Your view is from the side but moving downhill from right to left. You are supposed to weave



The Bobsleigh

past the appropriate poles but I found it only too simple to crash into the side barriers.

Finally comes the two man bobsled event. The sled is first pushed from left to right to the top of the run when the picture changes to give you a view looking down the run.

This is rather like Pole Position on ice with the run scrolling towards you and the background scenery whizzing across from side to side as you go round bends.

A small display in the bottom left of the screen shows an overhead view of the course.

The sled has a natural tendency to head up the banks of the trailer round bends and it's very hard to see that it doesn't flip over. The ride seemed to go on forever but this event turned out to be the easiest in my experience.

The game's main strength lies in the very picturesque graphics – lots of lovely Alpine scenery here for you to enjoy and some good animation, too. Sound effects and music are also used to the benefit of the game's atmosphere.

While the gameplay may not boast of anything new or novel and perhaps lacks lasting interest, there's no doubt that Tynesoft has done a good job on this one and you certainly get your money's worth of thrills and spills.

Bob Chappell

Sound	8
Graphics	9
Playability	8
Value for money	8
Overall	8

Two player destruction

Product Zybex
Price £2.99
Supplier Zeppelin Games
28 Osborne Road Newcastle upon Tyne NE2 2AJ
Tel 091 281 4401

AFTER taking a look at the pre-release version of Zybex in the March 1988 issue of *Atari User* I was delighted when the finished version arrived. Believe me it was well worth the wait.

The game revolves around the fate of two rebels Rinser and Cassalana. You control them in their bid to escape death row and execution – and before you think or say anything not the one in Alcatraz.

To do this you have to undertake an almost suicidal mission to the Czokan System.

Once there you have to visit 16 strange worlds and do battle with wave after wave of alien hordes.

If you survive you will be awarded a teleport crystal which allows you access to other planets in the system.

Eventually you will reach the restricted levels and the ultimate challenge – the Zybex itself.

As well as needing the crystals for access to the other planets you are also governed by how many tokens you have collected.

After completing the initial level it is possible to advance up to level 12 in any order you want without a token, but after that you will need three tokens to get to the restricted areas. These are awarded after the completion of a level.

If you survive and retrieve the Zybex the death rings – placed around your necks by your captors – will be removed.

To help you on the mission you have been given the Orbit weapon with its lowest power level.

As the mission progresses you can increase the destructive force of the Orbit by picking up debris of the same shape that appears on screen after you have blasted an alien wave.

Many different instruments of destruction can be collected including the Rail Gun, the 8 Way, the Wall and the Pulse.

Extra lives are awarded in the same way – simply fly over the spare man when he appears.

The game has an original shooting system. You have built in auto fire which allows you to select any of the weapons you have collected by pressing fire to stop through them.

In later stages you can have them all going at once – it was a real pleasure watching aliens explode all over the screen under a hail of laser fire.

Your weapons are displayed in two status screens that sandwich the main playfield – one for each player.

Another status line near the bottom of the screen shows lives remaining, score and which weapon you are using.

You can have both players on screen at the same time and [illegible] all of them.

The [illegible] a number of [illegible] with a [illegible] and super scrolling. The [illegible] stages [illegible] different planets have been beautifully designed.

Similar games are often criticised about the design and animation of the hero and aliens but Zybex doesn't suffer from any of these faults.

The animation and design of your player is excellent. He [illegible] jerk back as he fires his weapons and he swings and turns his legs as he thrusts upwards or accelerates.

Every alien wave that attacks you is animated in its own way. Some rotate and others pulse as they zoom across the screen.


The game caters for everything you would ever want. The high score table has a dual entry mode – two players with two joysticks can enter their names at the same time.


All game options are controlled using the joystick – all you need to do is simply highlight the icon you want on the main title screen and away you go.

One of my favourite features is the music. Several pieces are used throughout, but the main tune is so catchy I found myself whistling it all day.

A fine finishing touch to a wonderful shoot 'em up.

Neil Fawcett





The Czokan System – one of 16 worlds


Sound	10
Graphics	10
Playability	10
Value for money	10
Overall	10

Double trouble...

Program Double Pack I and II
Price £7.99 (cassette), £9.99 (disc)
Supplier Red Rat Software 11 15 Fennel Street, Manchester M4 3DU
Tel 061-834 4941

DOUBLE Pack I contains two games, Mad Jax and Planet Attack. In the first you control a car driving through horizontally scrolling scenery and your objective is to travel as far as possible

Out to stop you are a number of unsociable road hogs, which can either be shot or avoided



Madjax – mad joyriding

Various items along the roadway can be picked up by driving over them. These include fuel, weapons and a couple of objects which appeared to have no discernible effect on anything.

One of the weapons on offer is a rearward shooting cannon. Although I scored what appeared to be direct hits on vehicles behind me many times, not one of them blew up. Most upsetting.

There are two sections of road, desert and city. In the former there are the road hogs, while in the latter there are additional hazards in the form of moving road carriers.

To survive the city section you must have collected enough fuel during your drive through the desert.

I found the graphics all right but movement was perhaps a little on the slow side. The gameplay isn't varied or interesting enough to hold the imagination for long.

The two sections – although getting progressively more difficult – are rather short and, as far as I could see, repeated ad infinitum.

Planet Attack is the better game of the two. Earth is under attack from Tritanian forces which have established a base on Mars and are being kept in our time zone by the installation of Time Scalers.

It's your job to destroy these by attacking them from the ship Star Eagle, but you seem to have about as much chance of succeeding as Stockport County has winning the FA Cup.

Graphics are an improvement on Mad Jax. The background scrolls by on six different levels and gives a passable illusion of dimension in depth.

Forward progress of your ship is at a pre-set pace and movements available are up, down and sideways. Your relative position is indicated by your shadow on the ground.

Armaments available are forward shooting lasers to defend against attacking Tritanian Auto Droids, Space Cruisers and missiles.

The Star Eagle also has bombs which you can use to destroy ground installations, Tritanian settlements, radar sites and the all important Time Scalers.

Bombing a fuel dump increases your own fuel level, but if you do run out you can eject to safety. The game then continues as before, with you now controlling your ejector seat.

This amazing device also appears to be equipped with laser cannon and bombs and needs refuelling in the same way as your spaceship did.

After a short run – around 35 seconds – the landscape scrolls back to the launch pad and you must land your craft to gain bonus points. Re-launch for more of the same, but with additional hazards to contend with.

Double Pack II includes the games Space Wars and Dreadnought.

Space Wars really is looking a little long in the tooth. You control a spaceship at the bottom of the screen and have to fight off successive waves of aliens or meteors.

If you collide with one your shield loses effectiveness and the latter cannot be shot, but must be dodged.

This concept can still work if there is something in it to take it out of the ordinary and bring it alive. I didn't think Space Wars made that jump. The graphics are at





Planet Attack – rid Mars of the Tritans

best only average, response is a little sluggish and detection of a missile hit on the aliens seemed suspect at times.

The game's simplicity may appeal to younger children, perhaps just starting out on careers in Universe saving, but more experienced players will probably lose interest after a short while.

The other game Dreadnought is a sort of sub aquatic Dropzone. You control a submarine, blasting enemy subs and negotiating traps and underwater hazards.

You can move deeper into the water or towards the surface. Hitting the sea bed, or indeed surface waves costs you a life.

Horizontal speed can be delicately controlled and I found that I was more successful when resisting the urge to bolt round at a rate of knots blasting everything.

A slower pace made for more controlled accuracy and more reaction time if the enemy ships suddenly turned in front of you – as they had a habit of doing in the later stages.

Although not possessing the finesse, frenetic action or same quality graphics of Dropzone, Dreadnought is not a bad budget game in its own right.

Niels Reynolds

Pack I	
Sound	6
Graphics	7
Playability	7
Value for money	7
Overall	7

Pack II	
Sound	6
Graphics	7
Playability	7
Value for money	6
Overall	7

Kicking into touch...

Program Super Soccer
Price £9.95 (cassette), £14.95 (disc)
Supplier Tynesoft, Unit 3 Addison Industrial Estate Blaydon Tyne and Wear NE21 4TE
Tel 091-414 4611

WHEN all matches are off due to adverse weather conditions and Subbuteo sets have long since been strewn to all four corners of the loft, soccer fans might well be tempted to try a football game on their Atari.

Super Soccer gives you the opportunity to play a match against a team controlled by your computer or by another player.

Team colours can be cycled although both teams end up looking much the same and even the goalkeepers wear the same colours as their team.

You can choose which country you want to represent, but this seems to have no bearing on the game and is not referenced elsewhere – for example, the score board merely titles the sides as home and away.

Your view of the action is from the side with the pitch set against a backdrop of static spectators and ground-level advertisements.

The two teams – quite large figures – troop out, a whistle sounds and play begins. As players advance towards either goal – only a part of the pitch is visible at any time – the screen scrolls rather jerkily.

The player currently under control from each team is highlighted by a pair of brackets surrounding his head. Players and ball move slowly, particularly when two players are close to each other – essential when one player is trying to gain possession of the ball.

It is sometimes difficult to see who is who and quite what is going on.

The goalies can be controlled to a limited extent but only when the ball is nearby. At the press of the fire button, the appropriate one will immediately execute an unballetic dive.

The goalkeepers are likely to find themselves on the free transfer list before long – on several occasions they faced their goal when a goal kick was being taken.

I don't know if the invisible referee was off buying a packet of peanuts whenever it happened, but the teams have an unlawful habit of taking a goal kick when opponents are still in the goal area.

There is a good sporty opening tune, but apart from that and the piercing whistle, sound effects are lacking.

The roar of the crowd is nothing more than a constant hiss which rises and falls in volume in relation to the action and the ball boinks unrealistically when it bounces.

No much as I love football I really couldn't take to this game. It plays a little too slowly for my liking and didn't generate enough feeling of a real match. If it's a football simulation you want – I use this word because a graphical representation is not the same – you would be better off getting Addictive Games' ancient Football Manager – it's still the best soccer simulation.


But if you actually want to see 22 men running around a pitch you might give this one a try.

Bob Chappell

Sound	5
Graphics	6
Playability	5
Value for money	5
Overall	5




THE LATEST AND



ARCHON – ROM – £14.99 Joystick
A battle between the forces of light and darkness. You can't take a square you have to fight for it



BALLBLAZER – ROM – £14.99 Joystick
Can you shoot the Plasmorb through the moving goalbeams while piloting your Rotofoil? For one or two players



RESCUE ON FRACTALUS – ROM – £14.99
You have to rescue your friends from Fractalus – but the evil Jaggi aren't going to make it easy



TWILIGHT WORLD CASSETTE. £4.99
Battle your way through eleven dungeons and devils with anti matter pods and lasers

Atari have always had the greatest arcade games in the galaxy, now they're adding even more winners to the collection. From the high speed skills of handling a WW1 biplane, to the brain-aching Archon battle of wits. Whether you're landing the punches with Fight Night or using the awesome power of Thunderfox to blast the enemy, Atari give you the best combination of graphics speed and skill this side of Alpha Centauri.

ALL GAMES SHOWN ARE COMPATIBLE WITH: ATARI XE GAMES SYSTEM, ATARI


D THE GREATEST.



BLUE MAX – ROM – £14.99 (joystick)
The thrills of WW1 dogfighting and bombing raids

FIGHT NIGHT™

by Accolade



FIGHT NIGHT – ROM – £14.99 (joystick only)
Construct and train your own boxing champ then guide him to the championship. One or two players



THUNDERFOX CASSETTE. £4.99 (joystick)
The Zylostan war machine is complete. Can you beat the horrendous odds in your Thunderfox?



COMPILATION CASSETTE £4.99 (joystick or keyboard)
Five arcade favourites on one cassette. Centipede Star Raiders Missile Command Tennis Typo Attack

Then there is Atari's compilation cassette of all time favourites, which at only £4.99, makes it, you guessed it, the best value on Earth!

Pick the latest and the greatest from your Atari Dealer or fill in the coupon to order by mail

RI 65XE, 130XE, AND 800XL COMPUTERS.

Please tick title(s) required

Archon £14.99	☐	Pallblazer £14.99	☐
Rescue on Fractalus £14.99	☐	Fight Night £14.99	☐
Blue Max £14.99	☐	Twilight World £4.99	☐
Thunderfox £4.99	☐	Compilation £4.99	☐

Forward cheque/postal order for total amount accompanied by this order form to: Atari Corp (UK) Limited Atari House Railway Terrace Slough Berks SL2 5BZ

Name (Mr/Mrs/Miss)_____
Please complete using block capitals

Address_____

_____

_____ Postcode_____


Please allow 28 days for delivery


ATARI

AU 6 88

THE EIDOLON

by BRYAN STEVENS




LEVEL 5
LEVEL 6
LEVEL 7
ATARI USER
LEGEND
START
DRAGON
STALACTITE
DIRECTION OF RED FIREBALL
FORCE FIELD
JEWEL
FIREBALL

Your HINTS & TIPS

WE welcome letters from readers giving their help with games on the Atari that they would like to pass on to other readers The address to write to is

Hints and Tips
Atari User
Europa House
Adlington Park
Adlington
Macclesfield SK10 4NP

The Eidolon

THIS month s map on page 32 shows you the levels of Activision s entertaining game The Eidolon so to complement it here are some useful tips

● On the lower levels the Jewel Guardians are not very dangerous, but they can still drain your energy So when you approach one to wake it up, shoot your fireballs at it quickly while moving backwards

● If you do manage to get lost press P to pause the game and then refer to the map

● Shooting a blue fireball at a creature will freeze it but a green one will change it into something else But beware the monster it charges into may be more dangerous than the one you faced in the first place

● When you re fighting something dangerous and your energy level gets too low don t be proud – just run away Amass more energy by collecting fireballs and return for another go

● When confronting a dragon you can still collect the fireballs it spits at you by pressing the spacebar Unusual hint If you need both hands to hold your joystick take your shoes and socks off put the computer on the floor and use your left big toe to press the spacebar and your right one to press the P key

● If you collect all the jewels in the first five levels you can bypass all the creatures in levels six and seven That is if you don t get killed by a dragon in which case you lose all the jewels

● If you run out of time you will have to start again on level one So if time is running out you have two options Face any wall and shoot at it – the fireballs will rebound and kill you – or let a creature or dragon kill you

● On level eight collect as many jewels as you can to give you a high energy level Avoid all the red fireballs – you can t shoot them as the roof is too low

● Finally when you meet the dragon on level eight don t panic

Next month we ll introduce you to the demonic and strange monsters that inhabit the underground caves and tell you in detail how to kill them – **Bryan Stevens, Andover, Hants**



One of the dragons you encounter in the game

Universal Hero

FIRST of all you need to get the remote switch which can be found in what looks like a cart Go to the force field where the floppy disc is and use the switch, then get the disc

Next get to the tap on the surface and go as far as possible to the right You will see a white object sticking out of the cliff Use the tap to stop the fountain Now go all the way down the cliff and get the wire Go to the dynamite, near the start and down to the right

Get the plunger and go to the room with all the rocks piled up Use the plunger to clear the door

Go through this door and use the plug and the floppy disc When asked to identify yourself type SLARTIBARTFARST and the force door will now open Go through it to the pineapple

Get the oil and go to the fountain room Two screens on from this you will find a red machine Get the fuel and go to the spaceship but make sure that you have the ID card

Use the fuel and the ship will launch while you get ready for the next puzzle – **Gary Quigley, Finglas, Dublin**

Spy Hunter

WHEN the spy car is first placed on the road from the weapons van it can travel on the rough ground to the right of the screen – this normally causes your car to explode later in the game

To do this you must go forward at the slowest speed and pull right as far as the car will go

The noise is pretty bad but it gets you out of some pretty tight spots on the expert level

When the mad helicopter starts attacking the spy car watch for the small square on the side of it to flash before you move away Then unless you hit a screen boundary your car will not be destroyed

When one of the enemy vehicles goes under the helicopter wait until the chopper tries to drop a bomb and fire at the car Both of them will explode – **Andrew Patterson, Basingstoke, Hants**

Back to the Golden Age of Adventures

by Rouloc

WITH few new adventures being released for the 8 bit Atari just now, I suggest you rummage around in your sack and pull out a few of those golden oldies and revisit old acquaintances

And what better way to start with than with an Infocom adventure – there's so much in them that they always repay a return visit. The classic Zork trilogy should be high up on your list as should Planetfall, Deadline and Wishbringer.

For cassette owners I would recommend Level 9's Colossal Adventure for a replay. This is the best version of the famous Crowther and Woods original Colossal Cave adventure that I know and still gives me a real kick every time I go back to it.

One new adventure for 48k Atari machines has come to my attention but due to the fact that my disc drive has been showing signs of old age I have been unable to give it the Rouloc razor sharp review treatment. The game is OCI – Operation Computer Industry – and is produced by a company called Tearsoft.

The plot concerns one Professor Decker who has kidnapped a bunch of programmers attending a software conference. His plan is to hold them hostage while you go off and recover a folder which will prove that the professor's son was killed in a fighter test crash in 1980.

To keep the authorities at bay and the town clear while you accomplish your task, the professor has built an atomic bomb and has other aggressive tricks up his sleeve – no half-measures for this guy!

OCI is a text only adventure using a simple vocabulary. It costs only £1.99 on cassette and £2.99 on disc so you can't really go wrong. Copies are available direct from Tearsoft at Seawinds, Croft Road, Lochcarron, Ross Shire IV54 8YA.

Lots of help has been supplied by readers in response to Dave Hall of Sheffield's pleas for assistance with Alternate Reality: The Dungeon. Although Dave has since written to say that he is well on the way to solving all the secrets of this adventure, I think it would help other readers to print some of the advice received from those adventurers who have taken the time and trouble to write in.

David Lago of Burton Upon Humber says that he has found it better to start off with a new character as imported ones seem to get killed off too easily. He brought in a really good Level 11 character from the city but that too suffered the same early demise.

The progression of statistics is much better if you start off from scratch says David, and by using good weapons found in special places, you can have a better character at Level 5 in the Dungeon than by importing a higher level one from the City.

David recommends that if you find a silver key on a corpse or elsewhere, you should take it to the prison in the palace dungeon area. There you can free Acrissimird's assistant who will give you a spell called Temporal Fugue which speeds you up in combat, makes you hit harder and lets you pick up dropped weapons.

The oracle doesn't appear to know what your abilities are, but simply lists the quests in order. There's nothing for it but to keep on throwing in gold and listening. The first clue to the Gargoyle's riddle is SHIPWRECK and you can only cross the River Storm at midnight.

Susan Fairhurst of Ashton near Wigan, adds to this by saying that the other words needed to answer the Gargoyle's riddles are ORACLE and BLOODSTONE. She warns to take care as there is something nasty on the other side of the river.

Susan and others also advise that you check that you have version 2.1 as version 2.0 has two FBI agents that prevent you from transferring a city character to the dungeon.

Susan would like to know the solution to the three doors. She knows that going to the first three times opens the one to the corridor and going to door two shuts it – but what does door three do? The answer is something to do with two other minor quests – but does anyone know what?

Poet Laureate of the month award has to go to Dave Fox of Kemsing in Kent. He has sent in a number of

Turn to Page 36 ▶



◀ From Page 36

rhyming tips for The Dungeon For example

A beast with fangs and fearsome gaze,
Whose hide will stop the keenest blades
All forms of magic it withstands,
Yet thou might conquer with bare hands

Good, eh? What it actually means is that to gain the Bloodstone you must kill the Basilisk using the mirrored shield and your bare hands

In return for his magnificent poetic efforts the bard Dave Fox would like to know what is the Axiom of Truth in Ultima IV Can anyone help? And, in addition Dave Hall of Sheffield still has one question unanswered – what is the name of the Gargoyle?

Finally in response to requests from other readers including Chris Leighton of Sherwood in Nottingham and Andrew Merrett of Worthing Sussex, I have given some hints for Guild of Thieves and The Price of Magik

Until next month, exciting adventuring!

GUILD OF THIEVES

To cross the room of coloured squares starting on the black square follow the colours of the rainbow backwards – violet, indigo, blue green yellow orange and red – then move to the white square You should have noticed that WOBNIAR is the word Rainbow spelled backwards! To return across the room reverse the order

To enter the Bank of Kerovnia, you must place all the treasures in one of the night safes – the sign outside the bank will change depending on how many treasures have so far been deposited

The pick is used to get the chips of mineral from the rock face near the waterfall



PRICE OF MAGIK

To recover the sword stuck through the ceiling push the secret panel in one of the rooms – S then SE from the Misty Corridor – in the oak panelled corridor then pull the lever To read the inscription on the ceiling cast the fly spell on yourself

To deal with the glowing gateway, try giving any spell focus – the pendulum, for example.

ATARI USER MAIL ORDER OFFERS ATARI USER MAIL ORDER OFFERS

EXCLUSIVE OFFER

Power to your fingertips!

FREE WITH SUBSCRIPTION

Atari have developed an exciting range of credit card size calculators and databanks – and we've negotiated two exclusive offers for readers of *Atari User*

The CC81R ExecuCard is a five-function calculator with an eight character display showing a comma after every three digits It's solar powered only 1 8mm thick and comes with a protective wallet.

The DB2100R Data Bank stores 150 sets of data each with seven alpha numeric characters and 12 numbers There's a fast search facility a secret mode protected by a user defined password and an eight digit calculator Battery included

SAVE UP TO £7!



Product	RRP	Special reader offer	YOU SAVE	Price with subscription
Atari ExecuCard	£5 99	£4 99	£1	FREE
Atari Data Bank	£19 99	£16 99	£3	£12 99

Turn to page 61 to take advantage of this superb offer

OVER £600 IN PRIZES

NOW WE ARE THREE

This month Atari User is three years old and much has happened in the last 12 months The quality of software continues to improve as games players expect more and more from their computers Indeed Atari itself has launched an addition to its range with the Atari XE Games System

So to celebrate the success of the Atari as a games machine we are offering you the opportunity of winning



1st PRIZE

The Atari XE Games System consisting of keyboard, 65XE console light gun, joystick and built-in Missile Command You will also receive copies of the classic Flight Simulator II and Bug Hunt, which shows the potential of the light gun ***Value £119.99***

"A sophisticated games playing console with an amazing range of software and the possibility of upgrading to a full computer at a later stage"

André Willey, Atari User, February 1988

2nd PRIZE



From Tynesoft comes Winter Olympiad 88 This exciting new release comprises five games with first-rate graphics and excellent gameplay There are 15 copies to be won *Value £14.95 each*

Lots of lovely Alpine scenery for you to enjoy and some good animation too Sound effects and music are also used to the benefit of the game's atmosphere

Bob Chappell Atari User, May 1988

3rd PRIZE



15 copies of Mirax Force and Phantom – two more games of quality from Tynesoft *Value £9.95 each*

Mirax Force *"The sound graphics and superb scrolling complement each other with numerous levels featuring the very best of the Atari's graphic capabilities"*

Neil Fawcett, Atari User January 1988

Phantom *Character animation is superb both for spectre and your player character Phantom is original and well worth buying for the sheer pleasure of playing it*

Neil Fawcett, Atari User July 1987

WHAT YOU HAVE TO DO

Simply answer the following four questions, complete the entry form and send it to arrive no later than May 29, 1988

QUESTIONS

1. Which event did Eddie Edwards enter in the 1988 Winter Olympics?
2. In which year did Torvill and Dean win their last Gold Olympic medal?
3. How many GhostBusters were there by the end of the film?
4. Which film is famous for the phrase May the Force be with you'?

ENTRY FORM

ANSWERS.

1. _____
2. _____
3. _____
4. _____

Name _____

Address _____

_____

Postcode _____

I would like to receive *disc/cassette versions of my prize

(* Please delete the format you do not require)

Return to **Third Birthday Competition, Atari User, Europa House, Adlington Park, Adlington, Macclesfield SK10 4NP**

This Toolkit is a MUST!

ATARI USER exclusive!

Programming becomes so much easier when you've got the right tools for the job. With this *Atari User* package you can add TEN new commands to Atari Basic to dramatically improve your performance. *PLUS* your Atari will generate meaningful error messages instead of cryptic numbers.


Toolkit automatically boots in from cassette or disc and makes use of a normally unused area of memory.

This package of stunning utilities – specially commissioned by *Atari User* – is an absolute must. It comes complete with comprehensive on-screen instructions telling you how to get the most from each of the programs.



£5.95 tape
£7.95 disc

TO ORDER PLEASE USE THE FORM ON PAGE 61



HERE'S a very addictive game set in an abandoned mine which you explore in your UEV – Underground Exploration Vehicle. You descend from the top of each level – nine in all – avoiding radioactive stalactites, stalagmites, and evil ghosts on the prowl for victims.

A joystick plugged into port one controls the UEV's movements and the fire button accelerates it in case of trouble. You start the game with nine lives – and you'll need them – with extra ones being given as you enter levels four, six and eight. Touching walls, ghosts or various obstacles robs you of one life.

Once you've completed a level you are awarded a bonus which is calculated according to the time it took you – the quicker you do it the more you score.


Each successive level gets harder and some require a lot of thought before you can complete them. After you have finished press Start to begin again.

The layout for levels one to four can be found between lines 900 and 1090, with levels five to seven between 1550 and 1740. These routines use re-defined characters which makes it very easy to customise your own version of the game.

If you delete line 480 you can have infinite lives, while changing line 420 to read

```
420 RETURN
```

will remove all collision detection for your UEV and allow you to travel through walls and see the whole game from start to finish.



Level one of the game

```
10 REM MODE BORDER
20 REM BY STEPHEN WILLIAMSON
30 REM C64/128 USED
40 REM ENTERLIST
50 DIM SPC$(20):SPC$="
   " :REM 19SPACES
60 GRAPHICS 17+16:SETCOLOR 2,0,0
70 POSITION 0,20 ? #6;"MINE FOREMAN"
80 ? #6;"by Steve Williamson"
90 ? #6;"(c) 1985 ANTIC"
100 GOSUB 1560:GOSUB 2000
110 LEVEL=1:POKE 752,1:LIVES=9:POKE 70
0,70
120 SM=PEEK(88)+256*PEEK(89):GOSUB 112
0
130 REM READ MC ROUTINE
140 RESTORE 1770:FOR I=0 TO 283:READ A
:POKE 38000+I,A:NEXT I
150 REM SET UP VBI SYSTEM
160 PMB=36864:PL=PMB+1024:PL1=PMB+1280
:PL2=PMB+1536
170 RESTORE 1930:FOR I=0 TO 31:READ A:
POKE PMB+I,A:NEXT I
180 FOR I=0 TO 255:POKE PL+I,0:POKE PL
1+I,0:POKE PL2+I,0:NEXT I
190 POKE 53277,3:POKE 54279,104:POKE 5
59,62:POKE 623,1
200 RESTORE 220:FOR I=0 TO 14:READ A:P
OKE PL1+I+167,A:NEXT I
210 POKE 705,148:APOS1=53249:POKE APOS
1,100
220 DATA 60,126,254,214,146,186,238,23
8,238,254,124,60,60,56,56
230 M=USR(15556):REM INITIATE VBI ROUTI
NE
240 COLLF=53282:CRLLP=53278:GOSUB 820
250 SPEED=1536:UP=1537:UP 1536,DIR,154
0:POKE 1541,0
```

Turn to Page 42 ▶

ATARI **The leading North West Specialist ATARI Dealer**

LADBROKE COMPUTING INTERNATIONAL

33 Ormskirk Road
Preston, Lancs
Tel: (0772) 21474 (1 line)
(0772) 203166 (5 lines)
Out/Board 27236 6pm to 9am

ATARI

This Company has given years of full support to ATARI users Countrywide from their retail shop premises at Ormskirk Road, Preston. Now from their NEW Mail Order Depot they can offer the same Excellent service to all Mail Order Customers

All Software and Hardware is fully tested prior to selling This ensures Customers receive working items so that returned goods and all the attendant frustration are a thing of the past All Hardware is supported by our own 'ON SITE' engineers, therefore quick turn round on all repairs is Guaranteed All prices quoted are fully VAT Inc and there are no 'hidden extras', what you see is what you get Delivery Included in price Please ring for latest prices, new releases, etc

130XE Computer	£119 00
Disk Drive	Phone
XC12 Recorder	£32 00





	3½ D/S D/D	5¼ D/S D/D 48TPI
Per Disk	£1 99	£0 80
10 Disks	£16 00	£6 50
10 Disks+Plastic library case	£17 50	£7 50
100 Disks	£150 00	£60 00
500 Disks	£650 00	£280 00

All Disks are covered by an unconditional lifetime guarantee

TO ORDER Simply send, or phone your order, stating Full Name, Address, Visa or Access Nos, Cheque or Money order Make payable to Ladbroke Computing International, 33 Ormskirk Road, Preston, Lancs PR1 2QP



Our ATARI trained engineers will repair all Hardware in minimum time at competitive rates Please ring for a quotation All repairs carry a 90 day warranty

PRINTERS

Dot Matrix	
Star LC10	£220 00
NL10 Sheetfeeder	£55 00
National Panasonic	PHONE
MP165	PHONE
MP135	PHONE
LX86 Tractor Feed	£19 00
LX86 Sheetfeeder	£55 00
LQ800 24pin D/M	£525 00

All Printers, Disk Drives etc supplied with cables etc NO HIDDEN EXTRAS

DUST COVERS

Computers	£3 99
Monitors	£4 99
Disk Drives	£2 99
Printers	£7 99





We have a complete range of Software in stock and fully tested

IF IT'S AVAILABLE we have it! Send SAE for full catalogue

Any Software problems? Queries? give us a ring we usually have the answer

All Dedicated books and mags in stock

FOR MORE INFO CALL ON THE ABOVE NUMBERS OR SEND SAE AND STATE FULL REQUIREMENTS

See us on stand G14A at the Atari User Show, London 22nd-24th April



HOW DEBBIE MET A STRANGER!

'Desire' is like an intimate conversation on your PC screen! Just phone in and join in for hours of enjoyment There's no enrolment fee — just one phone call via your modem puts you through to a new world of handy services and fun things to do. Take a look at the menu

Charge Rate 36p inc. VAT peak & 25p inc VAT per min off peak

CHATTER BOX The interactive message board! Say what you want to say — stir up a hornets' nest, start up a friendship! See the immediate response!

MAILBOX A handy way to leave messages with friends.

DESIRE CLASSIFIEDS The perfect place to sell your old computers, or find a top computer job!

GRAFFITI CORNER Whatever you want to say, here's where to say it!

DEBBIE DESIRE'S PROBLEM PAGE Personal, emotional or sexual problems answered.


DESIRE
LONDON E14 9TW **PHONE NOW** 0898 555 555

◀ From Page 39

```
240 POKE 1542,0:SCORE=0:BONUS=0
270 REM INITIALIZE MOVEMENT
280 POKE SPEED,159:POKE AP,70:POKE VP,
26:POKE 0XE,1
290 REM
300 POKE 53278,8:A=USR(38213)
310 POKE 18,0:POKE 19,8:POKE 20,0:REM
SET TIMERS TO ZERO
320 REM MAIN MOVEMENT LOOP
330 A=USR(38000)
340 IF PEEK(VP)<25 THEN POKE VP,25
350 IF PEEK(VP)>192 THEN 370
360 IF PEEK(COLLP1)=0 AND PEEK(COLLP1)=0
 THEN GOTO 330
370 IF PEEK(COLLP1)<>0 THEN GOSUB 420
380 IF PEEK(COLLF)=8 THEN GOSUB 870
390 IF PEEK(COLLF)<>0 THEN GOSUB 420
400 POKE 53278,8 :GOTO 330
410 REM HIT WALL OR CEILING
420 IF PEEK(VP)>170 THEN POKE 53278,0
:GOTO 230
430 POKE HPOS,0
440 FOR M=28 TO 225:SOUND 0,M,0,14:NEX
T M
450 SOUND 0,0,0,0
460 FOR I=0 TO 28 POKE PL+PEEK(VP)+I,0
 :NEXT I
470 POKE 53278,0
480 LIVES=LIVES-1 :GOSUB 520
490 IF LIVES<2 THEN GOSUB 740 :GOTO 280
500 POP :GOTO 280
510 REM INCREMENT SCORE AND LEVEL
520 POKE HPOS,0
530 GOSUB 620
540 TIME=65536*PEEK(20)+256*PEEK(19)+
PEEK(18)/50:POKE 18,0:POKE 19,0 :POKE
20,0
550 BONUS=-20*(1000-TIME) :IF BONUS<0 TH
EN BONUS=0
560 SCORE=SCORE+BONUS
570 LEVEL=LEVEL+2.IF LEVEL=10 THEN LEV
EL 1
580 GOSUB 620:GOSUB 1120
590 GOSUB 790
600 GOTO 280
610 REM IF PLAY IKEO
620 POSITION 0,20 ? #6,SPC$ ? #6,SPC$
? #6,SPC$,
630 POSITION 0,20 ? #6;"LIVES";LIVES;"
  ";"SCORE",BONUS
640 ? #6,"LEVEL";LEVEL;" TIME";SCORE;
650 RETURN
660 REM SCORE DEC AND MOVE BAR IN RIT
H HAND
670 POKE SM+201,0 POKE SM+196,0
680 FOR N=64 TO 0 STEP -1
690 SOUND 0,N,10,12
700 NEXT N
710 IF LEVEL>7 THEN POKE SM+210,0
720 RETURN
730 REM GAME OVER
740 POSITION 0,22 ? #6;"GAME OVER"
750 SCORE=0:BONUS=0 LEVEL=1:LIVES=5
760 IF PEEK(53279)=7 THEN 760
770 GOSUB 1120 GOSUB 920 RETURN
780 REM ERASE MOVED/NOT SHAPE
790 FOR I=0 TO 28 POKE PL+PEEK(VP)+I,0
 NEXT I
800 RETURN
810 REM FIRESN LEVEL SOUND EFFECT
820 REM
830 FOR N 14 TO 0 STEP -2
840 SOUND 0,N*N,14,14:SOUND 1,N*N,14,1
2
850 FOR G=1 TO 100 NEXT G
860 NEXT N:FOR G=1 TO 50 NEXT G SOUND
0,0,0,0 SOUND 1,0,0,0
870 RETURN
880 REM RAISE JOLN OF LAD  LIVES ?
 TO 3
890 POSITION 0,0
```

This is one of hundreds of programs now available FREE for downloading on MicroLink

```
900 ? #6,"  ;;;;;;;;;;;;;;;;;;;;\";
910 ? #6,"{                    {",
920 ? #6,'{                    {";
930 ? #6,"{))))))))))))))))))  {",
940 ? #6,"{;;;;;;;;;;;;;;;;;;;;  {",
950 ? #6,"{                    {";
960 ? #6,"{                    {";
970 ? #6,"{ ))))))))))))))))))  {";
980 ? #6,"{  ;;;;;;;;;;;;;;;;;;  {",
990 ? #6,"{                    {",
1000 ? #6,"{                    {",
1010 ? #6;"{))))))))))))))))))  {";
1020 ? #6,'{;;;;;;;;;;;;;;;;;;  {";
1030 ? #6,'{                    {";
1040 ? #6,'{                    {";
1050 ? #6;"{   ))))))))))))))))  {";
1060 ? #6,'{   ;;;;;;;;;;;;;;;;  {",
1070 ? #6,"{                    {",
1080 ? #6;"{                    {",
```



```
1090 ? #6,"=>>>>>>>>>>>>>>>>>  >>",
1100 RETURN
1110 REM N OF 3 ARE4 CLEAR
1120 POKE 703,60 POKE 710,0:POKE 711,1
70 POKE 708,LEVEL*16+10
1125 IF LEVEL>4 THEN 1155
1130 IF LEVEL>7 THEN GOTO 1140
1140 IF LEVEL=1 THEN GOSUB 890.RETURN
1150 POKE SM+26,125 POKE SM+34,125
1160 POKE SM+49,126
1170 IF LEVEL=2 THEN RETURN
1180 POKE SM+189,125:POKE SM+192,125
1190 POKE SM+208,126:POKE SM+216,100
1200 IF LEVEL=3 THEN RETURN
1210 POKE SM+261,125 POKE SM+269,125:P
OKE SM+273,126
1220 POKE SM+288,126 POKE SM+250,126
1230 RESTORE 1270:FOR I=0 TO 14:READ D
POKE PL2+I+72,D:NEXT I
1240 POKE 706,12
1250 IF LEVEL<4 THEN LIVES=LIVES+1 GOS
UB 820:RETURN
1255 GOSUB 1540
1260 IF LEVEL=5 THEN RETURN
1270 POKE SM+283,125 POKE SM+287,125
1280 POKE SM+305,126
1290 IF LEVEL=8 SM+8 LIVES=LIVES+1 GOS
UB 820 RETURN
1300 POKE SM+293,126:POKE SM+115,126 P
OKE SM+32,125 POKE SM+250,120
1310 IF LEVEL=7 THEN RETURN
1320 REM
1330 REM LEVEL9
1340 FOR Y 25 TO 301 STEP 28
1350 FOR R=0 TO 17 POKE SM+Y+R,0:NEXT
R:NEXT Y
1360 IF LEVEL=5 THEN GOSUB 1400 POKE S
M+210,192 RETURN
1370 POKE SM+7,0 POKE SM+3,0
1380 FOR I=21 TO 242 STEP 28
1390 FOR L=0 TO 17 STEP 2
1400 POKE SM+I+L,125
1410 NEXT L NEXT I
1420 FOR Z=81 TO 102 STEP 28
1430 FOR L 1 TO 17 STEP 2
1440 POKE SM+I+L,125
1450 NEXT L NZRI I
1460 POKE SM+210,192
1470 IF LEVEL=8 THEN LIVES=LIVES+1 GOS
UB 820:RETURN
1480 REM LEVEL9
1490 FOR I=0 TO 703:L=INT(RND(0)*360) I
F PEEK(L+SM) 0 THEN POKE L+SM,INT(RND(L
)*12):NEXT
1500 NEXT I POKE SM+2,0 POKE SM+3,0
1510 RETURN
1520 REM SLOT *A ?  !SEEM C:FLAM  EV
EL 5 TO 7
1530 REM CONTROL CONNECTED ON LINE 260
5 IS REVERSE/CONDITION
1540 POSITION 0,0
1550 ? #6,"  ;;;;;;;;;;;;;;;;;;\";
1560 ? #6,"{)  )))))      ))))){";
1570 ? #6,"{,,  ,;;;       ,,,;{";
1580 ? #6;'{)  ))))   ))   ))  ){",
1590 ? #6,"{,   ,;   ;;;    ,{",
1600 ? #6;'{        ))      ))){";
1610 ? #6,'{;       ,,      ;,,,{";
1620 ? #6,"{)))))))))      )))))){",
1630 ? #6,"E,,,,;,,,,  ,;;;,;;{";
```

Turn to Page 43 ▶

ATARI

ATTENTION
ALL 1050
DISK DRIVE OWNERS

The 1050 I.S. Plate.

The ULTIMATE drive enhancement
from Innovated Software

DETAILS

Plug in high quality easily fitted PCB with
full fitting instructions
Now with full Happy compatibility
Improved drive speeds up to TWICE normal loading speed
Reduction of drive WEAR and TEAR
whole tracks can be stored in the PLATE's 16K of RAM
Supports Double Dual and Single densities
Sector SKEW is no longer required to obtain HI speed
Will run all available disk operating systems (DOS) including
SPARTADOS, HAPPY WARP SPEED DOS
AND OTHER HIGH SPEED SYSTEMS
The PLATE drive can also emulate other
drives via its massive on board RAM including
IS/US DOUBLER, STANDARD 1050 ARCHIVER,
HAPPY, LAZER AND WARP DRIVE.
HI SPEED reading and writing with special SIO gives
an increase in speed by a factor of SIX!!
Many special commands have been added to the SIO table

SOFTWARE DETAILS

Supplied with double sided menu disc
and a special HI SPEED menu
Built in diagnostic tester sector copier
and special backup menu

MANUAL

A comprehensive 30 page manual is supplied with
complete fitting instructions
and detailed information regarding software drive control
to allow you to access the full potential of the PLATE

All registered owners will be supplied with any software
updates etc for the price of a disk and return postage

Also supplied with
GREMLIN GRABBER III
The most comprehensive, HI-SPEED back-up utility disc on the market, complete with manual

This complete package

NOW ONLY £89.95 inc Post/Packing and 12 months warranty
A saving of £24.95 on previous advertised price!

Available only from

CHIPS

53 Bugby Road,
Worthing,
West Sussex,
BN11 5NB
Tel 0903 700804 (24hrs)

TRANSDISK IV

Commercial tapes CAN be transferred to disk!*

READ ON!

Are you tired of waiting for cassette games to load? Would you like to transfer them to disk for faster more reliable and convenient loading? You may have heard or read that this is not possible. Well not only is it possible but there is a program Transdisk IV that will do it all automatically you require no knowledge of cassette protection techniques! To put it simply Transdisk IV will read ANY Atari cassette (single multi stage non standard format 64K – no problem!) remove the protection then place it on to disk for you. Plus to load and run the new disk version of a cassette program requires just one keypress from a convenient autorun menu disk

The cost of this the most powerful tape to disk utility for the Atari is just, £24.95 inclusive of first class delivery. Also comes complete with comprehensive instructions which were specially written with the cassette upgrader and first time disk user in mind.

Requires Atari 800XL or 130XE Computer with disk drive and cassette recorder

Remember, that not only will you save money on upgrades to disk (if they are available) but many games are only available on cassette anyway so Transdisk IV has to be a worthwhile investment!

Send an SAE or phone for more details of this utility

Make Cheque or P.O. payable to **DIGICOMM** and send your order to
DIGICOMM
170 Bradwell Common Boulevard, Milton Keynes BUCKS MK13 8DG
Tel (0908) 663708
Demonstrations arranged for callers by appointment
*For your convenience from the original cassette only

STACK COMPUTER PRODUCTS

CENTRONICS PRINTER INTERFACE
400, 800, XL, XE (Any 8 Bit Atari)



TYPE 72000

- ANY CENTRONICS PRINTER
- NO SOFTWARE NEEDED
- ALL CABLES SUPPLIED
- EASY TO USE – JUST PLUG IN AND GO
- TRANSPARENT 8 CONVERSION FEATURES INCLUDED
- FULL YEARS WARRANTY


£39.95

FREE 40 PAGE CATALOGUE ON REQUEST OR WITH ORDER

MEEDMORE LIMITED
28 Ferriers Way, Netherton
Merseyside L30 4XL
Tel: 051-521 2282

◀ From Page 41

```
1640 ? #6;"{                }}}}}}}}{";
1650 ? #6,"{                ,,;;;;;;;;";
1660 ? #6;"{}}}}}}}}        }}}}}}}}{";
1670 ? #6,"{,,,,,,,,,,      ;;,,,{";
1680 ? #6;"{}}}}}}}}}}      }}}}}{";
1690 ? #6,"{,,,,,,,,,,      ,,,,;;{";
1700 ? #6;"{}}}}}}}}}}      }}}}}}{";
1710 ? #6,"{,,,,,,;;;;      ,,,,,,,{",
1720 ? #6,"{                {";
1730 ? #6,"{                {";
1740 ? #6," }}}}}}}}}}}}}}}}}}}}";
1750 RETURN
1760 REM MACHINE CODE DATA
1770 DATA 169,105,0,141,10,208,173,20
,2,201,15,240,14,201,7,208,8,173,119,2
1780 DATA 201,15,240,3,141,4,6,173,132
,2,201,8,240,4,201,1,240,22,162,8
1790 DATA 206,8,6,173,8,6,201,7,208,5,
169,3,141,8,6,232,228,25,208,236
1800 DATA 162,8,238,8,6,171,8,6,201,28
,208,5,169,255,141,8,6,173,4,6
1810 DATA 201,7,208,10,32,6,110,32,65,
110,238,1,6,96,201,11,208,20,32,6
1820 DATA 110,32,65,110,206,1,6,16,201
,14,208,10,32,6,110,32,65,110,206,2
1830 DATA 6,96,201,13,208,9,32,6,110,2
2,65,110,238,2,6,201,6,208,13,32
1840 DATA 6,110,32,65,110,206,2,6,138,
1,6,96,201,9,208,12,32,6,110,32
1850 DATA 65,110,238,2,6,206,1,6,201,2
0,208,12,32,6,110,32,65,110,206,1
1860 DATA 6,206,2,6,201,5,208,12,32,6,
110,32,65,110,238,2,6,210 2,6
1870 DATA 96,172,8,6,162,250,207,208,2
51,176,208,240,96,204,174,2,8,173,5,6
1880 DATA 201,8,240,7,169 0,142,5,6,24
8,76,32,110,169,1,141,5,6,160,16
1890 DATA 169,0,141,3,6,185,0 144,157,
0,140,208,232 210,1,6,173,1,6,201
1900 DATA 16,208,178,173,1,6,141,0,208
,32,245,227,76,173,0,6,201,139,2Ø6,3
1910 DATA 104,104,96,76
1920 REM HUMPBACK SHAPE DATA
1930 DATA 0 0 0,0 60 126,126,42,42,88,
84,126,60,0,0,0,0
1940 DATA 0,0,0,0,60,126,126,84,84,42,
42,126,60,0 0 0 0
1950 REM MIDI ML ROUTINE
1960 RESTORE 2220
1970 FOR I=0 TO 26
1980 READ A:POKE 1536+I,A:NEXT I
1990 DATA 104,169,0,160,31,162,5,32,92
,228,96
2000 DATA 230,180,6,173,180,6,141,1,20
8,206,202,6,173,181,6,141,2,208,238,19
7,Y
2010 DATA 169,0,133,77
2020 DATA 76,95,228
2030 RETURN
2040 REM LOAD CHARACTER SET
2050 OPN #L:S(48)
2060 REM
2070 CHR@SE 256*(A1206)
2080 RESTORE 2210 FOR A=1 TO 36 READ B
2090 #L:S(A,L)=CHR$(B):NEXT A
2100 A USR(ADR(#L:S),1261 POKE 756,126
2110 DATA 104,104,104,133,204,169,224,
133,206,162,0,160,0,177,205,145,203 20
0,200,249
2120 DATA 164,200,200,132,200,104,206,
200,112,206,202,224,5,208,232,96
2130 FOR I=0 TO 7 READ B
2140 POKE CHR@SE+(26*8)+I,B NEXT I
2150 DATA 77,219,255,192,127,215,224,1
17
2160 FOR I=0 TO 7 READ B
2170 POKE CHR@SE+(27*8)+I,B NEXT I
2180 DATA 52,247,225,221,255,171,64,0
2190 FOR I B TO 7 READ B
2200 POKE CHR@SE+(28*8)+I,B NEXT I
2210 DATA 112,200,240,200,224,176,112,
240
2220 FOR I=0 TO 7 READ B
2230 POKE CHR@SE+(29*8)+I,B:NEXT I
2240 DATA 64,64,215,256,127,107,253,06
2250 FOR I=0 TO 7 READ B
2260 POKE CHR@SE+(30*8)+I,B NEXT I
2270 DATA 0,192,215,232,222,172,203,12
8
2280 FOR I=0 TO 7 READ B
2290 POKE CHR@SE+(31*8)+I,B NEXT I
2300 DATA 6,7,215,251,255,249,201,04
2310 FOR I=0 TO 7 READ B
2320 POKE CHR@SE+(59*8)+I,B NEXT I
2330 DATA 14,4 11,11 7,12,15,8
2340 FOR I=0 TO 7 READ B
2350 POKE CHR@SE+(60*8)+I,B NEXT I
2360 DATA 48,58,107,221,151,225,7,1
2370 FOR I=0 TO 7 READ B
2380 POKE CHR@SE+(61*8)+I,B NEXT I
2390 DATA 124,48,48,24,56,48,16,0
2400 FOR I=0 TO 7 READ B
2410 POKE CHR@SE+(62*8)+I,B NEXT I
2420 DATA 0,28,48,58,24,48,48,124
2430 FOR I 0 TO 7 READ B
2440 POKE CHR@SE+64+I,B NEXT I
2450 DATA 0,16,68,99,126,70,68,16
2460 RETURN
```



LINE CHSUM	LINE CHSUM	LINE CHSUM	LINE CHSUM	LINE CHSUM	LINE CHSUM	LINE CHSUM	LINE CHSUM
0 CP1 (P)	320 MRU (J)	650 WYD (G)	940 LNV (L)	1240 05H (F)	1540 UF4 (O)	1850 DPW (A)	2160 DXE (J)
20 CP2 (B)	340 WKG (I)	660 APJ (Y)	950 ALK (E)	1250 FV4 (P)	1550 MY (X)	1860 IOL (A)	2170 UB5 (H)
30 CP3 (J)	340 3RH (V)	670 BTA (K)	960 4UK (K)	1255 Y2H (X)	1560 MLF (C)	1870 P,H (Y)	2180 V8J (S)
40 CPA (W)	350 P33 (G)	680 BLX (D)	970 NSP (E)	1260 OCF (E)	1570 JEU (A)	1880 DE (T)	2190 E4E (A)
50 SUX (K)	360 P4K (S)	690 UPU (W)	980 MEV (M)	1270 X8U (Z)	1580 JJB (Z)	1890 EU4 (P)	2200 UB5 (A)
60 JT4 (J)	370 5HW (P)	700 94C (E)	990 73K (E)	1280 4UX (P)	1590 E8H (D)	1900 4UJ (L)	2210 3B7 (S)
70 3MY (E)	380 18V (O)	710 152 (E)	1000 8AH (8)	1290 6A8 (S)	1600 AL8 (7)	1910 4CH (W)	2220 BYE (N)
80 ADM (A)	390 5VL (Z)	720 P37 (A)	1010 8AM (E)	1300 PWP (T)	1610 EFA (C)	1920 L8M (Y)	2230 UE5 (N)
90 H5H (V)	400 CME (3)	730 27T (G)	1020 MVT (8)	1310 05F (O)	1620 AE2 (L)	1930 RKX (A)	2240 VP9 (T)
100 USX (S)	410 CYV (8)	740 WEC (O)	1030 8NH (E)	1320 8PN (T)	1630 QOX (A)	1940 LVA (N)	2250 E0E (H)
110 L4A (A)	420 3V6 (3)	750 87Y (9)	1040 8NN (7)	1330 8NN (8)	1640 MSK (G)	1950 E8N (P)	2260 UB5 (H)
120 5C4 (6)	430 Y1K (L)	760 18A (A)	1050 8EV (N)	1340 MC1 (9)	1650 JM5 (V)	1960 D3W (J)	2270 V8V (O)
130 87S (7)	440 1L2 (7)	770 6B4 (M)	1060 81F (L)	1350 5J1 (N)	1660 B7Q (J)	1970 4WH (1)	2280 E4E (K)
140 XC1 (2)	450 PWR (N)	780 L5C (Y)	1070 8RR (S)	1360 FNX (N)	1670 R4E (8)	1980 4BH (K)	2290 UL5 (J)
150 JGS (F)	460 85K (S)	790 WK4 (N)	1080 8TH (N)	1370 DDL (K)	1680 M6A (X)	1990 RHM (S)	2300 RWV (7)
160 1NF (J)	470 T82 (N)	800 DUY (N)	1090 8IM (U)	1380 KV1 (K)	1690 8J5 (V)	2000 MLT (G)	2310 UVE (D)
170 J5U (M)	480 K36 (7)	810 RJN (S)	1100 VFK (X)	1390 C5R (W)	1700 ANH (1)	2010 2W0 (B)	2320 UN5 (P)
180 V25 (T)	490 ASC (1)	820 K3M (N)	1110 8AM (N)	1400 G3H (E)	1710 B7P (D)	2020 QJS (E)	2330 E4E (A)
190 7Q9 (O)	500 XLY (7)	830 8DO (Y)	1120 MVM (G)	1410 2A9 (A)	1720 9AH (4)	2030 VHL (C)	2340 E2E (U)
200 PQT (2)	510 CYW (E)	840 84O (S)	1130 8AE (P)	1420 KM1 (A)	1730 9QH (D)	2040 B3P (G)	2350 UN5 (J)
210 GJ7 (S)	520 KWC (V)	850 88N (4)	1130 SAE (S)	1430 AXE (4)	1740 SOM (S)	2050 W52 (U)	2360 SK5 (Y)
220 4HH (C)	530 2HN (B)	860 YVR (T)	1140 JGE (Q)	1440 51H (N)	1750 WHK (Z)	2060 BAP (N)	2370 E8E (F)
230 OMO (W)	540 8EC (4)	850 9OA (A)	1150 8QC (R)	1450 2Y9 (L)	1760 E8M (8)	2070 A7U (S)	2380 UU5 (B)
240 5F5 (S)	550 UH7 (7)	860 P5J (U)	1160 3C5 (L)	1460 5AR (C)	1770 NHT (G)	2080 8QG (K)	2390 GWC (Y)
250 Z5A (F)	560 J1X (V)	870 9Z8 (S)	1170 092 (R)	1470 G8M (A)	1780 LFC (K)	2090 MC1 (A)	2400 DXE (B)
260 XTW (O)	570 MGW (E)	880 DVO (T)	1180 XMN (K)	1480 8XN (N)	1790 CK7 (I)	2100 4XS (U)	2410 UK5 (K)
270 B0T (F)	580 95K (K)	890 Y2K (G)	1190 X5L (T)	1490 3ER (N)	1800 CFO (S)	2110 XF0 (K)	2420 GF8 (G)
280 CF8 (O)	590 KEN (1)	900 LX8 (J)	1200 YY6 (N)	1500 6CO (K)	1810 CSE (V)	2120 8KU (K)	2430 EAE (V)
290 BYT (O)	600 KJB (8)	910 63K (E)	1210 8CV (Y)	1510 WOK (S)	1820 E9O (Z)	2130 8RE (B)	2440 SFC (W)
300 NR1 (G)	610 LYX (K)	920 87K (9)	1220 XJL (O)	1520 8PN (W)	1830 B2Y (O)	2140 UE5 (P)	2450 GSY (G)
310 7G8 (V)	620 UVP (2)	930 M5P (E)	1230 WCT (V)	1530 8RN (S)	1840 B2R (N)	2150 V6N (I)	2460 WAL (A)

ATARI USER Classifieds

Has upgrading your computer given you hardware you no longer need? Or have changing interests left you with unwanted software? Then THIS is the place to advertise your surplus items. *Atari User* readers are always on the lookout for a bargain and this is the first place they look!

An added bonus!

Your advert will also be automatically displayed on MicroLink, the electronic mail service operated in association with Telecom Gold. This means it will be seen by thousands of computer enthusiasts who can send an instant response

Classified advertisements will be accepted under the following conditions:

- This service is EXCLUSIVELY for the use of private readers. No trade ads will be allowed
- To avoid encouraging software piracy, all ads will be carefully vetted before they are accepted
- Ads can only be accepted on this form (or a photocopy of it)
- There is no maximum to the number of words you include in your ad. If there is insufficient room on the form, continue on a separate sheet of paper
- The cost is 20p per word, with a minimum of 10 words
- We GUARANTEE your ad will appear in the next available issue of *Atari User*

● Volume's 1 Nos 5, 6, 8, 10 issues Atari User' wanted in any condition. Any reasonable price paid. Write: PO Box 3556, GR 100 10, Athens Greece

● Wanted 1050 disc drive. Reasonable price. Tel 031 552 3026

● 130XX XC12 Data Recorder, joystick, games + mags £100. Details Tel Woodbridge 6346

● 1027 printer. Mint with Ataniwriter disc £65. Tel 0227 464828

● New 8 Bit chips cheap. Original s/w Ataniwriter, Datasoft Compiler, Microsoft Basic II, Neumenue Dos + Demo tape to disc, many more £8 each. Music construction set, Silent Service + more £4. Tel 0600 6144. MicroLink MAG40417. Prestel 011111439

● Wanted 1027 printer, working order or for spares. Tel: 061 707 2992

● 800XL, 1050 disc drive, 1027 printer, 1010 recorder and joystick plus some original software, job lot £215 o n o. Tel: 08694 78393 evenings

● Atari 800XL (Revision C Basic), 1010 recorder, 10+ games, joystick, books, magazines £130 o n o. Tel Malvern (06845) 5936

● Data Recorder and £140 worth of games for sale £75 o n o. Tel 061 790 0813 ask for Robert

● WS2000 modem £70 posted. De-Re Atari £6. Page 6 on disc, 26 31 £15. Tel 0245 269030

● 600XL and cover 800XL (not working). Atari 400, 1050, 810 disc drives, 1010 recorder £200 of software assembler editor and utility pack M.L. book £300. Peter Barry, 61 Willowbank Road, Birkenhead, Merseyside, L42 7JX

● Atari 1029 printer as new with box, utilities including 10 print £90. Tel Coventry 713404

● Computereyes Digitiser software and manual £65. Speech Digitiser and recognoser includes software, phones, mic and manual £45. Touch Tablet, Atari Artist, Colour Space, Fun with Art, Technicolour Dream only £25. Tel: 01 542 9326

● Atari 1029 printer for sale as new £70. Tel 01 724 5472

● 800XL, 1050 drive, XCII cassette, joysticks, software (latest games), mags etc £200. Tel: 0268 754043 may split for right offer

● Atari 1027 letter quality printer for sale, virtually new, still with box, manuel etc only £60. Tel Farnham (0252) 713775 ask for Steve

● Wanted disc drive for Atari 65XE write to Alan Morley, 4 Norfolk Square, Great Yarmouth, NR30 1EE

Fill in now for the next issue

					10 words £2.00
					15 words £3.00
					20 words £4.00
					25 words £5.00
					30 words £6.00

Cheque enclosed for £_____

I certify that any software offered for sale is original and not a copy

Signed_____

Name_____

Address_____

POST TO: Atari User Classifieds, Europa House, Adlington Park, Adlington, Macclesfield SK10 4NP

SOFTWARE Solutions

Your programming problems solved by ANDRÉ WILLEY

THIS month the first letter comes from Bryan Kennerley who is based at Rhyl in Wales. He has a few questions about some puzzling aspects of the Atari floppy disc system

I am currently writing a disc sector editor and while doing so I have uncovered a few unusual phenomena. Firstly, on reading the directory of Alternate Reality – The City (disc 1, side 1) two directories appear to be displayed in a random order.

Investigation reveals that on reading the directory sectors (361 to 364) the same thing occurs. How can these sectors hold one set of data on one pass and a completely different set on the next?

Also, while writing the DLI routines I made extensive use of the Dos 2.5 ramdisc on my 130XE, and in doing so I discovered a seemingly pointless function. If a working DLI is disabled by setting bit 7 of location 54286 to zero (using POKE 54286,64) before accessing a D8: ramdisc file, the DLI miraculously springs back into life again. Is this essential to the ramdisc's operation, or is it just a bug?

I would like to include in my program the capability to detect, examine and create bad sectors – but to do so I need to know what one is. What makes them different to ordinary sectors and how are they created?

As far as the DLI part of your question goes, the answer is probably a slip up on the part of the authors of Dos 2.5. When the ramdisc is accessed various portions of rom and ram are switched in and out of the memory map and the operating system must always be deactivated before attempting to do such bank selection operations.

This involves turning off both the Vertical Blank and Display List Interrupts (VBIs and DLIs) by setting location 54286 to zero. Normally the original contents would be stored temporarily on the stack, but in this case that doesn't seem to happen and the value 192 is restored after the Dos call – re-activating any DLIs as well as the required VBI system.

The other part of your letter requires a greater understanding of the way in which an Atari disc drive works.

Although we tend to think of disc sectors as being numbered sequentially from 1 to 720, the disc drive actually sees them rather differently. It deals with the disc as 40 separate tracks with each containing 18 sectors of data (or 26 if you're using an enhanced density disc).

Each sector within a track is assigned a number between 1 and 18 so when you ask to read a given disc sector the number you specify must first be converted into track and sector references – and only when the disc drive's read/write head is positioned over the correct track can the sector offset value be used to read in the correct data.

For example, if you try to access sector 18 the drive looks on track 0 for the sector numbered 18. Similarly sector 19 would actually be at track 1/sector 1 and so on up to sector 720 which is really track 40/sector 18.

Some manufacturers use a special timing hole punched into all 5.25in discs to work out where each sector occurs within a track. Atari however, opted for a software approach and each sector has a short block of header data which provides the sector reference number and some error prevent on checksum data.

What you have come across is a method of copy protection used by some disc manufacturers. As you have observed, the first directory entry is located at sector number 361, which is in fact the first sector of track 20. Whenever you ask for a directory (from sector 361) the drive head moves straight to track 20 and starts reading each sector in turn until it finds one with a header value of one.

As soon as it finds the correct header it knows that it must send the next 128 bytes of data directly to your micro. Finally, all the data bytes are added together and compared with the original checksum digit found in the header, and only if the two numbers match will the transfer be considered complete.

The drive expects there to be 18 individual sectors, each with a unique number, but it is theoretically possible to have more than one sector with the same reference number – it being pot luck which one the drive arrives at first. Some discs even contain 18 sectors, all with the same number – giving 18 possible sets of data for one official sector number.

There are obviously some devious ways of contriving to read a specific sector out of the 18 present, but there is no point going into detail because there is absolutely no way in which you can create a disc like this with a normal drive. Software manufacturers use some very special pieces of equipment to make such discs, and the program won't run unless this custom format is present.

The same applies to so-called *bad* sectors, which are often physically damaged or given incorrect checksum digits – thus returning a disc read error even when there may be 128 bytes of good data present. Once again, you can't create these with a normal drive – indeed Atari has provided you with an awful lot of circuitry to prevent the possibility of any bad data being recorded on a disc.

Of course, you are a responsible Atari owner, and wouldn't be interested in actually *copying* such things anyway, would you? That would be both illegal and immoral, and is the

Turn to Page 46 ▶

◀ From Page 45

reason why such weird and uncopyable date formats were created in the first place. Here endeth today's lecture!

SuperScript puzzle

On now to a letter from the Netherlands from **Th P J Bloks**

Last August I bought the SuperScript word processor which I had seen advertised in Atari User and which I am generally very happy with.

However, a few days ago I was rereading your March 1986 issue containing the SuperScript review in which the reviewer mentions a bug with the Return character (13) versus the normal Atari code of 155.

As I had already encountered the problem of printing a text file to disc I was glad to get an answer to this problem, so I decided to follow the reviewer's advice and alter the 13 on my work disc defaults file, and in the Epson file on the master disc.

I booted up SuperScript and loaded the Epson printer driver and changed the Return number 13 to 155. Then I used the Document Replace option to write the printer driver back to my disc and put the program away.

The following day I tried to boot SuperScript and I could only get the READY prompt or the Self Test menu. Upon checking the disc I found that the first three files, the ones with hearts in the directory, had been deleted. I then used the Restore option from my modified Dos 2.9, and now the defaults file seems to contain some 600 sectors – but the disc still doesn't boot.

I hope that you can offer me a solution as to how to get SuperScript working again, or print a warning in your magazine for other readers so it won't happen to anyone else.

As you have by now realised it's always a mistake to write anything to a master disc unless you've first made a backup of it. Since SuperScript is heavily copy protected, it's best to assume that you just don't write anything to it at all.

What you should have done is to write your new defaults file on to your work disc and not used the original version on the master disc at all. As you have discovered, your master is now corrupted and you should send it back for a replacement (although you will probably have to pay the media cost – somewhere around £3 to £5 sounds reasonable).

The first three boot files on the disc were originally hidden from view by altering their respective directory entries so when you tried to write a new file on to the disc the first blank entry was assumed to be empty and re-used, thus corrupting the hidden DOS.SYS file.

I reckon that such techniques should not be used on business programs and you should not only be allowed to but be positively encouraged to take backups of your master discs. After all, you've paid out your £50 and the program's now useless through no real fault of your own. I hope you get it sorted out soon and perhaps software houses will ensure that future versions of such programs will be released in non-protected forms, as they already are on the ST.

Guide to local dealers

SOFTWARE EXPRESS

EUROPE'S LARGEST ATARI MAIL ORDER COMPANY
(021) 328 3585

ATARI

ATARI

OPENING SOON

OUR NEW ATARI STORE AT

9, EXETER STREET
PLYMOUTH
PHONE (0752) 265276

ATARI

NOW IN STOCK
The New Atari ROM Cartridges XL & XE
(See other side for details)

NEW ATARI ROM CARTRIDGES AVAILABLE
Track and Field
Rescue on Fractalus
Blue Max
Archon
Ball Blazer
Lode Runner
Fight Night
Pole Position
And many others
Phone for prices

ALSO AT 514/516 ALUM ROCK ROAD BIRMINGHAM B8 3HX (021) 328 3585
212/213 BROAD STREET BIRMINGHAM B15 2JP (021) 643 9100

Guide to local dealers

CARDIFF

EAGLE COMPUTERS

South Wales' Largest Atari Dealer

Atari DTP, Full range of software
Plus Laser Printing in Postscript and
Hawk Scanning facilities

48 Charles Street, Cardiff CF1 4EF
Telephone: 0222 390286

LEICESTERSHIRE

B. BYTES COMPUTER SYSTEMS of Hinckley

FULL SUPPORT FOR ATARI ST AND XL/XE

All ST computers from B.Bytes come with a free software pack which includes

1st Word II (Advanced word processor)	Over 50 PD Games	Desktop Accessories
data file)	ST Word (Word processor)	Mouse and graphics based
Neochrome (Art drawing package)	Utilities	

Friendly and prompt advice to help you get the most out of your machine and B.Bytes customised service call

3.5" DS/DD disks only £1 each if you buy 40 or more
30% off selected software (top titles not available)
Up to 30% off software for all other machines
Extensive ranges of Atari Accessories Joysticks and Mouse
Please write or phone for free information pack

B. Bytes Computer Systems
19 Southfield Road, Hinckley Leicestershire LE10 1UA. Tel.. (0455) 613977
All Prices include VAT. P&P may be extra.

GLASGOW

GLASGOW COMPUTER CENTRE
ATARI AUTHORISED DEALER
AND SERVICE CENTRE

RAM UPGRADES
For Atari 520 ST/M/FM Please phone for prices/Availability

3 5" DISKETTES

Branded SONY disks single sided (with two free storage cases)	£17.50
Branded SONY disks double sided	£18.00

Above prices are inc of VAT & P/P

Analogue to Digital Converter £130.00

Now Card Computers present the first industrial standard A/D converter for the ST

Tech Specifications	Applications
8 channels	Sound sampling Temperature
8 bit resolution	measurment, Blood cardiograms
2.5 billion seconds conversion rate	Blood pressure etc
0-5V input	Currently being used in the cardiac
Plugs into cartridge port	intensive care unit at Glasgow
Compact size 5.4x6.3x2.3cms	Infirmary monitoring patient's blood
CH1 ST Replay Compatible	pressure waveforms

GLASGOW COMPUTER CENTRE
122 WEST NILE STREET, GLASGOW G1 1QZ
TEL 041 332 6246
PROGRESS THROUGH TECHNOLOGY

BUCKINGHAMSHIRE

FIDGET COMPUTERWARE

30% off all Atari 8 bit products

Wide range of all Atari and Atari ST Software, Books, Joysticks, Dust Covers, Blank Discs, and much much more

Phone 0494 33144 for details

Write or phone for free catalogue and details of free membership of **Fidget Discount Software Club.**

Dept. PCW 150 Desborough Road, High Wycombe, Bucks HP11 2QA
Telephone: 0494 33144

BUCKINGHAMSHIRE

QUALITY DUST COVERS

ST or STFM	**£4.95**
Monitor	**£4.95**
XL/XE	**£3.78**

9T Monitor Cable £9.95
Other covers & cables available state machine type
Atari Paddles £9.95
Mouse Mats £4.95

Keep your mouse tidy – Mouse House (sticks to monitor) **£3.99**

VCS Cartridges from £2.99
800XL/130 PSU £19.95
Large range of 16 & 8 bit software & peripherals available Please send a s a e for full list – please quote AU1

CAPRI MARKETING LIMITED
24A WHITE FIT LANE
FLACKWELL HEATH
NR HIGH WYCOMBE
BUCKS HP10 9HR
WAREHOUSE BOURNE END (06285) 31244

5 LINERS

Recently our readers have been sending us Five Liners that have been getting more clever and imaginitive by the day. They're finding lots of ways to cram more and more code into the tight space available. So here are a couple of tips to help you enter the long lines.

Firstly, enter POKE 82,0 to remove the left hand screen margin. This allows you to enter four lines of Basic on the screen. You should also leave out all unecessary spaces.

Whenever possible use the abbreviated form of the commands. Some common ones are:

GRAPHICS	GR
FOR	F
NEXT	N
SOUND	SO
GOTO	G
DATA	D

ENHANCED ON-SCREEN EDITOR
from Karl Fitzhugh

HOW often have you been setting up a Graphics 0 title screen when you've had to strain your eyes to count the characters to the left of the cursor in order to work out coordinates for a POSITION statement?

Or how many times have you had to dig out your trusty manual to look up the internal code for a character when you needed to POKE it directly to the screen?

This Five Liner solves both of these problems. It sets up a machine code routine residing in Page 6 – locations 1536 to 1717 – that executes during the vertical blank period – VBI – so make sure that your program doesn't use this area of memory. An extra line of text is added at the top of a Graphics 0 screen which shows the current row and column of the cursor as well as the internal character set code for the character currently under the cursor.

Once you have typed it in, save a copy before running it as any mistakes in the DATA statements could cause the computer to crash. After the program is run you can type NEW to delete the Basic from memory and call the routine by typing X=USR(1576).

If you press Reset or execute a Graphics 0 command you will have to call it again but don't call it from any other mode or you will just get garbage on the screen.

```
1 DATA 0,36,47,44,0,29,0,16,16,0,0,58,
47,55,0,29,0,16,16,0,0,35,48,33,58,61,
37,62,0,75,47,36,17,0,29,0,16,16,16,0,
194,167
2 DATA 147,168,6,147,48,7,148,49 2,186
,0,164,69,147,154,6,149,155,6,167,0,1
08,71,165,7,32,92,220,96,108,93,32,134
,0,105
3 DATA 26,141,10,0,138,32,134,6,105,26
,141,37,6,24,138,105,16,141,36,6,165,0
4,32,134,6,165,26,141,11,0,24,138,105,
16,161
4 DATA 17,0,165,85 32,134,6,169,26,141
,0,6,24,138,105,16,141,7,6,76,98,228,1
62,0,58,233,10,144,4,201,76,137,6,24,5
0,112
5 FOR I=1536 TO 1717 READ B POKE I,B N
EXT I DATA 06,66,0,0,16,66,64,156,2,2,
2,2,2,2,2,2,2,2,2,2,2,2,2,2,2,2,2,2,65,147,6
```

Get it right!

1 LL6 (L)
2 RRM (V)
3 NMC (O)
4 TLG (4)
5 7NS (D)

PERCEPTION
from George Postler

TEST your reaction speed to a given situation by playing this fun-to use program. Pressing Start begins the game and the micro displays two numbers on the screen for a short time. If you recognise them as being the same press the fire button on your joystick, which should be plugged into port one.

If you are quick enough and the numbers are still the same the computer will award you one point but if you are wrong your attempts left will be reduced by one. After five goes the game will end and your final total will be displayed.

PROGRAM BREAKDOWN

1. Sets up a Graphics Mode 2+16 screen and tests for Start to be pressed.
2. Generates and prints the two random numbers and tests for the trigger to be pressed.
3. Speeds up the game, prints the score and your number of attempts.
4. Tests whether *X* is the same as *Y*, subtracts attempts and returns to line two.
5. Adds one point and returns to line two.

```
1 GRAPHICS 18 N=100-T 00;"PRESS START"
 POSITION 8,10 ? 00;"YOUR SCORE=";B P=
0 GRAPHICS 10 OR PEEK(53279)<>6 GOTO 1
0-0
2 X=INT(RND(0)*10) T=INT(RND(0)*10) PO
SITION 7,5 ? 00;X POSITION 11,5 ? 00,Y
 FOR M=0 TO 0-5 STRIG(0) OR S=0 GOSUB
4 NEXT M
3 K=K-0.1:POSITION 4,0:? 00,"YOUR SCOR
E=";B POSITION 5,11:? 00,"TRIES=";P
:OR P<=0 GOTO 1 GOTO 2
4 IF X<>Y THEN P=P-1 FOR M=0 TO 100 SO
UND 0,M,0,10 NEXT M SOUND 0,0,0,0 RETU
RN
5 B=B+1 FOR M=0 TO 200 SOUND 0,M,10,10
 NEXT M SOUND 0,0,0,0 RETURN
```

PROGRAM VARIABLES

- **X, Y** The two random numbers
- **P** Number of attempts made
- **B** Score
- **K** Controls the speed of the game

Get it right!

1 27Y (O)
2 AUU (P)
3 VN4 (Y)
4 J45 (W)
5 8GK (H)

IF you've written any useful or interesting five line programs why not send them to us to grace our pages?


We pay £25 for each one published

You should give a full description of the routine and any other details that are relevant And remember if you want your material returning please enclose a suitably stamped package

Win £25

Simply send a copy of the program on disc or tape together with the documentation – preferably as a word processed file – to

Atari User, Europa House, Adlington Park, Adlington, Macclesfield SK10 4NP



BOUNCE DEMO
from Keith and Joel Goodwin

THIS program proves that you can achieve smooth fine scrolling without having to use complex assembly language Instead it simply manipulates the display list to do the trick equally as well

When you first run it the message ATARI USER MAGAZINE! will bounce up and down the screen very smoothly with none of the jerkiness that usually occurs with on-screen character animation After a short while it slows down until it stops at the bottom of the display Then it starts all over again

```
1 Z=112 GRAPHICS 17 POKE 559,0 S=53760
  G=PEEK(560) I=PEEK(561) G=G+3:M=256*I+
PEEK(G+88) H=PEEK(G+89) FOR P=3 TO 22 POK
E G+P,0
2 NEXT P:POKE G+23,7:E POKE G+24,L POKE
  G+25,0 POKE G+28,65 POKE G+27,6 POKE
G+29,Z:? #6;"ATARI USER MAGAZINE!" POK
E 752,48
3 POKE 559 :41:FOR B=0 TO 15 STEP 8 Z P
OKE 708,22+B POKE 53760,B+10 POKE 537
61,152+B POKE 53762,1 NEXT B SOUND 0,0
,0,0 SOUND 1,0,0,0
4 FOR R P-1 TO 1 STEP  1:FOR A=0 TO 2
STEP 16 POKE G+0,A NEXT A NEXT R:P=P-2
:E P<0 THEN FOR A=0 TO 700:NEXT A:GOS
5 FOR B=15 TO 0 STEP -2:SOUND 0,10,0,B
  NEXT B FOR A=3 TO P 1:FOR R Z TO 0 ST
EP -16 POKE G+0,R NEXT R NEXT A:FOR B=
15 TO 0 STEP  3:SOUND 0,5,0,B NEXT B G
OTO 4
```

PROGRAM BREAKDOWN

1 Sets up the display list disables the screen and sets up the variables
2 Finishes the display list and prints a message
3 Re enables the screen and fades in the message with sound effects
4 Scrolls the message down lowers the height of the next bounce and checks whether the message has stopped bouncing at the bottom
5 Makes the sound of the message hitting the bottom scrolls the message up and makes the sound of hitting the top of the screen



1 4P4 (F)
2 EL6 (D)
3 483 (F)
4 LKT (P)
5 LPJ (O)

VARIABLES

G, I Low and high bytes of the display list
D Location of the display list
L, H Low and high byte pointers to the screen memory
P Holds the height of the current bounce
O, R FOR NEXT loop counters

LACE
from Damon Burroughs

HERE S a super little program that will show you just how easy it is to create colourful graphics on your Atari The finished three-colour picture is drawn in eight parts – mirrored in the specified colour

When the program has finished it holds the pattern for a short while and then starts it again Also included is a short sound effect which can be heard as the screen is drawn

PROGRAM BREAKDOWN

10 Sets up sound colour and graphics mode and then draws the first stage of the computer lace
20 Draws the second stage, changes the colours for the next two and then draws stage three
30 Draws the fourth stage changes the colour for the next four and then draws stage five
40 Draws stages six and seven
50 Draws stage eight switches off the sound holds the lace design for a few seconds and then loops back to line 10 to re draw the pattern

```
10 SOUND 1,150,158,12 GRAPHICS 15+16+32
:COLOR 1:FOR R=0 TO 159 STEP 5 PLOT 79,0
:DRAWTO R,79 NEXT R:FOR R=0 TO 159 STE
P 5
20 PLOT 79,159 DRAWTO R,79 NEXT R COLO
R 2 FOR R=0 TO 159 STEP 5:PLOT 79,159
DRAWTO R,79 NEXT R:FOR R=0 TO 159 STEP
 5
30 PLOT 79,0:DRAWTO R,79:NEXT R COLOR
 3 FOR R=0 TO 159 STEP 5 PLOT 2,0 DRAW
TO R,79:NEXT R:FOR R=0 TO 155 STEP 5
40 PLOT 156,0 DRAWTO R,79 NEXT R:FOR R
=0 TO 159 STEP 5 PLOT 155,159 DRAWTO R
,79 NEXT R:FOR R=0 TO 155 STEP 5
50 PLOT 2,159 DRAWTO R,79 NEXT R POKE
53760,15 FOR R=0 TO 1000 NEXT R:GOTO 1
0
```



10 5GD (C)
20 7A8 (O)
30 7UJ (1)
40 DAF (Q)
50 SFY (6)

Now you see it, now you don't

LEN GOLDING continues his look at animation using Atari Basic

AS we saw last month, it's quite easy to make a keyboard character move around the screen by just printing a blank space over it then re printing it somewhere else

This is fine as long as the background is blank but suppose the character has to move across a terrain map or other scenery? If you print a blank space every time the character moves it will leave behind it a trail of missing background

The theory behind overcoming the problem is straightforwerd We first look to see where our moving character is about to land find what s currently printed there and store the information in a safe place

Next we print our character, which will then erase the background at that position When the time comes to move it we re print the original background data which erases the moving character and restores the background – all in one go

Although it sounds fairly simple it s a very complicated thing for a computer to do Consider this statement

```
LOCATE 10,20,Q
```

In ordinary English, it means *Move the cursor to a position 10 columns in from the left and 20 rows down Read the character currently occupying that spot and store its code number in a variable called Q*

If, for example the letter A is cur

```
10 REM Program 1  8-directional joysti
ck-controlled movement over a backgrou
nd
20 GRAPHICS 0 REM Necessary for LOCATE
 command to work
30 POKE 752,1:? CHR$(125) REM turn cur
sor off and clear screen
40 H2=19:V2=11.REM Initial Horizontal
and Vertical co-ordinates for ball
50 GOSUB 350 REM Fill the screen with
a background of letters
60 GOTO 100 REM Start loop, printing t
he ball at its initial position
70 REM main loop starts here
80 GOSUB 150 REM Get new horizontal an
d vertical co-ordinates
90 POSITION H1,V1 ? CHR$(0) REM erase
 ball by printing background over it
100 LOCATE H2,V2,Q REM Store backgroun
d character on which the ball will lan
d
110 POSITION H2,V2 ? CHR$(20) REM Prin
t the ball
120 H1=H2 V1=V2 REM Reset H1 and V1 to
 new position, ready for next cycle
130 GOTO 80
140 REM Subroutines start here
150 S=STICK(0) REM Read position of jo
ystick in port 1
160 IF S=15 THEN GOTO 150 REM Do nothi
ng if stick centralised
170 REM Find next position for the bal
l to be printed
180 IF S=14 THEN GOSUB 270 GOTO 260 RE
M Up only
190 IF S=6 THEN GOSUB 270 GOSUB 310 GO
TO 260 REM Up/right
200 IF S=7 THEN GOSUB 310 GOTO 260 REM
 Right only
210 IF S=5 THEN GOSUB 290 GOSUB 330 GO
TO 260 REM Down/right
220 IF S=13 THEN GOSUB 290 GOTO 260 RE
M Down only
230 IF S=9 THEN GOSUB 290 GOSUB 330 GO
TO 260 REM Down/left
240 IF S=11 THEN GOSUB 330 GOTO 260 RE
M Left only
250 IF S=10 THEN GOSUB 270 GOSUB 330 R
EM Up/left
260 RETURN
270 IF V1>1 THEN V2=V1-1 REM Prepare t
o move up, if there s room
280 RETURN
290 IF V1<22 THEN V2=V1+1 REM Prepare
to move down, if there s room
300 RETURN
310 IF H1<36 THEN H2=H1+1 REM Prepare
to move right, if there s room
320 RETURN
330 IF H1>1 THEN H2=H1-1 REM Prepare t
o move left, if there s room
340 RETURN
350 FOR ROW=1 TO 22 FOR COLUMN=2 TO 37
360 POSITION COLUMN,ROW ? CHR$(ROW+64)
370 NEXT COLUMN NEXT ROW
380 RETURN
```

Program 1: Example of joystick control

rently sitting at coordinates 10,20 the value stored in *Q* will be 65 – the Ascii code for A.

As always, you can change either or both coordinates to any value within the corresponding screen boundary and variable *Q* can have any legal name you choose.

Here's how it works in practice using the ball – Ascii 20 – as our moving character. We'll let the ball's current position be *H1 V1* and its new position *H2 V2*. Also for convenience let's pretend the values for *H2* and *V2* are updated by an imaginary subroutine at line 1000. Our program might look like this:

```
10 GRAPHICS 0
20 H2=10 V2=20
30 GOTO 60
40 GOSUB 1000
50 POSITION H1,V1 PRINT CHR$(0)
60 LOCATE H2,V2,Q
70 POSITION H2,V2: PRINT CHR$(20)
80 H1=H2 V1=V2
90 GOTO 20
```

We start the program by telling the computer what graphics mode we're using. It's essential to do this or the LOCATE command won't work. Next we specify the ball's starting position *H2,V2* then jump into the middle of the main loop at line 60.

This line reads the background character at our ball's initial position and stores it in *Q*. Line 70 prints the ball and line 80 sets *H1* and *V1* to the ball's current coordinates. Line 90 then sets the game loop running. Line 40 executes our joystick subroutine and returns with the ball's new coordinates in *H2 V2*.

Line 50 erases the ball by restoring the original background detail – the character whose Ascii code is held in *Q*. Line 60 identifies the background character which is currently sitting at the ball's new destination – *H2 V2* – and stores its Ascii number in *Q*, replacing the previous value. Line 70 prints the ball at *H2 V2* and this is where we came in.

The whole process will repeat until we stop the program by pressing Break or Reset or switching power off.

Program I is a fully working demonstration that's similar to last month's Program IV but we've rearranged things to give you a bit more practice with subroutines. Notice that the joystick control system – lines 150 to 340 – is now nested. The first subroutine (150 to 260) calls other subroutines (270 to 340) as necessary before returning to the main-line code at line 110.

Because lines 150 to 340 are now a self-contained mini program you can incorporate the routine easily into your own games.

The screen background – a pattern of capital letters – is also drawn by a subroutine this time at line 350. You can easily change it to draw any pattern or background you choose – a haunted house or dungeon floor plan for example – using control characters. The utility program we gave you in Part III – the March 1988 issue of

Turn to Page 52 ▶




Figure I: Flow chart describing Program I

◄ From Page 51

Atari User – takes the drudgery out of this

Another use for LOCATE is to detect when your moving character has hit a target of some kind Try adding these lines to Program I

```
115 IF Q=72 THEN GOSUB 500
500 SOUND 0,150,10,8
510 FOR W=1 TO 20 NEXT W
520 SOUND 0,0,0,0
530 RETURN
```

Now you'll get a short beep whenever the moving ball lands on a letter H If you want the hit to produce a more exciting result, just change the code at line 500. Aren't subroutines wonderful?

If you want your moving character to destroy only certain symbols in the background picture without disturbing the rest that's easy too Try changing line 100 to read

```
100 LOCATE H2,V2,Q IF Q=77 THEN Q=32
```

If the ball now lands on a letter M, the value stored in Q will be changed from 77 – the Ascii code for M – to 32 – the code for a blank space So next time the ball moves it will leave a blank space behind it You'll find, therefore that the ball wipes out every M but doesn t disturb anything else

We re fast approaching the stage where we can write real arcade games and our programs are consequently becoming more complex Computers can follow the most tortuous listings without difficulty, but human programmers tend to get lost in the maze So now s a good time to introduce a system of diagrams which makes it much simpler to keep track of things

Look at Figure I on the previous page It shows the operation of Program I in simplified pictorial form Notice how the diagram corresponds to REMarks in the listing and try checking the program s operation against our written explanation The pictorial flow chart is much easier to follow and saves an awful lot of writing

Professional programmers use a whole range of symbols in their flow charts but we can get a long way with just two rectangles for operations and diamonds for decisions Diamonds always have two outputs correspond ing to yes and no while rectangles have only one, corresponding to done

Basic is one of the few languages that doesn t demand an accurate flow chart before you start programming – it s very tolerant of variations in construction and layout As your programs become more complicated, however you'll find that time spent on designing it – by flow chart or other methods – will save many hours of trial and error and the end result will be tidier, shorter and probably faster

Now let s turn to a topic that will help you to produce more realistic games – the use of colour Deep inside your Atari is a group of memory addresses called colour registers Whenever the computer draws a screen they tell it which colours to use and what to use them for You can change the contents of the registers and consequently the colours displayed by using SETCOLOR

For convenience – and to avoid mis spelling – this command can be abbreviated to SE – Basic will write it out in full when the program is LISTed Its format looks like this

```
SETCOLOR 1,2,8
```

The first figure after SETCOLOR identifies which register we want to alter In Graphics 0 we can use only registers 1, 2 and 4 but these enable us to change text brightness background colour and border colour respectively

The second figure specifies the colour – or hue – to be used and can have any value from 0 to 15 Figure II shows the hues available using Atari s own words but you may disagree with the descriptions In any case there s no absolute standard – many TVs and computers will inevitably produce different results

The third and final figure in a SETCOLOR command controls the colour s brightness and it can be any even number from 0 to 14 Changing this level has a marked effect on the perceived colour For example

```
SETCOLOR 2,12,8
```

will turn the background a dark green whereas

```
SETCOLOR 2,12,14
```

will turn it bright yellow even though the hue number is the same – 12 – in both cases

Program II lets you use a joystick to

experiment [illegible] colour registers 1, 2 and 4. Press the trigger to step from one register to the next, move the stick up or down to change the hue value, and move it left or right to change the brightness level. If things get out of hand, pressing Reset will automatically restore the screen to its normal condition.

All our programming so far has been done in Graphics Mode 0, which is comparatively limited in its use of colour.

Text is always printed in the same hue as its background, but at a different brightness level. You can make it very dark, very bright or invisible, but that's about the limit to special effects.

For genuine multi-colour displays [illegible] to enter a new dimension.

```
10 GRAPHICS 1
20 PRINT #6;"TeSt"
```

When you run this something very peculiar occurs. The screen first goes blank, then splits into two parts – a large black area, and a smaller blue one at the bottom – with the normal READY message printed in the blue area as it would be on a Graphics 0 screen.

The word TEST appears in large letters at the top of the black area, but instead of being printed exactly as in line 20, all the letters are in upper case and each is a different colour.

Change line 10 to GRAPHICS 2 and something similar happens, but this time the coloured letters are twice as large.

If you've followed this series from the first part you now know enough to write your first action game, and that's the best way to practise what you've learned.

Turn to Page 64 ▶

0	Black
1	Rust
2	Red-Orange
3	Dark Orange
4	Red
5	Dark Lavender
6	Cobalt Blue
7	Ultramarine Blue
8	Medium Blue
9	Dark Blue
10	Blue-Grey
11	Olive Green
12	Medium Green
13	Dark Green
14	Orange-Green
15	Orange

Figure 1i: Colour values – second parameter in a SETCOLOR statement

```
10 REM Program 11  Experimenting with
Colour registers  Graph cs 0
20 POKE 752,1 : CHRS 1[illegible] REM Clear sc
reen and make cursor invisible
30 R=4 HUE=0 SHADE=0 GOTO 140 REM Init
ialise colour variables
40 IF STRIG(0)=1 THEN GOTO 80 REM Bran
ch if trigger not pressed
50 IF R=1 THEN R=2 GOTO 140 REM select
 next colour register
60 IF R=2 THEN R=4 GOTO 140
70 IF R=4 THEN R=1 GOTO 140
80 S=STICK(0) REM Read joystick in por
t 1
90 IF S=15 THEN GOTO 40 REM Loop back
 if stick centralised
100 IF S=14 THEN IF HUE<15 THEN HUE=HU
E+1 GOTO 140 REM Joystick up
110 IF S=13 THEN IF HUE>0 THEN HUE=HUE
-1 GOTO 140 REM Joystick down
120 IF S=7 THEN IF SHADE<14 THEN SHADE
=SHADE+2 GOTO 140 REM Joystick right
130 IF S=11 THEN IF SHADE>0 THEN SHADE
=SHADE-2 REM Joystick left
140 POSITION 3,10 ? #;COMMAND = SETCOLO
R ;R;",";HUE;",";SHADE;
150 SETCOLOR R,HUE,SHADE REM Change th
e screen colour as ordered
160 FOR W=1 TO 50 NEXT W REM Short del
ay
170 GOTO 40
```

[illegible] demonstrator

Series

◀ From Page 53

Putting it into practice

As an exercise, try designing and writing a program to meet these specifications

- Turn the background brown with a green border and use Control characters to draw a city street plan
- Insert fuel dumps, airfields and shipyards, represented by the letters F (Ascii 70), A (Ascii 65) and S (Ascii 83)
- Use a + character (Ascii 19) to fly around the screen under joystick control, without disturbing the background
- Whenever the joystick trigger is pressed make the sound of a falling bomb. If the cross is covering an A, F or S, add an explosion sound and leave a blank space behind when the cross moves
- Near the bottom of the screen, print the number of bombs dropped and the number of hits achieved, updating this every time the trigger is pressed
- End the game after 20 bombs have been dropped

This will be a pretty complicated program, so don't expect to solve all the problems overnight. Try to get the first three steps working correctly first, using the subroutine from Program I for joystick control – Program II will give you a hint on how to incorporate the trigger feature.

The next two can be added as subroutines later, but the last step is best included as part of the main line code. If you can make it all work and understand its operation, you're well on the way to mastering Basic

- Next month we'll explain what's happening in our demonstration and show how easy it is to produce multi coloured animated displays

ARE YOU MISSING OUT?

You've got lots of questions about your computer but don't know who to ask! We do! You're not sure which software is best for your application! We do! You'd like to keep up to date with new releases and be sure they are a good buy but who's going to tell you? We will! You would love to get to know other Atari enthusiasts, but you don't know how! We do! You want to get some of that Public Domain software you've heard about, but where from? We know! You don't want to feel like you're the only Atari owner in the world, but where can you turn too! Well we can help! Great, but who are you??

We are the largest (and oldest) Atari Computer Owners Club in the U.K. For just £5.00 per year you get help, assistance, hints, tips, friends, pen pals, access to PD software, up to date information, games, utilities, hardware projects, software reviews, programming tutorials, and a glossy club magazine every quarter.

A club magazine as well!! One of those photocopied things that is unreadable eh! Well no, it's professionally produced, just like this magazine you're reading. It's called MONITOR, you may have heard of it? Yes, friends of mine have read it and say it's great! How do I join the club and get my copy of MONITOR? Easy, just send a cheque or postal order for £5.00 to the address below requesting a four issue subscription. Overseas membership is £8.00 (surface) or £12.00 (Airmail)

You won't be disappointed!!

The U.K. Atari Computer Owners Club
P.O. Box 3, Rayleigh, Essex, SS6 8LR

Independent User Group

C. S. Software

IF YOU SEE CHEAPER WE WILL BEAT THE PRICE!!

TITLE	CASS	DISC	TITLE	CASS
Arcade Classics	7.50		3D	6.95
Footballer of the Year	7.95	9.90	Bruce Lee	7.95
Flight Night	7.95	9.95	Bruce Lee	9.95
Pattern Perfection	7.90		Eagles	6.95
Bruce Lee	2.50	12.50	Spiderman	7.95
Zaxxo	7.95	9.50	Dr. Dan	6.95
Tomahawk	7.95	14.95	Bounty Bob	6.95
Spy Hunter	7.50	12.00	Strip Poker	6.95
Ace of Aces	7.95	9.50	Pinpoint	6.95
Solo Flight II	7.50	15.90	Speed Ace	6.95
3D'lit Bruce St		2.95	Panther	1.75
Green Beret	7.95		Henry's House	1.75
Living Daylights	7.90	15.95	Tomahawk	7.5
Ghostbusters	7.50	15.90	Universal Hero	7.5
Winter Olympics	6.95	9.95	Space Shuttle	7.5
Summer Games		9.95	Decathlon	7.5
Bristle	7.50	9.50	Deep Blue	7.5
Montezuma's Revenge	7.95	12.50	Colony	1.75
Silent Service	7.95	15.50	Feud	1.75
Arkanoid II	7.50	11.90	League Challenge	7.5

All software prices House Postage and Packing + VAT (Overseas add £1.00) Please send S.A.E. for full price list. All software normally despatched within 24 hours but Speed allow 7 days Subject to Availability
ATARI VCs AND ST SOFTWARE ALSO SUPPLIED
Please make Cheques and P.O.'s payable to
C. S. SOFTWARE (Dept AU) Unshire Farm, Buckingham Bierl, Whittlebury, Northants NN12 8XN

ATARI REPAIRS

Atari Approved Service Centre

All Atari products repaired, Computers, Printers, Monitors, Disk Drives etc

Atari trained engineers

All work fully guaranteed

Free estimates

AVON MICRO CENTRE
Unit 4 Western Road Industrial Estate,
Stratford upon Avon Warwickshire CV37 0AH
Telephone 0789 292269

£10 LETTER

DEEPER INTO THE DUNGEON

I THINK that I may be in a position to help Mr C V Howarth solve his problem with Alternate Reality The Dungeon that he mentions in the Hints and Tips section of the March 1988 issue of Atari User

Firstly, the item which he needs to use to pass through deaths doors is the portal access card

This will be given to him by Acriminiral in exchange for the staff pieces from the prisoner on level one, King Danjor on level two and the dragon on level three – it requires the bloodstone before it will give up its piece

Secondly, the River Stonz may be crossed at any time after midnight and before the first hour, provided that the boatman is paid with copper

Thirdly, Morgana s tiara should not be given up to the clothes horse on level two By wearing the tiara lost hit points are restored

The clothes horse will settle for a sweater or a cloak provided you have nothing better, otherwise it will take your finest item of clothing – especially if it's magical

Finally, does anyone know the name of the gar goyle on level three? – **Mike Ward, Warley, West Midlands**

Crashing worksheets

AFTER reading the review of the Swift Spreadsheet from Audiogenic in the March 1988 issue of Atari User I thought I'd point out a prob lem that I am having with it

When you are saving and loading worksheets they appear to save accurately and load every cell properly However, problems occur when the worksheet is then worked on further – the program is prone to crashing with odd garbaged mess ages appearing

This bug does not occur all the time but is quite common and very frus trating

The spreadsheet is potentially powerful and easy to use, and offers good value for money when you compare it to the more expensive VisiCalc and SynCalc

I have written to Audio genic but received no reply and I have talked over the phone to Metamorphosis Development – the design ers of the spreadsheet – who were helpful but unable to cure my problem – **W Cherlee, Winch Wen, Swansea**

● Have any of our readers experienced this problem? If you know the cure, please write in.

Getting that hash

I AM very flattered that my letter was chosen for publi cation in the March 1988 issue of Atari User I found your attached comment, however, didn't seem to square with my experiences at the keyboard

I have an 800XL linked to a 1050 disc drive chained to a Panasonic KXP 1081 printer via a graphics interface

If I use the AtariWriter word processor I found, as you say, that the hash sign is printed out as a £ but dis played on screen and again in preview mode as a hash

Using Mini Office II, however, if I key hash – Shift+3 – the pound sign appears on the screen, even if the printer is switched off and disconnected from the micro it is also output in both preview and print modes Finally, your reply to one of the letters in the March issue surprised me

Although the SMM804 is not a commonly advertised printer for the 8 bit Atari, it will work correctly for text if a Centronics type interface is connected – **J E Robinson, Millom, Cumbria**

Keys still available

WHEN I read the mailbag section in the March 1988 issue of Atari User I noticed a letter from someone who is having the same problem as me – broken keys on their 1010 tape recorder

I wrote to Silica Shop – enclosing a postal order for the required amount – but I was most upset when they wrote back to inform me that they had stopped selling replacement 1010 keys

After a dozen or so phone calls I found someone who sells them – A S Wooten & Son, 116 Edleson Road Crewe, CW2 7HD The keys are £1 50 each and £1 50 postage and package for up to four keys is required

Could you please tell me if a tape version of Monopoly is available and where I can get it? – **Bryan Pott, Barnsley, South Yorkshire**

● We've checked with Silica Shop and it still sells the keys They are £1 12 each and £1 50 postage and package must be included

We don t think there is a tape vers on of monopoly

Mini Office II on SpartaDos

I HAVE a 1050 disc drive with a US doubler fitted and

Turn to Page 56 ▶

WIN A TENNER!

EACH month we will award £10 prizes for the most interesting letters sent to us

So now there's more reason than ever to con tribute to our lively mail bag pages

Get your pens out, start writing and you could be one of the winners The address

Mailbag Editor
Atari User
Europa House
Adlington Park
Adlington
Macclesfield SK10 4NP

DOUBLE TROUBLE

I HAVE just typed in the excellent 3D Plotter pro gram from the March 1988 issue of Atari User and I came across what seems a slight error in the listing Line 800 has been duplicated and it re appears on line 790 It should read

```
790 PLOT X(POINT,1)+160,Y(PO
INT,1):DRAWTO MPX,MPY
```

Once this has been altered it runs correctly Thanks for a superb program – it has brought many hours of fun

Has any reader figured out how to dump the 3D image to an Epson or 1029 printer? – **Mark Wilkie, Marske by the Sea**

● Unfortunately as the magazine was put together the listing was scrambled slightly

We are sorry for any inconvenience caused

◀ From Page 55

I was wondering if it is possible to transfer my Mini Office II files to a SpartaDos format

It would be nice to have the high speed load facility on such a super program – **Alexander Mellor Brooke, Cheadle Hulme, Cheshire**

● Mini Office II works very well on nearly all disc operating systems including SpartaDos

MAPS COME IN HANDY

I WOULD like to thank you for the excellent article about Spellbound that appeared in the March 1988 issue of Atari User

Not only was the map very well presented, but the hints and tips were very useful in allowing me to complete this super mini-adventure for the first time

Also in the same issue was the map of Mercenary The Second City Although I have never played this particular graphics adventure I am now thinking about getting it as the map makes it look like a very enjoyable game The reviews section is always a firm favourite of mine and I was overjoyed when you started to use colour pictures again The new layout looks superb as does all the magazine

Thanks for a very interesting and informative read – **Sean Canning, Manchester**

Cartridge connection

I USE an assembler/editor cartridge quite a lot and find that I am having to continually plug it in or out to program in Basic.

I am concerned that the wear and tear on the edge connector will ultimately lead to unreliability

Would it be possible to build a gadget which would mount a cartridge and slt semi-permanently outside the micro? It could then be brought in or out of action by use of a simple switch

Also, a more complex system could be built to a accomodate more than one cartridge and allow them to be switched in or out as required – **R G Bryer, Ashtead, Surrey**

● The subject of this gadget has been looked at before and only a simple circuit is needed to allow a number of cartridges to be mounted together on one cable

The components would make this a rather expensive device, but if enough readers write to us to prove that demand is sufficient we ll reconsider it

More gadgets on the way

IN recent issues of Atari User there haven't been any gadgets by your resident expert Len Golding Has he stopped building them? – **Dave Manning, Reddish Stockport**

● Len has been having a rest recently but he promises to build us some more interesting and inventive gadgets soon

Pascal alternative

I OWN an Atari 800XL and 1050 disc drive Can you please tell me whether or not there is a software package that would enable me to use Prospero Pascal and, if so, how much it is and where I can buy it from? – **J W Brzezinski, Spital Tongues, Newcastle Upon-Tyne**

● Unfortunately, this particular program is not available for the 8 bit Atari At one time Kyan Pascal was easily obtainable but it is now very difficult to get hold of

You could try getting the Action! cartridge-based language Although it s not identical it does offer similar features to Pascal

It is a sort of hybrid Basic/C and is available from several advertisers in *Atari User*

Happy beginner

UNFORTUNATELY I was late in discovering Atari User, but I now have a regular order with my newsagent so I don't miss it

I recently bought the back issue pack of magazines from May 1985 to November 1985 and was absolutely delighted with Mike Bibby's articles for beginners

I'm physically disabled and so started using a computer when I could no longer work Being a novice at computing the series was a great help to me

Please convey my thanks to Mike for explaining things so clearly Also, thanks for a really terrific magazine – **Wilma Smith, Aberdeen**

XMM801 printer problem

I RECENTLY bought an Atari XMM801 printer and it was superb for word processing and listing Basic programs However, a friend lent me Print Shop by Broderbund and I have found it impossible to get it to print out

I have tried all combinations of options to no avail, so could you please tell me what the XMM801 is equivalent to? And is it possible for this program to work on my printer? – **Karen Seger, Stockport, Cheshire**

● Unfortunately, as with all Atari printers, the XMM801 is unique Atari has for some reason designed printers that don t work with commercial software and Print Shop will not work with your printer no matter what preferences you choose on the set up menu

Cartridge-only cable

IS there an effective way of interfacing software like Mini Office II to a printer without an expensive interface unit?

I successfully built and installed the Epson Interface from the April 1987 Gadgets series in Atari User but the software seems to overwrite the driver routine that I install – **P G Lord, Sutton Coldfield, West Midlands**

● Whenever your micro is switched off anything that is in ram s lost When you load most machine code software you must initiate a boot load by switching off your micro and holding down Option when you switch on

This means that the original driver software is lost so, as the article states, the cable will only work with commercial cartridge based software and unfortunately not with disc based software like Mini Office II

Italic on tap

WHILE I was working with Mini Office II on my 800XL I discovered that pressing the inverse video key causes any typing that you do after to be printed out in italic Pressing this key again switches you back to normal print style – **A R Hezzard, Swinden, Wilts**

Dipping into the toolkit

AFTER reading the advert for the Atari User Toolkit I decided to send off for the disc version I'm very pleased with it and I now use it every time I program or type in magazine listings

The renumber utility is very useful and the variable name change feature is an excellent idea. I find the way that it switches itself out when you run a program is great, and it's so easy to install once it has been loaded – just press System Reset – **Philip Marsh, Middlesbrough, Cleveland.**

The catch

I BOUGHT my children an Atari home computer for Christmas and a copy of the January 1988 issue of Atari User I found it an excellent publication, but I didn't understand one of the instructions on a Five Liner program – an unusual character on line 3 of Catch

Can you please help? – **Peter Brown, Harpenden, Hertfordshire**

● The character you are having problems with can be obtained by pressing the inverse character key and then Control+N A full list of these control characters was in the February issue of *Atari User*

Long wait for a drive

WHY on earth did Atari stop producing the 1050 disc drive, especially since the new one isn't even available?

Each month I am allowed out of my straightjacket to read your masterpiece of a magazine, but with dismay I find no mention of the 1050, and no news of the release of the new drive ever graces the pages Please could you tell me what exactly is happening? – **Martin Tiller, Oxford**

● Atari has had some problems with the new drive, but claims it will be available soon The classified section of *Atari User* contains many bargain offers including 1050 disc drives

Epson drive

I OWN an 800XL and 1010 tape deck Recently I was offered an Epson 5 25 floppy disc drive and was told that it was double sided with a one megabyte storage capacity Could you please tell me what interface I would need to get it working on my Atari? – **D E Fogerty, Salisbury, Wiltshire**

● Unfortunately this disc drive will not work easily on your Atari and an interface to make it work would probably cost more than a new Atari drive

The truth about TELEX

How much does it cost to go on Telex?

You could go the conventional way and buy a dedicated Telex machine The cheapest will cost you £1,604 (the Whisper) the dearest £2,892 (the Cheetah) You will also need a separate telephone line costing £101 to install plus £404 a year rental That s a total outlay over the first year of a minimum of £2 109 (All prices include VAT)

[illegible] would do what [illegible] more Atari users are doing use your micro to double as a

How do I turn my Atari into a Telex machine?

All you need is a modem and appropriate communications software (see the advertisements in this issue) a telephone and a subscription to *MicroLink*

Telex is just one of a growing number of services available to Atari users on *MicroLink* With MicroLink you can also read the news as it happens go teleshopping create your own closed user group send telemessages and electronic mail right round the world download free telesoftware programs directly into your micro and much more

But why use Telex?

Because it s a standard means of instant communication between businesses. Today there are 150 000 Telex machines in use in Britain – and more than 2 million worldwide It s used to dramatically speed up business communications – just as quick as using the phone but far more efficient, because you have a hard copy of every conversation for your records.

But there s a big bonus you get when you use *MicroLink* for Telex that the conventional way doesn t offer

With *MicroLink* you don t HAVE to be in your office to send or receive Telex messages You can just as easily use your computer at home (or even a portable) So now you can check whether there are any Telex messages waiting for you – anywhere anytime How that for your business efficiency?

How to join
See Page 4


Time and magik

The trilogy



Interactive fiction from Level 9







Three adventures in one. Level 9's most acclaimed adventure series – Lords of Time, Red Moon and The Price of Magik – comes together in one package. Each has been enhanced and enlarged with more text than ever before – Beyond mind-expanding words, magik and mystery round every corner. There's a powerful new parser, and more than seventy location illustrations that help to dramatically heighten the atmosphere.

What the press have said:

LORDS OF TIME: "Absolutely the best ever Level 9 adventure" – Computing with the Amstrad

RED MOON: "Best Graphic Adventure is Best Adventure of the Year" – Zzap 64 Gold Medal Award, CRASH Smash, Amstrad Computer User

THE PRICE OF MAGIK: "Another award winning adventure ... and just right" – Computer and Video Games, Adventure Section

MANDARIN SOFTWARE

Europa House, Adlington Park, Adlington, Macclesfield SK10 4NP.

£14.95

£19.95



The Tynesoft team with head of development David Croft (bottom right)

The Winter of content . . .

NEIL FAWCETT meets the programming team behind Olympiad '88

ONE of the best known software houses producing games for the 8 bit Atari is Tynesoft. Based in Blaydon, Tyne & Wear, it is constantly bringing out quality new software to add to its already impressive range.

So it was with eager anticipation that I went to have a chat with David Croft, Tynesoft's head of software development.

The main topic of conversation was the development of its new sports simulation. Said Croft, "We were determined Winter Olympiad '88 would surpass all other sports simulations in terms of realism, playability and visual presentation." He said this was Tynesoft's most ambitious project to date, with versions being produced across as many computer formats as possible.

To make this possible all other in-house work was halted and programmers, graphic artists and freelance people alike got together to decide the game's format. The first step towards creating it was to spend lots of time watching videos of winter sports and deciding which events would appear. They eventually settled for the downhill, bob sleigh, ski jump, slalom and biathlon.

The actual programming fell on the heads of Brian Jobling (downhill), Chris Murray (bob sleigh), Mike Hedley (ski jump, slalom and biathlon) and Philip Scott was their graphics artist. It took the team three months to finish the program.

While all this was going on, managing director Colin Courtney was busy negotiating permission to use the BBC Television theme music from Ski Sunday. He also managed to get programme presenter David Vine to write an introduction to the 1988 Winter Olympics to be included in the final packaging.

Tynesoft is very optimistic about the game's future. It has already sold the rights to Mindscape, an American company that will produce it under the name Winter Sports. So just how good is the game? You can find out by reading the full review by Bob Chappell on Page 26.

Now let's take a look at some of Tynesoft's more established games and their authors. Brian Jobling, who has now moved on to his own company, Zappelin, wrote many of the company's successful games on the 8 bit Atari. His first for Tynesoft – another sports simulation – was Winter Olympics, which sold nearly 4 000 copies in its first month of sales.

Phantom was another of Tynesoft's success stories. Written originally for the BBC Micro, it was converted for the Atari by Brian with music by Ian Waugh – a widely recognised micro music expert. It's an excellent game with everything you need – good sound, stunning graphics and, above all, addictiveness.

One of the best programs to come out of the company is Mirax Force by Chris Murray, a very talented writer with many games under his belt. He wrote this one as a freelance programmer but Tynesoft now has him under contract. Mirax Force is a wonderful sideways scrolling shoot-em-up with digitised speech which really has you wanting just one more go.

As well as producing very good software Tynesoft wraps its products in superb packaging. This is probably because it has facilities to do its own printing and make all the cassette and disc inlays.

The future is looking very rosey for Tynesoft with the release of Winter Olympiad '88, Super Soccer – also reviewed in this issue – and the Microvalue III pack. These Geordie lads definitely seem to know what they are about.



A scene from Phantom

Two discs crammed with the most popular programs from your favourite magazine!

These two exciting compilations bring together some of the very best listings from the pages of *Atari User*.

Whether you like games or prefer more serious pursuits there's something here for you – and you can also learn a great deal from examining and modifying the Basic listings.

Ten of the Best Games

Chopper Rescue – Take command of a helicopter to rescue lost soldiers
Des Bells – Rescue Esmerelda by negotiating the dangerous obstacles
Spacemaze – Fly your spacecraft through the deadly caverns below the lunar surface
Mazemunch – Guide your munch monster around the maze avoiding its deadly inhabitants
Moneybags – Gobble up all the money but beware of the sinister spiders
Frank the Fruit Fiend – Help Frank eat his favourite food in this platform game
Duck Dash – Dash round and chase up all the ducks before the storm hits the farm
Frogjump – Direct the frog across the busy road in this classic arcade game
Doctor Boris – Help the doctor build the new hospital but watch out for mad Norman

PLUS the latest Get It Right! program to help you correctly type in listings in Atari User

Bounder was the game you liked best of all. Now, in BOUNDER PLUS, we've made it even better – with SIX exciting new screens to test your dexterity. Bounce up and down on the springy trampoline to hit the many targets while avoiding the balloons. (XL and XE only.)

Ten of the Best Utilities

DiscError – Make sense of those Basic error numbers by turning them into words
DiscEdit – Modify those hidden sectors with this superb utility
DiscView – Take a look at all the useful information stored on your discs
Dump 15 – Make prints of your favourite pictures on your Epson or Atari 1029 printer
ArtShow – Load your AtariArtist pictures and create your own fantastic artshow
AutoDirectory – Gain instant access to disc directories without going to Dos
DiscRenumber – Renumber your Basic listings with this useful Autoboot program
FullPrint – Print out any resident character set in full to an Epson printer
DataEditor – Manipulate data with ease whether on disc cassette or in memory
80 Column – Generate a very impressive 80 column text display on your screen

PLUS the latest Get It Right! program to help you correctly type in listings in Atari User



ONLY £4.95 each

. . . or just £1.95 each when you take out a new subscription to Atari User – or if you renew your existing subscription.

TO ORDER PLEASE USE THE FORM ON PAGE 61

AT11/87

Protect your Atari .



with this luxury dust cover for your Atari XE or XL. It's made of clear, water-resistant vinyl and bound with strong cotton

Only £3.95

. . . and your Atari Users

A year's supply of Atari User can be kept in this handsome chocolate brown binder



Only £4.95

Secure storage for your discs



The ideal storage medium for your 5.25in discs

The luxury padded PVC boxes are strongly made to protect your valuable discs and can be packed flat when not in use

Holds up to 60 5.25in discs

£4.95

ORDER FORM

★ Special price if accompanied by subscription or renewal

Valid to 31/6/88

All prices include postage, packing and VAT
Overseas orders despatched by Airmail

(✓) £ p

Annual subscription

	NEW		RENEWAL	
UK £15	7001		7002	
Europe (incl Eire) £18	7003		7701	
Overseas (Airmail) £33	7004		7703	

Commence with _____ issue

FREE with subscription (tick one box only)

Atari ExecuCard	7026	
Starquake disc	7024	
Starquake tape	7025	

Back Issues

£1.50 UK, £2.00 Europe & Eire, £2.95 Overseas

January 1987	7408		
February 1987	7410		
March 1987	7411		
April 1987	7412		
May 1987	7413		
June 1987	7414		
July 1987	7415		
August 1987	7416		
September 1987	7417		
October 1987	7418		
November 1987	7419		
December 1987	7420		
January 1988	7421		
February 1988	7422		
March 1988	7423		
April 1988	7424		

Ten of the Best (see page 95)

Games disc	★ £14.95	£4.95	7013/7014
Utilities disc	★ £21.95	£4.95	7017/7018

Guild of Thieves

Atari 800/130 disc ★ £19.95 £14.95 7019/7020

The Pawn

Atari 800/130 disc ★ £19.95 £14.95 7033/7034

Atari Data Bank (see page 36) NEW

★ £19.99 £15.95 7027/7028

Atari ExecuCard (see page 26) NEW

£4.99 7026

Starquake (see page 32) NEW

Tape	£4.95	7030
Disc	£5.95	7047

Atari User Toolkit (see page 38) NEW

Tape	£5.95	7021
Disc	£7.95	7022

Add £1 for Europe inc Eire/Overseas

Mini Office II (see page 3)

Disc 400/800/XL/XE (48k) £19.95 7050

Add £2 for Europe inc Eire/£3 for Overseas

Readers in Europe (inc Eire) add £2. Overseas add £4 per item unless otherwise indicated

➡ ➡ ➡ ➡ ➡ TOTAL _____

Disc storage box

Holds up to 80 5.25" discs £4.95 7029

Dust cover

130XE	£3.95	7031	
800XL	£3.95	7050	

Add £1 for Europe inc Eire/Overseas

Atari User binder

£4.95 7029

Add £2 for Europe inc Eire/£7 Overseas

Send to Database Publications FREEPOST, Europa House, Adlington Park, Adlington, Macclesfield, Cheshire SK10 4NP
(No stamp needed if posted in UK) *Please allow 28 days for delivery*

Order at any time of the day or night

Telephone Orders 0625 879920

Fax Orders	Orders by Prestel	MicroLink/Telecom Gold
0625 879966	Key *89, then 614568383	72:MAG001

Don't forget to give your name, address and credit card number

ENQUIRIES ONLY 0625 879940 8am-5pm

Payment: please indicate method (✓)

Expiry Date ___/___

Access/Mastercard/Eurocard/Barclaycard/Visa

No

Cheque/Eurocheque made payable to Database Publications Ltd.

Name _____ Signed _____

Address _____

_____ Post Code _____

Tel _____ ATS

XL/XE MOUSE

AN ST MOUSE FOR YOUR XL/XE

Includes Mouse Art Package
Fast picture loader
Atari Artist/GAD translator
2 demo programs show the use of the mouse in your own software Supplied with all operating information

All for **£29.95 Post free**

Please state cassette/disk

LETTER 80

80-COLUMN WP ON SCREEN

This full feature letter/word processor supports standard Atari keyboard editing PLUS wordwrap insert & justification Address data and ref erase also control search/ mailshot feature Mouse/joystick operation with pull-down menus

Buy both for only £39.95 post free

Disk only **£24.95 Post free**

COD service available for £1.50

GLOBAL COMPUTER SERVICES

108 Navigation Road, NORTHWICH, Cheshire CW8 1BE (0606) 782413

OPENING OFFER AT

THE TAPE CENTRE

ATARI GAMES ALL AT £5.95

Kingsize (56 games)
A Day at the Races
Warriors of Ras
Smash Hits 2
Smash Hits 7
Raven Seuver
Montezumas Revenge
Spy v Spy
Spy v Spy II
Superman
Bruce Lee
Raiders of the Lost Ark
Zaxxo
Jet Set Willy
Domain of the Undead
Demon Game
Hacks
Trailblazer

ATARI 2600 GAMES

ALL AT £7.95

Enduro
Freeway
Ghost Busters
Pitfall
River Raid
Space Shuttle
Tennis
Phaser Tank

ALL AT £6.95

Dodgems Circus
Boing
Wizard of War
Smurfs
Venture
Solar Fox
Muse Trap
Gerl Donkey Kong

Please make Cheques/Postal Orders payable to The Tape Centre
Overseas add £1 50
Full price list please send S.A.E.

NOTE NEW ADDRESS

THE TAPE CENTRE
29 Northwood Drive Shepshed Loughborough Leics. LE12 9BL

Zeppelin Games

£2.99



No 1 In Charts

RAVE REVIEWS ARE NO GOOD IF YOU CANNOT GET THE GAMES

HERE'S HOW!

£2.99



See the review in this issue

PRIORITY ORDER FORM

Please rush by return of post

Speed Ace 48K @ £2 99 Inc P&P ☐
Zybex XL/XE @ £2 99 Inc P&P ☐
Total

Name & Address

Make cheques + P O payable to ZEPPELIN GAMES LTD
Send to Zeppelin Games Ltd 28 Osborne Road Jesmond Newcastle NE2 2AJ England

ADVERTISERS' INDEX

Atari	30 31
Atari World	62
Avon Micro Centre	64
8 Bytes Computer Shop	47
Capna Marketing	47
Centec	14
Chips	42
Communication & Media	40
Compumart	63
C S Software	54
Database Software	8
Digicomm	42
Eagle Business Services	47
Fidget Computerware	47
Glasgow Computer Centre	47
Global Computer Services	62
Ladbroke Computers	40
Mandarin Software	2,58
Maidmore Distribution	42
MicroLink	4
Miles Better Software	12
Monitor	54
Page 6	14
Pulsar Software	62
Silica Shop	7
Softscan	20
Software Express	46
Stortsoft	24
Superior Software	17
The Tape Centre	62
Tynesoft	64
Zeppelin Games	62

FIG FORTH



Fig Forth is a fast and versatile language for the 8 bit Atari with a minimum of 48k memory
Fig Forth comes with some useful sample programs
Fig Forth uses an ST Mouse with no hardware modifications.

Fig Forth is £14.95 inc VAT

Send a SAE for a full price list of public domain software

PULSAR SOFTWARE LTD

Pulsar Software Ltd
4 Church Hill Road
East Barnet, Herts. EN4 8TB
Tel. 01-441 8709

ATARI IN MANCHESTER

For the best selection of Software for your Atari Computer or Video Game Console visit

ATARI WORLD

15 Fennel Street, Manchester 4
(Opposite Victoria Station/Millgate Car Park)

Tel: 061-834 4941. Open: Mon.-Fri. 10-6 Sat. 10-5.30

Mail Order with pleasure Stamp for catalogue

Cut the hassle

Cut the coupon!

Compumart

A GREAT DEAL MORE FOR A GOOD DEAL LESS!

DEPARTMENT ATU
JUBILEE DRIVE
LOUGHBOROUGH
LEICS LE11 0XS
TEL 0509 610444
FAX 0509 610235

Send Now for your *Free* copy of the Compumart ST Information Pack and discover a full range of ST Accessories at Super Low Prices

For IMMEDIATE RESPONSE simply send this coupon to
COMPUMART FREEPOST LOUGHBOROUGH LEICS LE11 0BR

Please rush me

A FREE Compumart ST Information Pack | PLEASE TICK |

ATU

Name Address

Postcode

Date

EXPERIENCE THE REAL THING!

WIN A WINTER OLYMPIC HOLIDAY WORTH MORE THAN £2000




WINTER OLYMPIAD'88

Winter Olympiad'88 is undoubtedly the best winter sports simulation ever made. It features the classic winter Olympic events: Ski Slalom, Giant Slalom, Two-man Bob, Ski-Jump, Biathalon and Speed Skating. These have been depicted in a way never seen on any home computer before. The result is a phenomenally realistic and addictive game.

Available on the following formats:

- COMMODORE/SELECTRON, ATARI £9.95
- SPECTRUM, AMSTRAD CPC £7.95
- DISK - BBC £14.95
- MASTER COMPACT £14.95
- ATARI 8 BIT £14.95
- ST £19.95 • AMIGA £19.95
- IBM £19.95









TYNESOFT

ADDISON INDUSTRIAL ESTATE, BLAYDON, TYNE & WEAR, NE21 4TE. TEL: (0632) 456900